Civil Engineering and Development Department

Trunk Road T2 Monthly Environmental Monitoring and Audit Report (under EP-458/2013/C)

August 2025 (Version 1.0)

Approved By

(Environmental Team Leader:

Mr. KS Lee)

REMARKS:

The information supplied and contained within this report is, to the best of our knowledge, correct at the time of printing.

CINOTECH accepts no responsibility for changes made to this report by third parties

CINOTECH CONSULTANTS LTD

Room 1710, Technology Park, 18 On Lai Street, Shatin, NT, Hong Kong Tel: (852) 2151 2083 Fax: (852) 3107 1388

Email: info@cinotech.com.hk



Ref.: CEDKTDT2EM00_0_0803L.25

11 September 2025

By Post and Email

Hyder-Meinhardt Joint Venture 23/F, Two Harbour Square

180 Wai Yip Street, Kwun Tong

Kowloon, Hong Kong

Attention: Mr. Edwin Ching

Dear Mr. Ching,

Re: Agreement No. EDO 01/2019

Independent Environmental Checker for

Contract No. ED/2018/04 - Trunk Road T2 and Infrastructure Works for

Developments at the Former South Apron

Monthly EM&A Report (August 2025) for EP-458/2013/C

Reference is made to the Environmental Team's submission of the Monthly EM&A Report for August 2025 (Version 1.0) certified by the ET Leader and provided to us via email on 11 September 2025. We are pleased to inform you that we have no adverse comments on the captioned submission. We write to verify the captioned submission in accordance with Condition 4.4 of EP-458/2013/C.

Thank you for your attention. Please do not hesitate to contact the undersigned should you have any queries.

Yours sincerely, For and on behalf of Ramboll Hong Kong Limited

Y H Hui

Independent Environmental Checker

c.c. CEDD

Attn.: Mr. Tommy Wong

By Fax: 2739 0076

BTP

Attn.: Mr. Ivan Chau

By Email

Cinotech

Attn.: Mr. K. S. Lee

By Fax: 3107 1388

TABLE OF CONTENTS

		Page
EX	ECUTIVE SUMMARY	1
	Introduction	1 2 5 6
1.	INTRODUCTION	7
	Background Purpose of the Report Project Organizations Construction Activities undertaken during the Reporting Month Summary of EM&A Requirements Status of Environmental Licensing and Permitting	8 9 9
2.	AIR QUALITY	11
	Monitoring Requirement. Monitoring Locations. Monitoring Parameters and Frequency. Monitoring Equipment. Monitoring Methodology. Results and Observations Comparison of EM&A Result with EIA Prediction	11 12 12 12
3.	NOISE	18
	Monitoring Requirements Monitoring Locations Monitoring Parameters, Frequency and Duration Monitoring Equipment Monitoring Methodology and QA/QC Procedure Maintenance and Calibration Results and Observations Comparison of EM&A Result with EIA Prediction	
4.	WATER QUALITY	
	Monitoring Requirement	
5.	WASTE MANGEMENT	22
6.	ECOLOGY	23
7.	FISHERIES	23
8.	CULTURAL HERITAGE	23
9	LANDSCAPE AND VISUAL IMPACT	24

10.	LAND	FILL GAS MONITORING	24
	Monito	oring Requirement	24
11.		RD TO LIFE	
12.	ENVIF	RONEMNTAL AUDIT	25
	Site A	udits	25
		nentation Status of Environmental Mitigation Measures	
	Impler	nentation Status of Event and Action Plans	26
13.	ENVIE	RONMENTAL NON-COMFORMANCE	26
		ary of Complaint, Warning, Notification of any Summons and Successful Prosecu	
14.	FUTU	RE KEY ISSUES	26
	Monito	oring Schedule	27
15.		LUSION AND RECOMMENDATION	
13.			
		isions	
	Recom	nmendations	28
LIS	T OF T	ABLES	
Tab	le I	Summary of Key Construction Work in the Reporting Month	
Tab		Summary of Key Mitigation Measures Implemented in the Reporting Month	
Tab	le III	Non-compliance (exceedance) Record for the Project in the Reporting Month	
Tab	le IV	Monthly Complaints, Notifications of Summons and Successful Prosecutions	s in the
		Reporting Month	
	le V	Summary of Complaints Details in Reporting Month	
	le VI	Summary Table for Site Activities in the next Reporting Period	
	le 1.1	Key Project Contacts	
	le 1.2	Summary of Key Construction Work in the Reporting Month	
	le 1.3	Summary of Environmental License and Permit	
	le 2.1	Air Quality Monitoring Locations	
	le 2.2	Frequency and Parameters of Air Quality Monitoring	
	le 2.3	Air Quality Monitoring Equipment	
	le 2.4	Major Dust Source during Air Quality Monitoring	
	le 2.5	Comparison of 1-hr TSP Monitoring Data with Predictions in EIA Report	
	le 2.6 le 3.1	Comparison of 24-hr TSP Monitoring Data with Predictions in EIA Report Noise Monitoring Stations	
	le 3.1	Frequency and Parameters of Noise Monitoring	
	le 3.2	Noise Monitoring Equipment	
	le 3.4	Other Noise Source Identified during Noise Monitoring	
	le 3.4	Baseline Noise Level and Noise Limit Level for Monitoring Stations	
	le 3.5	Maximum Predicted Mitigated Construction Noise Levels in EIA Report	
	le 10.1	Landfill Gas Monitoring Equipment (not used)	
	le 10.1	Observations and Recommendations of Site Audit	
	le 14.1	Site Activities and the Key Environmental Issues in the next Reporting Period	
- 40	111	200 100 100 100 100 100 100 100 100 100	

LIST OF FIGURES

Figure 1 Site Layout Plan

Figure 1.2 Organizational Structure for Environmental Management

Figure 2 Locations of Air Quality and Construction Noise Monitoring Stations

LIST OF APPENDICES

Appendix A Action and Limit Levels

Appendix B Copies of Calibration Certificates

Appendix C Weather Information

Appendix D Environmental Monitoring Schedules

Appendix E 1-hour TSP Monitoring Results and Graphical Presentations
Appendix F 24-hour TSP Monitoring Results and Graphical Presentations

Appendix G Noise Monitoring Results and Graphical Presentations

Appendix H Waste Generation in the Reporting Month

Appendix I Site Audit Summary

Appendix J Environmental Mitigation Implementation Schedule (EMIS) Appendix K Record of Landfill Gas Monitoring by Contractor (not used)

Appendix L Event and Action Plans

Appendix M Summaries of Environmental Complaint, Warning, Summon and Notification of

Successful Prosecution

Appendix N Summary of Exceedance

Appendix O Tentative Construction Programme

EXECUTIVE SUMMARY

Introduction

1. This is the 64th Environmental Monitoring and Audit (EM&A) Report prepared by the Environmental Team (ET), Cinotech Consultants Ltd., for Contract No. ED/2018/04 "Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron", Contract No. ED/2020/03 "Trunk Road T2 - Traffic Control And Surveillance System (TCSS) and Associated Works" and Contract No. NE/2015/01 "Tseung Kwan O – Lam Tin Tunnel–Main Tunnel and Associated Works". This report summarized the monitoring results and audits findings of the EM&A programme under the issued Environmental Permit (EP) No. EP-458/2013/C and in accordance with the EM&A Manual (AEIAR-173/2013) during the reporting month of August 2025.

Summary of Main Works Undertaken and Key Measures Implemented

2. The main works undertaken during the reporting period are as follows:

Table I Summary of Key Construction Work in the Reporting Month

Contract No.	Contract Title	Site Activities
ED/2018/04	Trunk Road T2 and	East Bound – Tunnel excavation
	Infrastructure Works for	• EVB – ABWF
	Developments at South	• EVB – E&M works
	Apron	
ED/2020/03	Trunk Road T2 - Traffic	
	Control And Surveillance	• EVB – Installation of TCSS Cable
	System (TCSS) and	Containment
	Associated Works	
NE/2015/01	Tseung Kwan O – Lam Tin	
	Tunnel-Main Tunnel and	Soft Landscape
	Associated Works	

3. Implementation of the key mitigation measures during the reporting period are as follows:

Table II Summary of Key Mitigation Measures Implemented in the Reporting Month

Contract No. and Project Title	Key Mitigation Measures Implemented		
ED/2018/04 - Trunk Road T2 and Infrastructure Works for Developments at South Apron	 Construction Noise Construction activities were scheduled to minimize noise nuisance to the nearby sensitive receiver. Use of Quality Powered Mechanical Equipment (QPME) on site. Erected the noise barrier on site. Air Quality		

	 Regularly watering on site to avoid dust generation.
	Landscape and Visual
	• Tree protection zones were fenced off to protect the existing trees on site.
	Waste Management
	 Avoid accumulation of construction waste and general refuse.
ED/2020/03 - Trunk Road T2 -	
Traffic Control And	Waste Management
Surveillance System (TCSS) and	 Avoid accumulation of construction waste and general refuse.
Associated Works	
NE/2015/01 - Tseung Kwan O- Lam Tin Tunnel- Main Tunnel and Associated Works	 Construction Noise Construction activities were scheduled to minimize noise nuisance to the nearby sensitive receiver. Use of Quality Powered Mechanical Equipment (QPME) on site. Erected the noise barrier on site.
	Air Quality
	 Regularly watering on site to avoid dust generation.
	Waste Management
	 Avoid accumulation of construction waste and general refuse.

Environmental Monitoring Works

- 4. Environmental monitoring for the Project was performed in accordance with the EM&A Manual and the monitoring results were checked and reviewed. Site Inspections/Audits were conducted once per week. The implementation of the environmental mitigation measures, Event Action Plans and environmental complaint handling procedures were also checked.
- 5. Summary of the non-compliance (exceedance) in the reporting month for the Project is tabulated in **Table I**.

Table III Non-compliance (exceedance) Record for the Project in the Reporting Month

Environmental Monitoring		-compliance edance)	No. of Non-compliance (Exceedance) due to Construction Activities of this Project		Action Taken
	Action Level	Limit Level	Action Level	Limit Level	
Air Quality	0	0	0	0	N/A
Noise	0	0	0	0	N/A
Marine Water Quality	N/A	N/A	N/A	N/A	N/A
Groundwater Level Monitoring	N/A	N/A	N/A	N/A	N/A

Monthly EM&A Report - August 2025

(Piezometer Monitoring)					
Ecological	N/A	N/A	N/A	N/A	N/A
Cultural Heritage	N/A	N/A	N/A	N/A	N/A
Landfill Gas	N/A (1)	N/A	N/A (1)	N/A	N/A

Note: (1): No Action Level for Landfill Gas Monitoring.

Air Quality Monitoring

- 6. No Action/Limit Level exceedance for 1-hour TSP monitoring was recorded.
- 7. No Action Level exceedance and no Limit Level exceedance was recorded for 24-hour TSP monitoring in the reporting month.

Construction Noise Monitoring

- 8. No Action Level exceedance was recorded due to documented complaint in the reporting month. The Summary of Documented Complaints in the Reporting Month is tabulated in **Table IV**.
- 9. No Limit Level exceedance for day time construction noise monitoring were recorded in the reporting month. Detail shall refer to **Appendix N**.

Water Quality Monitoring

- 10. Groundwater quality monitoring had been suspended since October 2019 upon the agreement by EPD. Further details should be founded at **Section 4.1**.
- 11. No marine water quality monitoring is required as no marine works will be conducted at the Cha Kwo Ling and Lam Tin areas for this project.
- 12. As the construction activity is approximately 120m away from the piezometer gate, no piezometer monitoring is required.

Waste Management

13. Wastes generated from this Project include inert construction and demolition (C&D) materials, and non-inert C&D materials. Details of waste management data is presented in **Appendix H**.

Ecological Monitoring

14. No coral monitoring is required as no marine works will be conducted at the Cha Kwo Ling and Lam Tin areas for this project.

Fisheries Impact Monitoring

15. No specific fisheries monitoring programme is required during the construction phase.

Monitoring on Cultural Heritage

16. As the construction works of Cha Kwo Ling Tunnel from the end of Trunk Road T2 to the TKOLTT at the Eastern Ventilation Building are located more than 100m away from the Cha Kwo Ling Tin Hau temple, no monitoring on cultural heritage is required.

Landscape and Visual Monitoring and Audit

17. The implementation of landscape and visual mitigation measures was checked by a registered landscape architect. Recommended follow-up actions have been discharged by the Contractor. Details of the audit findings and implementation status are presented in **Section 12**.

Landfill Gas Monitoring

18. Monitoring of landfill gases was commenced in December 2016. Since no excavation activity for this Project was carried out within the Sai Tso Wan Landfill Consultation Zone in the reporting month, no landfill gas monitoring is required

Hazard to Life Monitoring

19. No environmental monitoring and audit are required as no hazard assessment was conducted.

Environmental Site Inspection

20. Joint weekly site inspections were conducted by representatives of the Contractor, Engineer and Environmental Team. Details of the audit findings and implementation status are presented in **Section 12**.

Key Information in the Reporting Month

21. Summary of key information in the reporting month is tabulated in **Table II**.

Table IV Summary of Complaints, Notifications of Summons and Successful Prosecutions in the Reporting Month

1100ccutions in the Itepoteng Worth							
Event	Event Details		Action Taken	Status			
Event	Number	Nature	Action Taken	Status			
Complaints Received	0		N/A	N/A			
Notifications of any summons & prosecutions received	0		N/A	N/A			

22. Summary of complaints received in the reporting month is tabulated in **Table III.**

Table V Summary of Complaints Details in Reporting Month

Complaint Type	Investigation Findings	Follow-up Action / Mitigation Measure	

Reporting Changes

23. For the project "Tseung Kwan O – Lam Tin Tunnel and Associated Works" (TKO-LTT) under EP-458/2013/C, all works contracts except Contract No. NE/2015/01 has been terminated on 17 July 2025 after the approval by EPD. As Contract No. NE/2015/01 (under TKO-LTT) and Contract No. ED/2018/04 & ED/2020/03 (under Trunk Road T2) falls under the same EP-458/2013/C, the reporting of the remaining EM&A works for Contract No. NE/2015/01 (Lam Tin portion of TKO-LTT) will be subsumed into the EM&A reporting for the T2 project and presented as a single combined report starting from August 2025.

Future Key Issues

24. The key works or activities will be anticipated in the next reporting period are as follows:

Table VI Summary Table for Site Activities in the next Reporting Period

Table VI Summary Table for Site Activities in the next Reporting Period					
Contract No. and Project Title	Site Activities (September 2025)	Key Environmental Issues			
ED/2018/04 - Trunk Road T2 and Infrastructure Works for Developments at South Apron	 EVB – ABWF EVB – E&M works East Bound – Tunnel excavation 	(A) / (B) / (C) / (D) / (E)			
ED/2020/03 - Trunk Road T2 - Traffic Control And Surveillance System (TCSS) and Associated Works	• TCSS installation- CKR Gantry, WVB, T2 Gantry, Tunnel & Service Gallery, TKO-LTI, EVB	(E)			
NE/2015/01 - Tseung Kwan O-Lam Tin Tunnel-Main Tunnel and Associated Works	Stage 1 Commissioning Outstanding Works	(A)/(C)/(E)			

Notes:

- (A) Dust generation from haul road, stockpile of dusty materials, exposed site area, excavation works;
- (B) Noisy construction activity such as breaking and drilling activities;
- (C) Runoff from exposed slope or site area;
- (D) Wastewater and runoff discharge from site; and
- (E) Accumulation of construction waste or general refuse.

1. INTRODUCTION

Background

- 1.1 In 2009, Civil Engineering and Development Department (CEDD) commissioned a Kai Tak Development (KTD) Trunk Road T2 and Infrastructure at South Apron Investigation. The assignment covers the provision of the Trunk Road T2 and its connections with the Central Kowloon Route (CKR) at the north apron area and the Tseung Kwan O Lam Tin Tunnel (TKOLTT) to the south in the Cha Kwo Ling area.
- 1.2 The Trunk Road T2 Project is one of the designated Projects under Schedule 2 of the EIAO proposed in the KTD. CEDD submitted the Project Profile (No. PP-379/2009) on 24 March 2009 for application for an EIA study brief for the Trunk Road T2 Project under the EIAO. Accordingly, an EIA Study Brief (ESB-203/2009) for the Trunk Road T2 Project was issued on 30 April 2009. The Environmental Impact Assessment (EIA) Report for the Trunk Road T2 Project was approved under the Environmental Impact Assessment Ordinance (EIAO) on 19 September 2013. The corresponding Environmental Permit (EP) was issued on 19 September 2013 (EP no.: EP-451/2013).
- 1.3 The Contract No. ED/2018/04 is the main contract of Trunk Road T2 ("T2 Main Works") which comprises mainly the design and construction of a dual two-lane trunk road of approximately 3.0km long with about 2.7km of the trunk road in form of tunnel; ventilation and administration buildings, environmental protection and mitigation works and etc. Moreover, the Contract No. ED/2020/03 is the other contract under Truck Road T2 Project which comprises mainly design and construction of the TCSS for this Project. The EM&A programme under the Contract ED/2018/04 and ED/2020/03 are governed by the two EPs (EP-451/2013 and EP-458/2013/C) and two EM&A Manuals (AEIAR-174/2013 and AEIAR-173/2013). The work areas of the T2 Main Works are shown in **Figure 1** and the works to be executed under these Contracts and corresponding EPs are summarized as follows:

Environmental Permit	Works Description
EP-451/2013 – Trunk Road T2	<u>ED/2018/04</u>
	• Construction of highway and sub-sea tunnel connecting between Central Kowloon Route and Cha Kwo Ling Tunnel
	Western & Eastern Ventilation Buildings
	ED/2020/03
	Design and construction of TCSS for Trunk Road T2
EP-458/2013/C – Tseung Kwan O –	<u>ED/2018/04</u>
Lam Tin Tunnel (TKOLTT) and	Construction of Cha Kwo Ling Tunnel from the end of Trunk Road
Associated Works	T2 to the TKOLTT at the Eastern Ventilation Building
	ED/2020/03
	 Design and construction of TCSS for Trunk Road T2

Monitoring Works in Lam Tin under EP-458/2013/C

- 1.4 Under Agreement No. CE 59/2015 (EP) Tseung Kwan O Lam Tin Tunnel (TKOLLT) and Associated Works, the baseline monitoring works in Lam Tin under the EM&A Manual (AEIAR-173/2013) were conducted by the Environmental Team (ET) for the Agreement No. CE 59/2015 (EP) at the approved monitoring locations, namely AM1, AM2, AM3, AM4, AM4 (A) CM1, CM2, CM3, CM4 and CM5. Impact monitoring within the Lam Tin area shall be conducted by the ET of Contract No. ED/2018/04 upon cessation of Agreement No. CE 59/2015 (EP). The data obtained from the impact monitoring works completed by the ET of Agreement No. CE 59/2015 (EP) will be adopted in this report.
- 1.5 Cinotech Consultants Ltd. was designated as the Environmental Team (ET) to undertake the EM&A works for "Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron" (hereinafter called the "Project").
- 1.6 For the project "Tseung Kwan O Lam Tin Tunnel and Associated Works" (TKO-LTT) under EP-458/2013/C, all works contracts except Contract No. NE/2015/01 has been terminated on 17 July 2025 after the approval by EPD. As Contract No. NE/2015/01 (under TKO-LTT) and Contract No. ED/2018/04 & ED/2020/03 (under Trunk Road T2) falls under the same EP-458/2013/C, the reporting of the remaining EM&A works for Contract No. NE/2015/01 (Lam Tin portion of TKO-LTT) will be subsumed into the EM&A reporting for the T2 project and presented as a single combined report starting from August 2025.

Purpose of the Report

1.7 This is the 64th Monthly EM&A Report which summarises the impact monitoring results and audit findings for the EM&A programme during the reporting period in August 2025.

Project Organizations

- 1.8 Different Parties with different levels of involvement in the Project organization include:
 - Permit Holder Civil Engineering and Development Department (CEDD)
 - Supervisor Representative Hyder-Meinhardt Joint Venture (HMJV)
 - Environmental Team (ET) Cinotech Consultants Limited (Cinotech)
 - Independent Environmental Checker (IEC) Ramboll Hong Kong Limited (Ramboll)
 - Contractor Bouygues Travaux Publics (BTP) (For ED/2018/04), GTECH Services (Hong Kong) Limited (For ED/2020/03) and Leighton-China State Joint Venture (LCSJV) (For NE/2015/01)
- 1.9 The key contacts of the Project are shown in **Table 1.1**.

Table 1.1 Key Project Contacts

Party	Party Role Contact		Phone No.	
CEDD	Permit Holder	Mr. Wong Chi Wai, Tommy	3842 7111	
HMJV	Supervisor Representative	Ms. Hazel Tang	2149 8524	
Cinotech	Environmental Team	Mr. KS Lee (ETL)	2151 2091	

		Ms. Karina Chan	2157 3880
Ramboll	Independent Environmental Checker	Mr. YH Hui	3465 2850
BTP	Contractor (ED/2018/04)	Mr. Roy Leung	6628 2685
GTECH	Contractor (ED/2020/03)	Mr. Deacon Choi	6038 3568
LCSJV	Contractor (NE/2015/01)	Mr. Valentine Ho	3973 0409

1.10 The Organizational Structure for Environmental Management is shown in **Figure 1.2**.

Construction Activities undertaken during the Reporting Month

1.11 The major site activities undertaken in the reporting month included:

Table 1.2 Summary of Key Construction Work in the Reporting Month

Contract No.	Project Title	Site Activities
ED/2018/04	Trunk Road T2 and	
	Infrastructure Works for	
	Developments at South	• EVB – E&M works
	Apron	
ED/2020/03	Trunk Road T2 – Traffic Control And Surveillance System (TCSS) and Associated Works	EVB – Installation of TCSS Cable Containment
NE/2015/01	Tseung Kwan O – Lam Tin Tunnel–Main Tunnel and Associated Works	

Summary of EM&A Requirements

- 1.12 The EM&A programme requires construction noise, air quality monitoring and environmental site audit, etc. The EM&A requirements for each parameter are described in the following sections, including:
 - All monitoring parameters;
 - Action and Limit levels for all environmental parameters;
 - Event Action Plans;
 - Environmental mitigation measures, as recommended in the Project EIA Report.
- 1.13 The advice on the implementation status of environmental protection and pollution control/mitigation measures is summarized in **Section 12** of this report.
- 1.14 This report presents the monitoring results, observations, locations, equipment, period, methodology and QA/QC procedures of the monitoring parameters of the required environmental monitoring works and audit works for the Project in August 2025.

Status of Environmental Licensing and Permitting

1.15 All permits/licenses obtained for the Project are summarized in **Table 1.3**.

Table 1.3 Summary of Environmental License and Permit

D/I. N	Valid	Period	C4 - 4			
Permit / License No.	From	То	Status			
Environmental Permit (EP)	Environmental Permit (EP)					
EP-451/2013	19 Sep 2013	N/A	Valid			
EP-458/2013/C	20 Jan 2017	N/A	Valid			
Notification pursuant to Air Pollution (Const	ruction Dust) R	Regulation				
Ref. No.: 451120	20 Nov 2019	N/A	Valid			
Billing Account for Construction Waste Disp	osal					
A/C No.: 7036016	09 Dec 2019	N/A	Valid			
Construction Noise Permit						
CNP No. (For Portion U): GW-RE0272-25	01 Apr 2025	30 Sep 2025	Valid			
CNP No. (For Portion T1): GW-RE0385-25	16 Apr 2025	15 Sep 2025	Valid			
CNP No. (For Portion Q): GW-RE0696-25	01 Jul 2025	31 Dec 2025	Valid			
CNP No. (For Portion T1): GW-RE0861-25	28 Jul 2025	27 Jan 2026	Valid			
Wastewater Discharge License						
WT00036699-2020	14 Jan 2021	31 Jan 2026	Valid			
Chemical Waste Producer License						
WPN: 5213-286-B2557-03	09 Mar 2020	N/A	Valid			

2. AIR QUALITY

Monitoring Requirement

2.1 According to Section 2.2.4 of the EM&A Manual (AEIAR-173/2013), 1-hour and 24-hour Total Suspended Particulates (TSP) monitoring was conducted to monitor the air quality for this Project. For regular impact monitoring, a sampling frequency of at least once in every six days at all of the monitoring stations for 1-hour and 24-hour TSP monitoring. **Appendix A** shows the established Action/Limit Levels for the environmental monitoring works.

Monitoring Locations

2.2 Five designated monitoring stations were selected for air quality monitoring programme. **Table** 2.1 describes the air quality monitoring locations, which are also depicted in **Figure 2**.

Table 2.1 Air Quality Monitoring Locations

Monitoring Stations	Location	Location of Measurement
AM1	Tin Hau Temple	Ground Level
AM2	Sai Tso Wan Recreation Ground	Ground Level
AM3	Yau Lai Estate Bik Lai House	Rooftop (41/F)
$AM4^{(1)}$	Sitting-out Area at Cha Kwo Ling Village	Ground Level
AM4(B) ^{(2) (*) (**)}	Flat 103 Cha Kwo Ling Village	Ground Level

Remarks:

- (1) For 1-hour TSP monitoring;
- (2) For 24-hour TSP monitoring
- (*) Air quality monitoring at designated station AM4 (24-hr TSP) was rejected by the premise owners. Therefore, baseline and impact air quality monitoring works were carried out at alternative air quality monitoring stations AM4 (A) (24-hr TSP only)
- (**) AM4(A) is not available for conducing monitoring due to the demolition of administrative office.

Monitoring Parameters and Frequency

2.3 **Table 2.2** summarizes the monitoring parameters, monitoring period and frequencies of impact air quality monitoring. The monitoring schedule is shown in **Appendix D**.

Table 2.2 Frequency and Parameters of Air Quality Monitoring

Monitoring Stations	Parameter	Period	Frequency
AM1, AM2, AM3, AM4	1-hour TSP	0700 - 1900	3 times per 6 days
AM1, AM2, AM3, AM4(B)	24-hour TSP	24 hours	Once every 6 days

Monitoring Equipment

- 2.4 High Volume Samplers (HVS) in compliance with the specification stipulated in the EM&A Manual (AEIAR-173/2013), Section 2.3.1, were used to carry out 24-hour TSP monitoring. Direct reading dust meter were also used to measure 1-hour average TSP levels. The 1-hour sampling was determined by HVS to check the validity and accuracy of the results measured by direct reading method.
- 2.5 Wind data monitoring equipment was set at rooftop (about 41/F) of Yau Lai Estate Bik Lai House for logging wind speed and wind direction such that the wind sensors are clear of obstructions or turbulence caused by building. The wind data monitoring equipment is re-calibrated at least once every six months and the wind directions are divided into 16 sectors of 22.5 degrees each. The location is shown in **Figure 2**. This weather information for the reporting month is summarized in **Appendix C**.
- 2.6 **Table 2.3** summarizes the equipment used for air quality monitoring by the ET for Contract No. CE 59/2015 (EP). Copies of calibration certificates are attached in **Appendix B**.

Table 2.3 Air Quality Monitoring Equipment

Table 2.5 All Quanty Monitoring Equipment					
Equipment	Model	Quantity			
1-hour TSP Dust Meter	Sibata Model No. LD-5R (Serial No.: 972777, 972778, 972780, 8Y2374, 8Y2373, 972781, 2Y6194)	7			
HVS Sampler	GMW model: GS2310 (Serial No.: 1287, 10379, 10599)	3			
_	TE 5170 (Serial No.: 1956)	1			
Calibrator	TISCH Model: TE-5025A (Serial No.: 3864)	1			
Wind Anemometer	Davis Weather Monitor II, Model no. 7440 (Serial No.: MC01010A44)	1			

Monitoring Methodology

1-hour TSP Monitoring

Measuring Procedures

2.7 The measuring procedures of the 1-hour dust meter are in accordance with the Manufacturer's Instruction Manual as follows:

(Sibata Model No.: LD-5R)

- The 1-hour dust meter is placed at least 1.3 meters above ground.
- Set POWER to "ON" and make sure that the battery level was not flash or in low level.
- Allow the instrument to stand for about 3 minutes and then the cap of the air sampling inlet has been released.
- Push the knob at MEASURE position.

- Set time/mode setting to [BG] by pushing the time setting switch. Then, start the background measurement by pushing the start/stop switch once. It will take 6 sec. to complete the background measurement.
- Push the time setting switch to change the time setting display to [MANUAL] at the bottom left of the liquid crystal display. Finally, push the start/stop switch to stop the measuring after 1 hour sampling.
- Information such as sampling date, time, count value and site condition were recorded during the monitoring period.

Maintenance/Calibration

- 2.8 The following maintenance/calibration is required for the 1-hour dust meter:
 - Check and calibrate the meter by HVS to check the validity and accuracy of the results measured by direct reading method at 2-month intervals throughout all stages of the air quality monitoring.

24-hour TSP Monitoring

<u>Instrumentation</u>

- 2.9 High volume samplers (HVS) (TISCH Model: TE-5170 and GMW Model: GS2310) completed with appropriate sampling inlets were employed for 24-hour TSP monitoring. The sampler was composed of a motor, a filter holder, a flow controller and a sampling inlet and its performance specification complied with that required by USEPA Standard Title 40, Code of Federation Regulations Chapter 1 (Part 50).
- 2.10 The positioning of the HVS samplers are as follows:
 - A horizontal platform with appropriate support to secure the samplers against gusty wind shall be provided;
 - No two samplers shall be placed less than 2 meters apart;
 - The distance between the sampler and an obstacle, such as buildings, must be at least twice the height that the obstacle protrudes above the sampler;
 - A minimum of 2 metres of separation from walls, parapets and penthouses is required for rooftop samplers;
 - A minimum of 2 metres of separation from any supporting structure, measured horizontally is required;
 - No furnace or incinerator flue is nearby;
 - Airflow around the sampler is unrestricted;
 - The sampler is more than 20 metres from the dripline;
 - Any wire fence and gate, to protect the sampler, shall not cause any obstruction during monitoring;
 - Permission must be obtained to set up the samplers and to obtain access to the monitoring stations; and
 - A secured supply of electricity is needed to operate the samplers.

Operating/analytical procedures for the operation of HVS

- 2.11 Operating/analytical procedures for the air quality monitoring are highlighted as follows:
 - Prior to the commencement of the dust sampling, the flow rate of the high-volume sampler was properly set (between 0.6 m³/min. and 1.7 m³/min.) in accordance with the EM&A manual (AEIAR-173/2013). The flow rate shall be indicated on the flow rate chart.
 - For TSP sampling, fiberglass filters with a collection efficiency of > 99% for particles of 0.3 µm diameter were used.
 - The power supply was checked to ensure the sampler worked properly. On sampling, the sampler was operated for 5 minutes to establish thermal equilibrium before placing any filter media at the designated air monitoring station.
 - The filter holding frame was then removed by loosening the four nuts and a weighted and conditioned filter was carefully centered with the stamped number upwards, on a supporting screen.
 - The filter was aligned on the screen so that the gasket formed an airtight seal on the outer edges of the filter. Then the filter holding frame was tightened to the filter holder with swing bolts. The applied pressure should be sufficient to avoid air leakage at the edges.
 - The shelter lid was closed and secured with the aluminium strip.
 - The timer was then programmed. Information was recorded on the record sheet, which included the starting time, the weather condition and the filter number (the initial weight of the filter paper can be found out by using the filter number).
 - After sampling, the filter was removed and sent to the HOKLAS laboratory (ALS Technichem (HK) Pty Ltd.) for weighing. The elapsed time was also recorded.
 - Before weighing, all filters were equilibrated in a conditioning environment for 24 hours. The conditioning environment temperature should be between 25°C and 30°C and not vary by more than ±3°C; the relative humidity (RH) should be < 50% and not vary by more than ±5%. A convenient working RH is 40%.

Maintenance/Calibration

- 2.12 The following maintenance/calibration is required for the HVS:
 - The high-volume motors and their accessories were properly maintained. Appropriate maintenance such as routine motor brushes replacement and electrical wiring checking were made to ensure that the equipment and necessary power supply are in good working condition.
 - High volume samplers were calibrated at bi-monthly intervals using TE-5025A Calibration Kit throughout all stages of the air quality monitoring.

Results and Observations

2.13 The impact monitoring works for air quality monitoring locations AM1, AM2, AM3 and AM4 are completed by the ET of Agreement No. CE 59/2015 (EP), and the data will be adopted in this report. As the proposal for relocation approved, the monitoring at AM4(A) will be conducted at AM4(B). For the time being, as the station CKL2 for the 24 hr TSP monitoring, carried out under EM&A works for Trunk Road T2 Project (EP- 451/2013), is located in close proximity to AM4(B); the results from CKL2 are adopted as reference for the 24 TSP monitoring at AM4(B), which has similar environment when compared with that for CKL2. The location of monitoring station CKL2 is shown in **Figure 2**.

- 2.14 The impact air quality monitoring was conducted at all five monitoring stations as scheduled. The monitoring schedule is shown in **Appendix D**.
- 2.15 No Action Level exceedance was recorded for 24-hour TSP monitoring in the reporting month and No Limit Level exceedance was recorded for 24-hour TSP monitoring in the reporting month.
- 2.16 No Action/Limit Level exceedance was recorded for 1-hour TSP monitoring in the reporting month.
- 2.17 The monitoring data and graphical presentations of 1-hour and 24-hour TSP monitoring results are shown in **Appendix E** and **Appendix F** respectively.
- 2.18 According to field observations by ET for Agreement No. CE 59/2015 (EP) in the reporting period, the major dust source identified at the designated air quality monitoring stations are as follows:

Table 2.4 Major Dust Source during Air Quality Monitoring

able 2.4 Major Dust Source during Air Quanty Monitoring			
Monitoring Stations	Major Dust Source		
AM1 – Tin Hau Temple	Road Traffic at Cha Kwo Ling Road, non-project related influence and the construction activity from other construction site (i.e underground utility work in TKOLTT project)		
AM2 – Sai Tso Wan Recreation Ground	Road Traffic along Sin Fat Road		
AM3 – Yau Lai Estate Bik Lai House	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza, non-project related influence and the construction activity from other construction site (i.e road paving work in TKOLTT project)		
AM4 - Sitting-out Area at Cha Kwo Ling Village	Road Traffic at Cha Kwo Ling Road		
AM4(B) ^(**) - Flat 103 Cha Kwo Ling Village	Road Traffic at Cha Kwo Ling Road (*)		

^{(*):} Field observation observed at CKL2 during monitoring is presented. Detail refers to S2.13.

Comparison of EM&A Result with EIA Prediction

2.19 The air monitoring data was compared with the predictions (with the assessment height of 1.5 mAG) in Table 3.17 of EIA Report, AEIAR-173/2013 (as approved in 2013) as summarised in **Table 2.5** and **Table 2.6**.

^(**) AM4(A) is not available for conducing monitoring due to the demolition of administrative office.

Table 2.5 Comparison of 1-hr TSP Monitoring Data with Predictions in EIA Report

Monitoring Stations	ASR ID	Predicted Maximum 1-hr TSP Concentration in EIA Report (AEIAR- 173/2013), μg/m ³	Maximum 1-hr TSP Concentration in the Reporting Month (August 2025), μg/m³
AM1 – Tin Hau Temple	CL1	707	63.0
AM2 – Sai Tso Wan Recreation Ground	CL6	266	81.7
AM3 – Yau Lai Estate Bik Lai House	CL9	507	62.7
AM4 - Sitting-out Area at Cha Kwo Ling Village	CL16	430	73.5

Table 2.6 Comparison of 24-hr TSP Monitoring Data with Predictions in EIA Report

Monitoring Stations	ASR ID	Predicted Maximum 24-hr TSP Concentration in EIA Report (AEIAR- 173/2013), μg/m ³	Maximum 24-hr TSP Concentration in the Reporting Month (August 2025), μg/m³
AM1 – Tin Hau Temple	CL1	199	17.8
AM2 – Sai Tso Wan Recreation Ground	CL6	109	21.9
AM3 – Yau Lai Estate Bik Lai House	CL9	123	21.7
AM4(B) – Flat 103 Cha Kwo Ling Village ^(*)	N/A (1)	N/A (1)	122.0 (**)

Remarks:

2.20 In the reporting month, the 1-hour TSP concentrations at AM1, AM2, AM3 and AM4 were lower than the prediction in the EIA Report, AEIAR-173/2013 (as approved in 2013). No Action/Limit level exceedance was recorded in the reporting period.

⁽¹⁾ No 24-hr TSP concentration was predicted in EIA Report (AEIAR-173/2013)

^(*) Air quality monitoring at designated station AM4 (24-hr TSP) was rejected by the premise owners. Therefore, baseline and impact air quality monitoring works were carried out at alternative air quality monitoring stations AM4 (B) (24-hr TSP only)

^{(**):} Monitoring results at CKL2 is presented. Detail refers to S2.13

2.21 In the reporting month, the 24-hour TSP concentrations at AM1, AM2 and AM3 were lower than the prediction in the EIA Report, AEIAR-173/2013 (as approved in 2013). No Action Level exceedance was recorded for 24-hour TSP monitoring in the reporting month and no Limit Level exceedance was recorded for 24-hour TSP monitoring in the reporting month.

3 NOISE

Monitoring Requirements

3.1 According to Section 3.2.1 of the EM&A Manual (AEIAR-173/2013), construction noise monitoring was conducted to monitor the construction noise arising from the construction activities. The regular monitoring frequency for each monitoring station shall be on a weekly basis and conduct one set of measurements between 0700 and 1900 hours on normal weekdays. Appendix A shows the established Action and Limit Levels for the environmental monitoring works.

Monitoring Locations

3.2 Noise monitoring was conducted at five designated monitoring stations, namely CM1, CM2, CM3, CM4 and CM5 in the reporting period. **Table 3.1** and **Figure 2** show the locations of these stations.

Table 3.1 Noise Monitoring Stations

Monitoring Stations	Location	Location of Measurement
CM1	Nga Lai House, Yau Lai Estate Phase 1, Yau Tong	Rooftop (41/F)
CM2	Bik Lai House, Yau Lai Estate Phase 1, Yau Tong	Rooftop (41/F)
CM3	Block S, Yau Lai Estate Phase 5, Yau Tong	Rooftop (40/F)
CM4	Tin Hau Temple, Cha Kwo Ling	Ground Level
CM5	CCC Kei Faat Primary School, Yau Tong	Rooftop (6/F)

Monitoring Parameters, Frequency and Duration

3.3 **Table 3.2** summarizes the monitoring parameters, frequency and total duration of monitoring. The noise monitoring schedule is shown in **Appendix D**.

Table 3.2 Frequency and Parameters of Noise Monitoring

Monitoring Stations	Time Period	Duration	Frequency	Parameter	Measurement	
CM1				L ₁₀ (30 min.) dB(A)	Façade Measurement	
CM2	0.000 1000 1	0700-1900 hrs on normal 30 minutes			Façade Measurement	
CM3	on normal		30 minutes	30 minutes	Once per week	L ₉₀ (30 min.) dB(A)
CM4	weekdays			L _{eq} (30 min.)	Façade Measurement	
CM5				dB(A)	Façade Measurement	

Monitoring Equipment

3.4 Integrating Sound Level Meter was used for impact noise monitoring. The meters were Type 1

sound level meter capable of giving a continuous readout of the noise level readings including equivalent continuous sound pressure level (L_{eq}) and percentile sound pressure level (L_x) that also complied with International Electrotechnical Commission Publications 651:1979 (Type 1) and 804:1985 (Type 1) specifications. **Table 3.3** summarizes the noise monitoring equipment being used by the ET for Agreement No. CE 59/2015 (EP) within the reporting period. Copies of calibration certificates are attached in **Appendix B**.

Table 3.3 Noise Monitoring Equipment

· ·		
Equipment	Model	Quantity
	BSWA 308 (Serial No.: 570187,	
Integrating Sound Level Meter	580238, 570188)	4
	SVAN 957 (Serial No.: 23851)	
Calibrator	AWA6021A (Serial No.: 1023253,	2
Calibrator	1023064)	2

Monitoring Methodology and QA/QC Procedure

- 3.5 The monitoring procedures are as follows:
 - The monitoring station was normally be at a point 1m from the exterior of the sensitive receivers building façade and be at a position 1.2m above the ground.
 - For free field measurement, the meter was positioned away from any nearby reflective surfaces. All records for free field noise levels were adjusted with a correction of +3 dB(A).
 - The battery condition was checked to ensure the correct functioning of the meter.
 - Parameters such as frequency weighting, the time weighting and the measurement time were set as follows:
 - Frequency weighting: A
 - Time weighting: Fast
 - Time measurement: 30 minutes
 - Prior to and after each noise measurement, the meter was calibrated using a Calibrator for 94.0 dB at 1000 Hz. If the difference in the calibration level before and after measurement was more than 1.0 dB, the measurement would be considered invalid and repeat of noise measurement would be required after re-calibration or repair of the equipment.
 - The wind speed was frequently checked with the portable wind meter.
 - At the end of the monitoring period, the L_{eq}, L₉₀ and L₁₀ were recorded. In addition, site conditions and noise sources were recorded on a standard record sheet.
 - Noise monitoring would be cancelled in the presence of fog, rain, and wind with a steady speed exceeding 5 m/s, or wind with gusts exceeding 10 m/s. Supplementary monitoring would be provided to ensure sufficient data would be obtained.

Maintenance and Calibration

- 3.6 The microphone head of the sound level meter and calibrator were cleaned with a soft cloth at quarterly intervals.
- 3.7 The sound level meter and calibrator were checked and calibrated at yearly intervals.
- 3.8 Immediately prior to and following each noise measurement the accuracy of the sound level meter was checked using an acoustic calibrator generating a known sound pressure level at a known frequency. Measurements were accepted as valid only if the calibration levels from before

and after the noise measurement agree to within 1.0 dB.

Results and Observations

- 3.9 The data obtained from the impact monitoring works completed by the ET of Agreement No. CE 59/2015 (EP) will be adopted in this report.
- 3.10 No Action Level exceedance was recorded due to the documented complaint in the reporting month.
- 3.11 No Limit Level exceedance was recorded for day-time construction noise monitoring in the reporting month.
- 3.12 Noise monitoring results and graphical presentations are shown in **Appendix G**.
- 3.13 According to field observations by ET for Agreement No. CE 59/2015 (EP) in the reporting period, the major noise sources identified at the noise monitoring stations are shown in Table 3.4.

Table 3.4 Other Noise Source Identified during Noise Monitoring

Monitoring Stations	Major Noise Source
	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza, non-
CM1	project related construction activities (i.e road paving work in
	TKOLTT project)
	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza, non-
CM2	project related construction activities (i.e road paving work in
	TKOLTT project)
	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza non-project
CM3	related construction activities (i.e road paving work in TKOLTT
	project)
CM4	Road Traffic at Cha Kwo Ling Road, non-project related construction
CIVI4	activities (i.e underground utility work in TKOLTT project)
CM5	Road Traffic near Eastern Cross Harbour Tunnel Toll Plaza,
CIVIS	Road Traffic at Yau Tong Road

Table 3.5 Baseline Noise Level and Noise Limit Level for Monitoring Stations

Monitoring Stations	Baseline Noise Level, dB (A) (at 0700 – 1900 hrs on normal weekdays)	Noise Limit Level, dB (A) (at 0700 – 1900 hrs on normal weekdays)
CM1	65.5	
CM2	63.6	75
CM3	65.6	75
CM4	62.0	
CM5	68.2	70*

^(*) Noise Limit Level is 65 dB(A) during school examination periods.

Comparison of EM&A Result with EIA Prediction

3.14 The noise monitoring data was compared with the predictions in Table 4.15 of EIA Report (AEIAR-173/2013) as summarised in **Table 3.6**.

Table 3.6 Maximum Predicted Mitigated Construction Noise Levels in EIA Report

Monitoring Stations	NSR ID	Maximum Predicted Mitigated Construction Noise Levels in EIA Report (AEIAR- 173/2013), dB(A)	Maximum Construction Noise Levels in the Reporting Month (August 2025), Leq (30min) dB(A)
CM1 – Nga Lai House, Yau Lai Estate Phase 1, Yau Tong	N1102	73	66
CM2 – Bik Lai House, Yau Lai Estate Phase 1, Yau Tong	N1204	75	68
CM3 – Block S, Yau Lai Estate Phase 5, Yau Tong	N2105	75	67
CM4 – Tin Hau Temple, Cha Kwo Ling	N3101a	73	62
CM5 – CCC Kei Faat Primary School, Yau Tong	N4101	71	67

3.15 The results at CM1, CM2, CM3, CM4 and CM5 were lower than the maximum predicted mitigated construction noise level in EIA Report, AEIAR-173/2013 (as approved in 2013). No Limit level exceedance was recorded in the reporting period.

4. WATER QUALITY

Monitoring Requirement

Groundwater Quality

4.1 The existing groundwater quality monitoring programme has been suspended as the monitoring results had been deemed non-representative of the impact from the project justified by two major factors: (1) influence on the monitoring results from non-project related factors, such as anthropogenic activities and natural phenomenon; and (2) large separation between the monitoring stations and works area. In addition, as no alternative locations for the groundwater quality monitoring were available, the groundwater quality monitoring has been suspended since October 2019 upon the agreement by EPD.

Marine Water Quality

4.2 According to Section 4.4.3 of EM&A Manual (AEIAR-173/2013), marine water quality impact monitoring stations is carried out during marine construction for TKOLTT reclamation. Since the construction of Cha Kwo Ling Tunnel from the end of Trunk Road T2 to the TKOLTT at the Eastern Ventilation Building does not involve reclamation, the marine water quality monitoring programme stated in Section 4.4 of the EM&A Manual (AEIAR-173/2013) is therefore not applicable to Contract No. ED/2018/04.

Groundwater Level Monitoring (Piezometer Monitoring)

4.3 According to Section 4.1.2 of EM&A Manual (AEIAR-173/2013), daily piezometer monitoring will be carried out on a daily basis when any tunnel construction activities are carried out within +/- 50m of the piezometer gate in plan. As the construction works of Cha Kwo Ling Tunnel from the end of Trunk Road T2 to the TKOLTT at the Eastern Ventilation Building is approximately 120m away from the piezometer gate in plan, the piezometer monitoring programme stated in Section 4.2 of the EM&A Manual (AEIAR-173/2013) is therefore not applicable to Contract No. ED/2018/04.

5. WASTE MANGEMENT

- 5.1 According to Section 5.1.2 of the EM&A Manual (AEIAR-173/2013), Waste materials generated during construction activities, such as construction and demolition (C&D) materials and general refuse, are recommended to be audited at regular intervals (at least quarterly) to ensure that proper storage, transportation and disposal practices are being implemented by the Contractor. To fulfil this requirement, site audits are carried out on a weekly basis. The summaries of site audits are attached in **Appendix I**.
- 5.2 With reference to relevant handling records of this Project, the quantities of different types of waste generated in the reporting month are summarised and presented in **Appendix H**.

6. ECOLOGY

Post-Translocation Coral Monitoring

6.1 Post-translocation monitoring survey is recommended in Section 6.2.5 of the EM&A Manual (AEIAR-173/2013), to audit the success of coral translocation. Since the construction of Cha Kwo Ling Tunnel from the end of Trunk Road T2 to the TKOLTT at the Eastern Ventilation Building does not involve any marine works in the concerned area mentioned in Section 6.1.2 of the EM&A Manual (AEIAR-173/2013), the post-translocation monitoring survey stated in Section 6.2.5 of the EM&A Manual (AEIAR-173/2013) is therefore not applicable to Contract No. ED/2018/04.

7. FISHERIES

- 7.1 According to Section 7.1.3 of EM&A Manual (AEIAR-173/2013), no specific fisheries monitoring programme is required during the construction phase.
- 7.2 The implementation of the mitigation measures stated in the Water Quality Impact Assessment (Refer to Section 5 of EIA Report (AEIAR-173/2013)) will be audited as part of the EM&A procedures during the construction period. The summaries of site audits are attached in **Appendix I**.

8. CULTURAL HERITAGE

- 8.1 According to Condition 3.7 of EP-458/2013/C and Section 8.2.1 of the EM&A Manual (AEIAR-173/2013), monitoring of vibration impacts was conducted when the construction works are less than 100m from the Built Heritage in close proximity of the worksite, namely the Cha Kwo Ling Tin Hau temple. Tilting and settlement monitoring should be applied on the Cha Kwo Ling Tin Hau Temple.
- 8.2 As the construction works of Cha Kwo Ling Tunnel from the end of Trunk Road T2 to the TKOLTT at the Eastern Ventilation Building are located more than 100m away from the Cha Kwo Ling Tin Hau temple, the vibration impact monitoring stated in Section 8.3.1 of the EM&A Manual (AEIAR-173/2013) is not applicable to Contract No. ED/2018/04.

Mitigation Measures for Cultural Heritage

- 8.3 According to Condition 3.6 of EP-458/2013/C, to prevent damage to Cha Kwo Ling Tin Hau Temple and its Fung Shui rocks (Child-given rocks) during the construction phase, a temporarily fenced-off buffer zone (Rocks buffer zone is 5 m from the edge of Rocks and 15m from the edge of Rocks alter) with allowance for public access (minimum 1 m) around the temple and the Fung Shui rocks shall be provided. The open yard in front of the temple should be kept as usual for annual Tin Hau festival.
- As there is a large buffer distance from the current works to Cha Kwo Ling Tin Hau Temple and the Fung Shui rocks (Child-given rocks), the temporarily fenced-off rocks buffer zone and from the edge of Rocks alter is not required. The fenced-off rocks buffer zone would be implemented when there are construction activities in vicinity of the cultural heritage.

9. LANDSCAPE AND VISUAL IMPACT

- 9.1 According to Section 9.3 of the EM&A Manual (AEIAR-173/2013), landscape and visual mitigation measures during the construction phase shall be checked to ensure that they are fully realized and implemented on site.
- 9.2 Site audits were carried out on a weekly basis to monitor and audit the timely implementation of landscape and visual mitigation measures listed in "Environmental Mitigation Implementation Schedule (EMIS)" (shown in **Appendix J**).
- 9.3 The implementation of landscape and visual mitigation measures was checked by a registered landscape architect. No non-compliance of the landscape and visual impact was recorded in the reporting month. Details of the audit findings and implementation status are presented in **Appendix I**.

10. LANDFILL GAS MONITORING

Monitoring Requirement

10.1 In accordance with Section 10.1.1 of the EM&A Manual (AEIAR-173/2013), monitoring of landfill gas is required for construction works within the Sai Tso Wan Landfill Consultation Zone during the construction phase. Since no excavation activity for this Project was carried out within the Sai Tso Wan Landfill Consultation Zone in the reporting month, no landfill gas monitoring is required.

11. HAZARD TO LIFE

11.1 According to Section 11.1.1 of EM&A Manual (AEIAR-173/2013), as no overnight storage of explosive on site is required for the construction of the Project, the hazard assessment is deemed not necessary. Thus, environmental monitoring and audit is not required.

12. ENVIRONEMNTAL AUDIT

Site Audits

- 12.1 Site audits were carried out on a weekly basis to monitor the timely implementation of proper environmental management practices and mitigation measures in the Project site. The summaries of site audits are attached in **Appendix I**.
- 12.2 Site audits for each contract were conducted as follows.
 - ED/2018/04 Site audits were conducted on 07, 15, 21 & 28 August 2025 in the reporting month. Site inspection of the IEC was conducted on 21 August 2025. No non-compliance was observed during the site audit.
 - ED/2020/03 Site audits were conducted on 07, 15, 21 & 28 August 2025 in the reporting month. Site inspection of the IEC was conducted on 21 August 2025. No non-compliance was observed during the site audit.
 - NE/2015/01 Site audits were conducted on 06, 13, 20 & 27 August 2025 in the reporting month. Site inspection of the IEC was conducted on 20 August 2025. No non-compliance was observed during the site audit.

Implementation Status of Environmental Mitigation Measures

- 12.3 According to Environmental Permits, the approved EIA Reports (Register No.: AEIAR-174/2013 and AEIAR-173/2013), and the EM&A Manuals of the Project (AEIAR-174/2013 and AEIAR-173/2013), the mitigation measures detailed in the documents are recommended to be implemented during the construction phase. An Environmental Mitigation Implementation Schedule (EMIS) is provided in **Appendix J**.
- 12.4 The ET weekly site inspections were carried out during the reporting month and the observations and recommendations are summarized in **Table 12.1**. Refer to **Appendix I** for the site inspection summary reports in the reporting month.

Table 12.1 Observations and Recommendations of Site Audit

Parameters	Date	Observations and Recommendations	Follow-up
Air Quality	N/A	There was no observation in the reporting period.	N/A
Noise	N/A	There was no observation in the reporting period.	N/A
	07 August 2025	Stagnant water was observed at Portion SB.	Stagnant water was cleaned.
Water Quality	07 August 2025	Stagnant water was observed at Portion TY.	Larvicide oil was placed into the stagnant water.
Ecology	N/A	There was no observation in the reporting period.	N/A

Parameters	Date	Observations and Recommendations	Follow-up
Landscape and Visual	N/A	There was no observation in the reporting period.	N/A
Waste/Chemical Management	20 August 2025	The Contractor is reminded to remove the accumulated general refuse (i.e. water bottles) on the slope.	The general refuse has been removed.
Permits /Licences	N/A	There was no observation in the reporting period.	N/A

Implementation Status of Event and Action Plans

12.5 The Event and Action Plans for air quality and construction noise monitoring, and the Limit Levels and Action Plan for landfill gas monitoring are presented in **Appendix L**.

Air Quality Monitoring

- No Action/Limit Level exceedance for 1-hour TSP monitoring was recorded in the reporting month.
- No Action Level exceedance for 24-hour TSP monitoring was recorded in the reporting month and no Limit Level exceedance for 24-hour TSP monitoring was recorded in the reporting month.

Construction Noise Monitoring

- No Action Level exceedance was recorded due to the documented complaint in the reporting month.
- No Limit Level exceedance for construction noise monitoring was recorded in the reporting month.

13. ENVIRONMENTAL NON-COMFORMANCE

Summary of Complaint, Warning, Notification of any Summons and Successful Prosecution

13.1 The summaries of environmental complaint, warning, summon and notification of successful prosecution for the Project is presented in **Appendix M**.

Summary of Exceedance

13.2 The summary of exceedance record in the reporting month is shown in **Appendix N**.

14. FUTURE KEY ISSUES

- 14.1 Tentative construction programmes for the next three months are provided in **Appendix O**.
- 14.2 Major site activities undertaken for the coming months are summarized as follows:

Table 14.1 Site Activities and the Key Environmental Issues in the next Reporting Period

Table 14.1 Site Activities and the Key Environmental Issues in the next Reporting Period			
Contract No. and Project Title	Site Activities (September 2025)	Key Environmental Issues	
ED/2018/04 - Trunk Road T2 and Infrastructure Works for Developments at South Apron	 EVB – ABWF EVB – E&M works East Bound – Tunnel excavation 	 Dust generation from haul road, stockpile of dusty materials, exposed site area, excavation works; Noisy construction activity such as breaking and drilling activities; Runoff from exposed slope or site area; and Wastewater and runoff discharge from site. Accumulation of construction waste or general refuse. 	
ED/2020/03 - Trunk Road T2 - Traffic Control And Surveillance System (TCSS) and Associated Works	TCSS installation- CKR Gantry, WVB, T2 Gantry, Tunnel & Service Gallery, TKO-LTI, EVB	Accumulation of construction waste or general refuse.	
NE/2015/01 - Tseung Kwan O- Lam Tin Tunnel- Main Tunnel and Associated Works	Stage 1 Commissioning Outstanding Works	 Dust generation from haul road, stockpile of dusty materials, exposed site area, excavation works; Runoff from exposed slope or site area; and Accumulation of construction waste or general refuse. 	

Monitoring Schedule

14.3 The tentative environmental monitoring schedule for the next month is shown in **Appendix D**.

15. CONCLUSION AND RECOMMENDATION

Conclusions

15.1 This is the 64th Monthly EM&A Report which presents the EM&A works undertaken during the reporting month in accordance with the EM&A Manual (AEIAR-173/2013) and the requirement under EP.

Air Quality Monitoring

- 15.2 No Action/Limit Level exceedance was recorded for 1-hour TSP monitoring in the reporting month.
- 15.3 No Action Level exceedance for 24-hour TSP monitoring was recorded in the reporting month and no Limit Level exceedance for 24-hour TSP monitoring was recorded in the reporting month.

Construction Noise Monitoring

- 15.4 No Action Level exceedance was recorded due to documented complaint in the reporting month.
- 15.5 No Limit Level exceedance for construction noise monitoring was recorded in the reporting month.

Site Audit

15.6 Four (4) ET joint weekly environmental site inspections were conducted for the Contract No. ED/2018/04, ED/2020/03 and NE/2015/01 in the reporting month.


Complaint, Notification of Summons and Successful Prosecution

15.7 No environmental complaint was received in the reporting period. No notifications of summons and successful prosecutions were received in the reporting month.


Recommendations


15.8 According to the environmental audit performed in the reporting month, no recommendations were made.

FIGURES









APPENDIX A ACTION AND LIMIT LEVELS

APPENDIX A – Action and Limit Levels

Air Quality

1-hr TSP

Monitoring Stations	Location	Action Level, μg/m ³	Limit Level, μg/m³
AM1	Tin Hau Temple	275	
AM2	Sai Tso Wan Recreation Ground	273	500
AM3	Yau Lai Estate Bik Lai House	271	500
AM4	Sitting-out Area at Cha Kwo Ling Village	278	

24-hr TSP

Monitoring Stations	Location	Action Level, μg/m ³	Limit Level, μg/m³
AM1	Tin Hau Temple	173	
AM2	Sai Tso Wan Recreation Ground	192	
AM3	Yau Lai Estate Bik Lai House	167	260
AM4(B)	Flat 103 Cha Kwo Ling Village	210	

Noise

Time Period	Action Level	Limit Level
0700-1900 hrs on normal weekdays	When one documented complaint is received	75 dB(A) ⁽¹⁾

Landfill Gas Monitoring

Parameter	Limit Level
Oxygen	<19%
	<18%
Methane	>10% LEL (i.e. > 0.5% by volume)
	>20% LEL (i.e. > 1% by volume)
Carbon	>0.5%
Dioxide	>1.5%

 ¹ 70 dB(A) for schools and 65 dB(A) for schools during examination period.
 ² Acceptable Noise Levels for Area Sensitivity Rating of A/B/C
 ³ If works are to be carried out during restricted hours, the conditions stipulated in the construction noise permit issued by the Noise Control Authority have to be followed.

APPENDIX B COPIES OF CALIBRATION CERTIFICATES



Certificate of Calibration - Wind Monitoring Station

Description: Yau Lai Estate, Bik Lai House

Manufacturer: <u>Davis Instruments</u>

Model No.: <u>Davis7440</u>

Serial No.: <u>MC01010A44</u>

Equipment No.: <u>SA-03-04</u>

Date of Calibration <u>17-Feb-2025</u>

Next Due Date <u>17-Aug-2025</u>

1. Performance check of Wind Speed

Wind Sp	peed, m/s	Difference D (m/s)
Wind Speed Reading (V1) Anemometer Value (V2)		D = V1 - V2
0.0 0.0		0.0
1.5	1.4	0.1
2.5	2.4	0.1
4.0	3.8	0.2

2. Performance check of Wind Direction

Wind Di	rection (°)	Difference D (°)
Wind Direction Reading (W1) Marine Compass Value (W2)		D = W1 - W2
0	0	0.0
90	90	0.0
180	180	0.0
270	270	0.0

Test Specification:

- 1. Performance Wind Speed Test The wind meter was on-site calibrated against the anemometer
- 2. Performance Wind Direction Test The wind meter was on-site calibrated against the marine compass at four direction

Calibrated by:

Wong Shing Kwai

Approved by:

Henry/Leung



Certificate of Calibration - Wind Monitoring Station

Description: Yau Lai Estate, Bik Lai House

Manufacturer: <u>Davis Instruments</u>

Model No.: <u>Davis7440</u>

Serial No.: MC01010A44

Equipment No.: SA-03-04

Date of Calibration 17-Aug-2025

Next Due Date 17-Feb-2026

1. Performance check of Wind Speed

Wind Speed, m/s		Difference D (m/s)
Wind Speed Reading (V1) Anemometer Value (V2)		D = V1 - V2
0.0	0.0	0.0
1.5	1.5	0.0
2.5	2.4	0.1
4.0	3.9	0.1

2. Performance check of Wind Direction

Wind Di	rection (°)	Difference D (°)
Wind Direction Reading (W1) Marine Compass Value (W2)		D = W1 - W2
0	0	0.0
90	90	0.0
180	180	0.0
270	270	0.0

Test Specification:

- 1. Performance Wind Speed Test The wind meter was on-site calibrated against the anemometer
- 2. Performance Wind Direction Test The wind meter was on-site calibrated against the marine compass at four direction

Calibrated by:

Wong Shing Kwai

Approved by:

Henry Leung





RECALIBRATION DUE DATE:

January 7, 2026

Certificate of Calibration

Calibration Certification Information

Cal. Date: January 7, 2025 Rootsmeter S/N: 438320 Ta: 293 °K

Operator: Jim Tisch Pa: 759.0 mm Hg

Calibration Model #: TE-5025A Calibrator S/N: 3864

Run	Vol. Init (m3)	Vol. Final (m3)	ΔVol. (m3)	ΔTime (min)	ΔP (mm Hg)	ΔH (in H2O)
1	1	2	1	1.4590	3.2	2.00
2	3	4	1	1.0360	6.4	4.00
3	5	6	1	0.9160	8.0	5.00
4	7	8	1	0.8800	8.8	5.50
5	9	10	1	0.7270	12.7	8.00

	Data Tabulation					
Vstd	Qstd	$\sqrt{\Delta H \left(\frac{Pa}{Pstd}\right) \left(\frac{Tstd}{Ta}\right)}$		Qa	√∆H(Ta/Pa)	
(m3)	(x-axis)	(y-axis)	Va	(x-axis)	(y-axis)	
1.0114	0.6932	1.4252	0.9958	0.6825	0.8787	
1.0071	0.9721	2.0156	0.9916	0.9571	1.2427	
1.0050	1.0971	2.2535	0.9895	1.0802	1.3893	
1.0039	1.1408	2.3635	0.9884	1.1232	1.4572	
0.9987	1.3737	2.8505	0.9833	1.3525	1.7574	
	m=	2.08969		m=	1.30853	
QSTD	b=	-0.02374	QA	b=	-0.01464	
	r=	0.99985		r=	0.99985	

Calculations				
Vstd=	ΔVol((Pa-ΔP)/Pstd)(Tstd/Ta)	Va=	ΔVol((Pa-ΔP)/Pa)	
Qstd=	Vstd/∆Time	Qa=	Va/ΔTime	
	For subsequent flow rate calculations:			
Qstd=	$1/m\left(\left(\sqrt{\Delta H\left(\frac{Pa}{Pstd}\right)\left(\frac{Tstd}{Ta}\right)}\right)-b\right)$	Qa=	$1/m\left(\left(\sqrt{\Delta H\left(Ta/Pa\right)}\right)-b\right)$	

	Standard Conditions		
Tstd:	298.15 °K		
Pstd:	760 mm Hg		
	Key		
	or manometer reading (in H2O)		
ΔP: rootsmeter manometer reading (mm Hg)			
Ta: actual absolute temperature (°K)			
	arometric pressure (mm Hg)		
b: intercept			
m: slope			

RECALIBRATION

US EPA recommends annual recalibration per 1998 40 Code of Federal Regulations Part 50 to 51, Appendix B to Part 50, Reference Method for the Determination of Suspended Particulate Matter in the Atmosphere, 9.2.17, page 30

FAX: (513)467-9009

High-Volume TSP Sampler

5-POINT CALIBRATION DATA SHEET



File No. MA16034/05/0054

Project No.	AM1 - Tin Hau	Temple						
Date:	13-J	un-25	Next Due Date:	13-2	Aug-25	Operator:	SK	
Equipment No.:	A-0	01-05	Model No.:	GS	S2310	Serial No.	10599	
			Ambient C	Condition				
Temperatur	re, Ta (K)	300.5	Pressure, Pa			754.4		
			ifice Transfer Star	ndard Informa	ation			
Last Calibration Date: 7-Jan-25 $ mc \times Qstd + bc = [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} $				-0.02377				
Last Calibra	ation Date:							
Next Calibra	ation Date:	7-Jan-26		$Qstd = \{ [\Delta H \ x]$	(Pa/760) x (298/	[a)] 1/2 -bc} / m	c	
			Calibration of	TCD Complex				
		Ο	Calibration of r	1SP Sampler		HVS		
Calibration Point	ΔH (orifice), in. of water		60) x (298/Ta)] ^{1/2}	Qstd (CFM) X - axis	ΔW (HVS), in. of water	[ΔW x (Pa/76	(50) x (298/Ta)] ^{1/2} (-axis	
1	13.1		3.59		8.4	,	2.88	
2	10.2		3.17		6.2	,	2.47	
3	7.1		2.64		4.0		1.98	
4	5.1		2.24		2.6		1.60	
5	2.7		1.63	27.97	1.3		1.13	
By Linear Regr Slope, mw = Correlation of *If Correlation C	0.0530 coefficient* =		.9989	Intercept, bw =	-0.389	1		
			Set Point C	alculation				
From the TSP Fi From the Regres Therefore, Se	sion Equation, t	he "Y" value acc		`	98/Ta)] ^{1/2}			
Remarks: Conducted by:	Wong Sl	ning Kwai	Signature:		√ -	Date:	13-Jun-25	
Checked by:	Henry	Leung	Signature:	- tem	y way	Date:	13-Jun-25	



File No. MA16034/05/0055

Project No.	AM1 - Tin Hau	Temple							
Date:	13-At	ıg-25	Next Due Date:	13-	Oct-25	Operator:	SK		
Equipment No.:	A-0	1-05	Model No.:	GS	52310	Serial No.	10599		
			Ambient C	ondition					
Temperatu	re. Ta (K)	303.1	Pressure, Pa			754.3			
<u>F</u>	()			(8)		70 110			
		Or	ifice Transfer Star	ndard Informa	ntion				
Serial	l No.	3864	Slope, mc	0.05914	Intercept	t, bc	-0.02377		
Last Calibra	ation Date:	7-Jan-25	mc x Qstd + bc = $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$						
Next Calibr	ration Date:	7-Jan-26		$Qstd = \{ [\Delta H \ x] $	(Pa/760) x (298/7	Γa)] ^{1/2} -bc} / m	ıc		
		•							
			Calibration of	ΓSP Sampler					
Calibration			fice	Qstd (CFM)		HVS			
AII (amifina)		[ΔH x (Pa/70	[ΔH x (Pa/760) x (298/Ta)] ^{1/2}		ΔW (HVS), in. of water		60) x (298/Ta)] ^{1/2} Y-axis		
1	13.0		3.56	60.63	7.8		2.76		
2	10.0		3.12		5.8		2.38		
3	7.0		2.61	44.59	3.8		1.93		
4	5.0		2.21	37.75	2.5	1.56			
5	2.6		1.59	27.33	1.3		1.13		
Slope , mw = Correlation	coefficient < 0.99	0	.9988	Intercept, bw =	-0.267	75			
			Set Point Ca	alculation					
From the Regres	ield Calibration C ssion Equation, th et Point; W = (m	e "Y" value acc		`	98/Ta)] ^{1/2}				
Remarks:				h	- J				
Conducted by:	Wong Sh	ing Kwai	Signature:	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	<i>y</i> \	Date:	13-Aug-25		
Checked by:	Henry	Leung	Signature:	1 tem	7 mon 7	Date:	13-Aug-25		



File No. MA16034/08/0054

Project No.	AM2 - Sai Tso	Wan Recreation	Ground							
Date:	13-3	13-Jun-25 Next Due Date: 13-Aug-25		Operator:	SK					
Equipment No.:	A-(01-08	_		S2310	<u> </u>	1287			
			-			·				
			Ambient C	ondition						
Temperatur	re, Ta (K)	300.5	Pressure, Pa	(mmHg)		754.4				
		0	ifice Transfer Star	adoud Inform	ation .					
Serial	No	3864	Slope, mc	0.05914	Intercept	. hc	-0.02377			
Last Calibra		7-Jan-25	$mc \times Qstd + bc = [\Delta H \times (Pa/760)]$							
Next Calibra		7-Jan-26	($Qstd = \{ [\Delta H x] \}$	(Pa/760) x (298/7	Γa)] ^{1/2} -bc} / m	ıc			
	·									
Calibration of TSP Sampler										
Calibration		Oı	fice			HVS	1/2			
Point	ΔH (orifice), in. of water	[ΔH x (Pa/76	50) x (298/Ta)] ^{1/2}	Qstd (CFM) X - axis	ΔW (HVS), in. of water		60) x (298/Ta)] ^{1/2} /-axis			
1	13.3		3.62	61.58	8.3		2.86			
2	10.3		3.18	54.24	6.4		2.51			
3	7.7	i	2.75	46.95 37.92	4.2		2.03			
4	5.0		2.22		2.4		1.54			
5	3.4		1.83	31.34	1.2		1.09			
By Linear Regr	assian of V on	v								
	0.0587	A	1	ntercent, bw =	-0.721	0				
	coefficient* =		.9987							
*If Correlation C	oefficient < 0.9	90, check and red	calibrate.							
			Set Point Ca	alculation						
From the TSP Fi										
From the Regress	sion Equation, t	the "Y" value acc	ording to							
		mw x ($\mathbf{Qstd} + \mathbf{bw} = [\Delta \mathbf{W} \ \mathbf{x}]$	(Pa/760) x (29	$[0.08]^{1/2}$					
			2							
Therefore, Se	et Point; $W = (1$	nw x Qstd + bw)	2 x (760 / Pa) x (7	$\Gamma a / 298) =$	3.31					
Remarks:										
•										
				h	ما					
Conducted by:	Wong S	hing Kwai	Signature:		<u> </u>	Date:	13-Jun-25			
				\ o	Λ	_				
Checked by:	Henr	y Leung	Signature:	- tem	7 mon 7	Date:	13-Jun-25			



File No. MA16034/08/0055

Project No.	AM2 - Sai Tso V	Van Recreation	Ground						
Date:	13-Aı	ıg-25	Next Due Date: 13-Oc		Oct-25	Operator:	SK		
Equipment No.: A-01-08 Model No.:		GS	GS2310		1287				
			Ambient C	Condition					
Temperatur	re, Ta (K)	303.1	Pressure, Pa			754.3			
Serial	No	3864	Slope, mc	0.05914	Ation Intercept	t he	-0.02377		
Last Calibra		7-Jan-25	mc x Qstd + bc = $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$						
Next Calibra		7-Jan-26			$(Pa/760) \times (298/7)$				
		•	•			/1 /			
			Calibration of	TSP Sampler					
Calibration		Oı	fice	_		HVS			
Point	ΔH (orifice), in. of water	[ΔH x (Pa/76	50) x (298/Ta)] ^{1/2}	Qstd (CFM) X - axis	ΔW (HVS), in. of water		50) x (298/Ta)] ^{1/2} '-axis		
1	13.5		3.63	61.77	8.4		2.86		
2	10.5		3.20	54.53	6.5		2.52		
3	7.8		2.76	47.05	4.3		2.05		
4	5.2		2.25	38.49	2.5		1.56		
5	3.5		1.85	31.65	1.4		1.17		
Slope, mw = Correlation of *If Correlation C	coefficient* =		.9993	- -	-0.628				
			Set Point C	alculation					
From the TSP Fig From the Regress		e "Y" value acco		z (Pa/760) v (29	98/Ta)1 ^{1/2}				
Therefore, Se	t Point; W = (m		² x (760 / Pa) x ('						
Remarks:									
Checked by:			Signature:	1 0	X. X	Date:	13-Aug-25		
Checked by:	Henry	Leung	Signature:	Tem	7000/	Date:	13-Aug-25		



File No. MA16034/03/0054

Project No.	AM3 - Yau Lai	Estate, Bik Lai I	House				
Date:	13-J	un-25	Next Due Date:	13-2	Aug-25	Operator:	SK
Equipment No.:	A-(01-03	Model No.:	GS	S2310	Serial No.	10379
	I		Ambient C		<u> </u>		
Temperatu	re, Ta (K)	300.5	Pressure, Pa	(mmHg)		754.4	
		Or	ifice Transfer Star	ndard Informe	ation		
Serial	No.	3864	Slope, mc	0.05914	Intercept	i, be	-0.02377
Last Calibra	ation Date:	7-Jan-25		nc x Qstd + bo	$c = [\Delta H \times (Pa/760)]$	x (298/Ta)]	1/2
Next Calibra	ation Date:	7-Jan-26			(Pa/760) x (298/7		
	ı		Calibration of	TSP Sampler			
Calibration		Oı	fice	Г		HVS	1/2
Point	ΔH (orifice), in. of water	[ΔH x (Pa/76	50) x (298/Ta)] ^{1/2}	Qstd (CFM) X - axis	ΔW (HVS), in. of water		760) x (298/Ta)] ^{1/2} Y-axis
1	13.0		3.58		8.4		2.88
2	10.1		3.15		6.1		2.45
3	7.3		2.68		4.2		2.03
4	5.2		2.26		2.3		1.50
5	3.1		1.75	29.94	1.3		1.13
D 11 D		•					
By Linear Regr		X	•	[44]	0.722		
. ,	0.0575 coefficient* =	_	.9973	intercept, bw =	-0.633	3	
		90, check and red		•			
ii conclution c	occincient (0.)	50, eneck and rev	ouriorate.				
			Set Point Ca	alculation			
From the TSP Fi	ield Calibration	Curve, take Qstd	= 43 CFM				
From the Regres	sion Equation, t	he "Y" value acc	ording to				
			$\mathbf{pstd} + \mathbf{bw} = [\Delta \mathbf{W} \ \mathbf{x}]$	(Da/760) v (20	00/Ta)1 ^{1/2}		
		IIIW X Q	įstu i bw – įΔw x	(1 a//00) x (2)	70/1 a) _]		
Therefore, Se	et Point; W = (n	nw x Qstd + bw)	² x (760 / Pa) x (7	Γa / 298) =	3.43		
Remarks:							
				1.0	. 1		
Conducted by:	Wong S	hing Kwai	Signature:	χ'	<u> </u>	Date:	13-Jun-25
J						· -	-
Checked by:	Henry	Leung	Signature:	-lem	y day	Date:	13-Jun-25



File No. MA16034/03/0055

Project No.	AM3 - Yau Lai	Estate, Bik Lai	House			<u>-</u>		
Date:	13-A	ug-25	Next Due Date:	13-	Oct-25	Operator:	SK	
Equipment No.:	A-0	01-03	Model No.:	GS	S2310	Serial No.	10379	
			Ambient C	Condition				
Temperatur	re, Ta (K)	303.1	Pressure, Pa			754.3		
Caria1	N.		Slope, mc	0.05914	I	. h.a	-0.02377	
Serial Last Calibra		3864 7-Jan-25	Slope, mc 0.05914 Intercept, bc -0.0237 $mc \ x \ Qstd + bc = [\Delta H \ x \ (Pa/760) \ x \ (298/Ta)]^{1/2}$					
Next Calibra	The state of the s	7-Jan-25 7-Jan-26	1/2					
ricat Canon	ation Date.			Q514 ([211 A	(1 u/ 100) A (200)	(((((((((((((((((((
			Calibration of	TSP Sampler				
Calibration		0	rfice			HVS		
Point AH (orifice), in. of water		[ΔH x (Pa/7	[ΔH x (Pa/760) x (298/Ta)] ^{1/2}		ΔW (HVS), in. of water		0) x (298/Ta)] ^{1/2} -axis	
1	13.2		3.59		8.5	2	2.88	
2	10.3		3.17		6.2	2	2.46	
3	7.4		2.69		4.0	1	.98	
5	5.5 3.3		2.32 1.79		2.5 1.4		.17	
	0.0574 coefficient* = Coefficient < 0.99		0.9981	Intercept, bw = -	-0.644	15		
			Set Point C	alculation				
From the Regres	eld Calibration (sion Equation, the sion Equation, the sion Equation) the sion of the sion	ne "Y" value acc		`	98/Ta)] ^{1/2}			
Remarks: Conducted by:	Wong Sl	ning Kwai	Signature:		<u></u>	Date:	13-Aug-25	
Checked by:	Henry	Leung	Signature:	-lem	y Xoy	Date:	13-Aug-25	



File No. MA20003/55/033 CKL 2 - Flat 103 Cha Kwo Ling Village Project No. 4-Jul-25 Next Due Date: 4-Sep-25 Date: Operator: SK Equipment No.: A-01-55 Model No.: TE 5170 Serial No. 1956 **Ambient Condition** Temperature, Ta (K) 303.8 Pressure, Pa (mmHg) 754.1 **Orifice Transfer Standard Information** 0.05914 Intercept, bc 3864 Slope, mc -0.02377 Serial No. mc x Qstd + bc = $[\Delta H \times (Pa/760) \times (298/Ta)]^{1/2}$ 7-Jan-25 Last Calibration Date: Qstd = $\{ [\Delta H \times (Pa/760) \times (298/Ta)]^{1/2} -bc \} / mc$ Next Calibration Date: 7-Jan-26 **Calibration of TSP Sampler** Orfice Calibration $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ ΔH (orifice), Ostd (CFM) ΔW (HVS), in. $[\Delta H \ x \ (Pa/760) \ x \ (298/Ta)]^{1/2}$ Point in. of water X - axis of water Y-axis 2.98 1 13.4 3.61 61.47 9.1 11.2 7.2 2 3.30 56.23 2.65 9.3 3.01 51.27 2.31 4 5.1 2.23 38.07 2.6 1.59 5 3.7 2.0 1.90 32.49 1.40 By Linear Regression of Y on X Slope , mw = 0.0551 Intercept, bw = -0.4575 Correlation coefficient* = 0.9969 *If Correlation Coefficient < 0.990, check and recalibrate. **Set Point Calculation** From the TSP Field Calibration Curve, take Qstd = 43 CFM From the Regression Equation, the "Y" value according to mw x Qstd + bw = $[\Delta W \times (Pa/760) \times (298/Ta)]^{1/2}$ Therefore, Set Point; W = $(\text{mw x Qstd} + \text{bw})^2 \times (760 / \text{Pa}) \times (\text{Ta} / 298) =$ 3.76 Remarks: Conducted by: Wong Shing Kwai Checked by: Henry Leung



Certificate of Calibration

Τt	is certified that the i	item under calibration	has been calibrated by c	orresponding calibrate	d High Volume Sample
ıι	is confined that the	nem unuel cambianon	nas occii candiaicu ov c	onesponding campiate	a i ngn yorunc sambi

Description:	Laser Dust Mo	nitor		Date of	f Calibration	30-Jul-25		
Manufacturer:	Sibata Scientif	ic Technology LTD.		Validity of Calibra	tion Record	30-Sep-25		
Model No.:	LD-3B							
Serial No.:	2Y6194							
Equipment No.:	SA-01-02		Sensitivity	0.001 mg/m3				
High Volume Sa		A-01-03	Before Sensi	tivity Adjustment	578			
Tisch Calibratio	n Orifice No.:	3864	After Sensiti	vity Adjustment	578			
			Calibration of 1 hr T	SP				
Calibration		Laser Dust Monit			HVS			
Point	Total Count	Count / X-a		Mass	concentration (μ Y-axis	ıg/m³)		
1	4000	76	.0		143.0			
2	3600	64	.0	115.0				
3 3000 53.0				104.0				
Avei	rage	64	.3		120.7			
Slope , mw =	Slope , mw = 1.7053 Intercept, bw = 10.9597 Correlation coefficient* = 0.9756							
Set Correlation l SCF = [K=High		oler / Dust Meter, (μ :	g/m3)]	1.9				
The Dust Monito (CF) between the	or was compared e Dust Monitor	the instruction manual with a calibrated High and High Volume Samed by HOKLAS labor	h Volume Sampler and pler.		d to generate the	Correlation Factor		
Calibrated by: Techni	cal Officer (Wor	ng Shing Kwai)	_	Approved by: _	Project Manager	(Henry Leung)		

Digital Dust Indicator



Date of Calibration 30-Jul-25

Certificate of Calibration

Description:

Manufacturer: Sibata Scientific Technology LTD.		_	Validity of Calibration Record 30-Sep-25						
Model No.:	LD-5R								
Serial No.:	8Y2374								
Equipment No.:	SA-01-04		Sensitivity	0.001 mg/m3					
High Volume Sa	mpler No.:	A-01-03	Before Sensitiv	ity Adjustment	652				
Tisch Calibration	orifice No.:	3864	After Sensitivi	ty Adjustment	652				
		Cal	libration of 1 hi	· TSP					
Calibration		Laser Dust Monitor			HVS				
Point	M	Iass Concentration (μg/1	m3)	Mass concentration (μg/m ³)					
X-axis					Y-axis				
2	76.0 67.0			130.0 122.0					
3		52.0			103.0				
Average		65.0			118.3				
- ´	Slope , mw = 1.1395								
		Set	t Correlation F	actor					
Particaulate Con	centration by I	High Volume Sampler ($\mu g/m^3$)		118.3				
Particaulate Con	centration by I	Oust Meter (μg/m ³)			65.0				
Measureing time					60.0				
Set Correlation F SCF = [K=Higl	•	npler / Dust Meter, (μg	g/m3)]	1.8					
In-house method	in according t	to the instruction manua	ıl:						
The Dust Monitor was compared with a calibrated High Volume Sampler and The result was used to generate the Correlation Factor (CF) between the Dust Monitor and High Volume Sampler. Those filter papers are weighted by HOKLAS laboratory (HPCT Litimed)									
Calibrated by:		M.	_	Approved by:	\-lem	y Xon			
Technica	al Officer (Wo	ng Shing Kwai)		Projec	t Manager (Henry	Leung)			

Digital Dust Indicator



30-Jul-25

Date of Calibration

Certificate of Calibration

Description:

Τŧ	is certified that	the iten	n under ca	libration	has been	calibrated by	corresponding	calibrated High	Volume Samn	ler
ıι	. Is certified that	me nen	i under Ca	11101 au 011 .	nas been	cambrated by	Corresponding	cambrated might	volume Samb	ICI

Manufacturer:	Sibata Scientific Technology LTD.	Validity of Calib	ration Record 30-Sep-25
Model No.:	LD-5R		
Serial No.:	8Y2373		
Equipment No.:	SA-01-05	Sensitivity 0.001 mg/m3	<u>.</u>
High Volume Sa	ampler No.: <u>A-01-03</u>	Before Sensitivity Adjustment	657
Tisch Calibratio	n Orifice No.: 3864	After Sensitivity Adjustment	657
	Ca	libration of 1 hr TSP	
Calibration	Laser Dust Monitor	r	HVS
Point	Mass Concentration (μg/	/m3) Mas	ss concentration (μg/m³)
	X-axis		Y-axis
1	72.0		133.0
2	64.0		114.0
3	56.0		101.0
Average	64.0		116.0
Slope , mw = Correlation co			-12.0000
		et Correlation Factor	
	ncentration by High Volume Sampler	(μg/m³)	116.0
	centration by Dust Meter (μg/m³)		64.0
Measureing time Set Correlation 1	· · · · · · · · · · · · · · · · · · ·		60.0
	h Volume Sampler / Dust Meter, (μ	g/m3)] 1.8	
The Dust Monitor Factor (CF) between	I in according to the instruction manuor was compared with a calibrated Hiween the Dust Monitor and High Volumers are weighted by HOKLAS laborations.	gh Volume Sampler and The result ime Sampler.	was used to generate the Correlation
Calibrated by	al Officer (Wong Shing Kwai)	Approved by: Project	ct Manager (Henry Leung)

Digital Dust Indicator



Date of Calibration 30-Jul-25

Certificate of Calibration

Description:

Manufacturer:	Sibata Scient	ific Technology LTD.		Validity of Calibra	ation Record	30-Sep-25		
Model No.:	LD-5R							
Serial No.:	972777							
Equipment No.:	SA-01-06		Sensitivity	0.001 mg/m3				
High Volume Sa	mpler No.:	A-01-03	Before Sensitiv	vity Adjustment	645			
Tisch Calibration	n Orifice No.:	3864	After Sensitivi	ty Adjustment	645			
		Ca	libration of 1 h	r TSP				
Calibration		Laser Dust Monitor	•		HVS			
Point	M	Iass Concentration (μg/	m3)	Mass concentration (μg/m³)				
	X-axis				Y-axis			
1		76.0			135.0			
2		56.0			115.0			
3		52.0			108.0			
Average		61.3			119.3			
By Linear Regr Slope , mw = Correlation co	1.08			ept, bw =	52.8065			
		Se	t Correlation F	actor				
Particaulate Con-	centration by I	High Volume Sampler ($(\mu g/m^3)$		119.3			
Particaulate Con-	centration by I	Oust Meter (μg/m ³)			61.3			
Measureing time	, (min)				60.0			
Set Correlation F	actor, SCF							
SCF = [K=Higl	n Volume San	npler / Dust Meter, (μ	g/m3)]	1.9				
In-house method	in according t	to the instruction manua	 al:					
The Dust Monito	or was compare	ed with a calibrated Hig	gh Volume Samp	oler and The result	was used to gener	ate the Correlation		
		Monitor and High Volu	=	T N				
Those filter pap	ers are weigh	ted by HOKLAS labo	oratory (HPCT	Litimed)				
Calibrated by:		ng Shing Kwai)	_	Approved by: Projec	lem t Manager (Henry	Leung)		

Digital Dust Indicator



Date of Calibration 30-Jul-25

Certificate of Calibration

Description:

Manufacturer:	Sibata Scient	ific Technology LTD.	_	Validity of Calib	ration Record	30-Sep-25
Model No.:	LD-5R					
Serial No.:	972778					
Equipment No.:	SA-01-07		Sensitivity	0.001 mg/m3	_	
High Volume Sa	mpler No.:	A-01-03	Before Sensiti	vity Adjustment	735 CPM	
Tisch Calibration	n Orifice No.:	3864	After Sensitiv	ity Adjustment	735 CPM	
		Ca	libration of 1 h	r TSP		
Calibration		Laser Dust Monitor	•		HVS	
Point	N.	Iass Concentration (μg/ X-axis	(m3)	Mas	ss concentration (ug/m³)
1		75.0			Y-axis 141.0	
2		63.0			118.0	
3		52.0			105.0	
Average		63.3			121.3	
Slope , mw = Correlation co	1.57 pefficient* =	0.9910		cept, bw =	21.8665	<u>; </u>
		Se	t Correlation F	actor		
	•	High Volume Sampler ($(\mu g/m^3)$		121.3	
	•	Dust Meter (μg/m³)			63.3	
Measureing time					60.0	
Set Correlation I SCF = [K=Hig	-	npler / Dust Meter, (μ	g/m3)]	1.9		
In-house method	in according t	to the instruction manua	al:			
Factor (CF) betw	veen the Dust I	ed with a calibrated Hig Monitor and High Volu Ited by HOKLAS labo	me Sampler.	•	was used to gene	rate the Correlation
Calibrated by:						
		ing Shing Kwai)	_	Approved by:	ct Manager (Henr	y (Leung)

Digital Dust Indicator



30-Jul-25

Date of Calibration

Certificate of Calibration

Description:

-						
Manufacturer:	Sibata Scient	ific Technology LTD.	_	Validity of Calib	ration Record	30-Sep-25
Model No.:	LD-5R					
Serial No.:	972780					
Equipment No.:	SA-01-09		Sensitivity	0.001 mg/m3	_	
High Volume Sa	impler No.:	A-01-03	Before Sensitiv	ity Adjustment	739 CPM	
Tisch Calibratio	n Orifice No.:	3864	After Sensitivit	y Adjustment	739 CPM	
		Ca	libration of 1 hi	TSP		
Calibration		Laser Dust Monitor	•		HVS	
Point	N.	lass Concentration (µg/	m3)	Mas	ss concentration (ug/m³)
		X-axis			Y-axis	
1		76.0			134.0	
2		62.0			113.0	
3		56.0			100.0	
Average		64.7			115.7	
Slope , mw = Correlation co		0.9958		ept, bw =	8.0253	
		Se	t Correlation Fa	ictor		
Particaulate Con	centration by l	High Volume Sampler ($(\mu g/m^3)$		115.7	
Particaulate Con	centration by l	Dust Meter (μg/m³)			64.7	
Measureing time	e, (min)				60.0	
Set Correlation 1	Factor, SCF					
SCF = [K=High Volume Sampler / Dust Meter, (µg/m3)] 1.8						
In-house method	l in according t	to the instruction manua	al:			
Factor (CF) betw	veen the Dust I	ed with a calibrated Hig Monitor and High Volunted by HOKLAS laborated	me Sampler.		was used to gene	rate the Correlation
Calibrated by		ong Shing Kwai)	_		-lem	/ /
1 ecililic	ai Officei (WO	ng sining ixwai)		110,100	or manager (116111)	y Louing)

Digital Dust Indicator



30-Jul-25

Date of Calibration

Certificate of Calibration

Description:

-						
Manufacturer:	Sibata Scient	ific Technology LTD.	_	Validity of Calib	ration Record	30-Sep-25
Model No.:	LD-5R					
Serial No.:	972781					
Equipment No.:	SA-01-10		Sensitivity	0.001 mg/m3	_	
High Volume Sa	mpler No.:	A-01-03	Before Sensitiv	rity Adjustment	734 CPM	
Tisch Calibration	n Orifice No.:	3864	After Sensitivit	y Adjustment	734 CPM	
		Ca	libration of 1 hr	TSP		
Calibration		Laser Dust Monitor			HVS	
Point	M	fass Concentration (μg/	m3)	Mas	ss concentration (µ	ug/m³)
		X-axis			Y-axis	
1		75.0			132.0	
2		66.0			115.0	
3		55.0			101.0	
Average		65.3			116.0	
Slope , mw = Correlation co		99 0.9936		ept, bw =	15.3953	
		Se	t Correlation Fa	ictor		
Particaulate Con	centration by I	High Volume Sampler ($(\mu g/m^3)$		116.0	
Particaulate Con	centration by I	Dust Meter (μg/m³)			65.3	
Measureing time	e, (min)				60.0	
Set Correlation I	Factor, SCF					
SCF = [K=High Volume Sampler / Dust Meter, (µg/m3)] 1.8						
In-house method	l in according t	to the instruction manua	al:			
Factor (CF) betw	veen the Dust I	ed with a calibrated Hig Monitor and High Volu Ited by HOKLAS labo	me Sampler.		was used to gener	rate the Correlation
Calibrated by:		ong Shing Kwai)	_	Approved by: Projec	Ct Manager (Henry	Leung)

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 00964 | Issue Date : 30 Dec 2024

Application No. : HP00820

Certificate of Calibration

Applicant : Cinotech Consultants Limited

RM 1710, Technology Park,

18 On Lai Street,

Shatin, N.T., Hong Kong

Sample Description : Submitted equipment stated to be Sound Level Calibrator.

Equipment No.: : N-16-01

Manufacturer: : Hangzhou Aihua Instruments Co., Ltd.

Other information : Model No.

Model No. AWA6021A
Serial No. 1023253

Date Received : 27 Dec 2024

Test Period : 30 Dec 2024 to 30 Dec 2024

Test Requested : Performance checking for Sound Level Calibrator

Test Method : The Sound Level Meter and Calibrator has been calibrated in accordance with

the documented procedures and using standard and instrument which are

recommended by the manufacturer, or equivalent.

Test conditions : Room Temperature: 22-25 degree Celsius

Relative Humidity: 35-70%

Test Result : Refer to the test result(s) on page 2.

Remark : 1. Information of the sample description provided by the Applicant.

2. The result(s) relate only to the items tested or calibrated.

For and on behalf of HIGH PRECISION CHEMICAL TESTING LIMITED

Lee Wai Kit Laboratory Manager

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 00964 | Issue Date : 30 Dec 2024

Application No. : HP00820

Certificate of Calibration

Measuring equipment

Description	Sound Calibrator
Manufacturer	Brüel & Kjær
Model No.	TYPE 4231
Serial No.	2326353
Equipment No.	N-02-01

Description	Sound Meter
Manufacturer	BSWA Technology
Model No.	BSWA 308
Serial No.	570183
Microphone No.	570605
Equipment No.	N-12-01

Test Result

Reference value, dB	Indication value, dB	Deviation, dB	Allowed deviation, dB
94.0	94.3	+ 0.3	± 0.3
114.0	114.3	+ 0.3	± 0.5

Note

- : 1. "Instrument Readings" presents the figures shown on item under calibration / checking regardless of equipment precision or significant figures.
 - 2. The indication value was obtained from the average of ten replicated measurement.

- End of report -

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 01015 Issue Date : 04 Feb 2025

Application No. : HP00868

Certificate of Calibration

Applicant : Cinotech Consultants Limited

RM 1710, Technology Park,

18 On Lai Street,

Shatin, N.T., Hong Kong

Sample Description : Submitted equipment stated to be Sound Level Calibrator.

Equipment No.: : N-16-02

Manufacturer: : Hangzhou Aihua Instruments Co., Ltd.

Other information : Model No. AWA6021A

Serial No. 1023064

Date Received : 28 Jan 2025

Test Period : 03 Feb 2025 to 04 Feb 2025

Test Requested : Performance checking for Sound Level Calibrator

Test Method : The Sound Level Meter and Calibrator has been calibrated in accordance with

the documented procedures and using standard and instrument which are

recommended by the manufacturer, or equivalent.

Test conditions : Room Temperature: 22-25 degree Celsius

Relative Humidity: 35-70%

Test Result : Refer to the test result(s) on page 2.

Remark : 1. Information of the sample description provided by the Applicant.

2. The result(s) relate only to the items tested or calibrated.

For and on behalf of HIGH PRECISION CHEMICAL TESTING LIMITED

Lee Wai Kit Laboratory Manager

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 01015 Issue Date : 04 Feb 2025

Application No. : HP00868

Certificate of Calibration

Measuring equipment

Description	Sound Calibrator
Manufacturer	Brüel & Kjær
Model No.	TYPE 4231
Serial No.	2326353
Equipment No.	N-02-01

Description	Sound Meter
Manufacturer	SVANTEK
Model No.	SVAN 977
Serial No.	92677
Microphone No.	10352
Equipment No.	N-14-01

Test Result

Reference value, dB	Indication value, dB	Deviation, dB	Allowed deviation, dB
94.0	94.2	+ 0.2	± 0.3
114.0	114.3	+ 0.3	± 0.5

Note

- : 1. "Instrument Readings" presents the figures shown on item under calibration / checking regardless of equipment precision or significant figures.
 - 2. The indication value was obtained from the average of ten replicated measurement.

- End of report -

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 00870 | Issue Date : 14 Oct 2024

Application No. : HP00731

Certificate of Calibration

Applicant : Cinotech Consultants Limited

RM 1710, Technology Park,

18 On Lai Street,

Shatin, N.T., Hong Kong

Sample Description : Submitted equipment stated to be Integrating Sound Level Meter.

Equipment No.: : N-08-12

Manufacturer: : SVANTEK

Other information : N

Model No.	SVAN 957
Serial No.	23851
Microphone No.	22391

Date Received : 07 Oct 2024

Test Period : 09 Oct 2024 to 09 Oct 2024

Test Requested : Performance checking for Sound Level Meter

Test Method : The Sound Level Calibrator has been calibrated in accordance with the

documented procedures and using standard and instrument which are

recommended by the manufacturer, or equivalent.

Test conditions : Room Temperature: 22-25 degree Celsius

Relative Humidity: 35-70%

Test Result : Refer to the test result(s) on page 2.

Remark: 1. Information of the sample description provided by the Applicant.

2. The result(s) relate only to the items tested or calibrated.

For and on behalf of HIGH PRECISION CHEMICAL TESTING LIMITED

Lee Wai Kit Laboratory Manager

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Application No. : HP00731

Certificate of Calibration

Measuring equipment

Description	Sound Calibrator
Manufacturer	Brüel & Kjær
Model No.	TYPE 4231
Serial No.	2326353
Equipment No.	N-02-01

Test Result :

Reference value, dB	Indication value, dB	Deviation, dB	Allowed deviation, dB
94.0	94.0	± 0.0	± 1.5
114.0	114.2	+ 0.2	± 1.5

Note

- : 1. "Instrument Readings" presents the figures shown on item under calibration / checking regardless of equipment precision or significant figures.
 - 2. The indication value was obtained from the average of ten replicated measurement.

- End of report -

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 00871 Issue Date : 14 Oct 2024

Application No. : HP00732

Certificate of Calibration

Applicant : Cinotech Consultants Limited

RM 1710, Technology Park,

18 On Lai Street,

Shatin, N.T., Hong Kong

Sample Description : Submitted equipment stated to be Integrating Sound Level Meter.

Equipment No.: : N-12-02

Manufacturer: : BSWA Technology

Other information : N

Model No.	BSWA 308
Serial No.	570187
Microphone No.	590079

Date Received : 07 Oct 2024

Test Period : 09 Oct 2024 to 09 Oct 2024

Test Requested : Performance checking for Sound Level Meter

Test Method : The Sound Level Calibrator has been calibrated in accordance with the

documented procedures and using standard and instrument which are

recommended by the manufacturer, or equivalent.

Test conditions : Room Temperature: 22-25 degree Celsius

Relative Humidity: 35-70%

Test Result : Refer to the test result(s) on page 2.

Remark: 1. Information of the sample description provided by the Applicant.

2. The result(s) relate only to the items tested or calibrated.

For and on behalf of HIGH PRECISION CHEMICAL TESTING LIMITED

Lee Wai Kit Laboratory Manager

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Application No. : HP00732

Certificate of Calibration

Measuring equipment

Description	Sound Calibrator
Manufacturer	Brüel & Kjær
Model No.	TYPE 4231
Serial No.	2326353
Equipment No.	N-02-01

Test Result :

Reference value, dB	Indication value, dB	Deviation, dB	Allowed deviation, dB
94.0	93.9	- 0.1	± 1.5
114.0	113.7	- 0.3	± 1.5

Note

- : 1. "Instrument Readings" presents the figures shown on item under calibration / checking regardless of equipment precision or significant figures.
 - 2. The indication value was obtained from the average of ten replicated measurement.

- End of report -

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 01074 Issue Date : 19 Mar 2025

Application No. : HP00912

Certificate of Calibration

Applicant : Cinotech Consultants Limited

RM 1710, Technology Park,

18 On Lai Street,

Shatin, N.T., Hong Kong

Sample Description : Submitted equipment stated to be Integrating Sound Level Meter.

Equipment No.: : N-12-03

Manufacturer: : BSWA Technology

Other information : Mod

Model No.	BSWA 308
Serial No.	570188
Microphone No.	570608

Date Received : 17 Mar 2025

Test Period : 18 Mar 2025 to 18 Mar 2025

Test Requested : Performance checking for Sound Level Meter

Test Method : The Sound Level Calibrator has been calibrated in accordance with the

documented procedures and using standard and instrument which are

recommended by the manufacturer, or equivalent.

Test conditions : Room Temperature: 22-25 degree Celsius

Relative Humidity: 35-70%

Test Result : Refer to the test result(s) on page 2.

Remark: 1. Information of the sample description provided by the Applicant.

2. The result(s) relate only to the items tested or calibrated.

For and on behalf of HIGH PRECISION CHEMICAL TESTING LIMITED

Lee Wai Kit Laboratory Manager

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 01074 Issue Date : 19 Mar 2025

Application No. : HP00912

Certificate of Calibration

Measuring equipment

Description	Sound Calibrator
Manufacturer	Brüel & Kjær
Model No.	TYPE 4231
Serial No.	2326353
Equipment No.	N-02-01

Test Result

Reference value, dB	Indication value, dB	Deviation, dB	Allowed deviation, dB
94.0	93.9	- 0.1	± 1.5
114.0	114.0	± 0.0	± 1.5

Note

- : 1. "Instrument Readings" presents the figures shown on item under calibration / checking regardless of equipment precision or significant figures.
 - 2. The indication value was obtained from the average of ten replicated measurement.

- End of report -

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 01075 Issue Date : 19 Mar 2025

Application No. : HP00913

Certificate of Calibration

Applicant : Cinotech Consultants Limited

RM 1710, Technology Park,

18 On Lai Street,

Shatin, N.T., Hong Kong

Sample Description : Submitted equipment stated to be Integrating Sound Level Meter.

Equipment No.: : N-12-04

Manufacturer: : BSWA Technology

Other information : M

Model No.	BSWA 308
Serial No.	580238
Microphone No.	570605

Date Received : 17 Mar 2025

Test Period : 18 Mar 2025 to 18 Mar 2025

Test Requested : Performance checking for Sound Level Meter

Test Method : The Sound Level Calibrator has been calibrated in accordance with the

documented procedures and using standard and instrument which are

recommended by the manufacturer, or equivalent.

Test conditions : Room Temperature: 22-25 degree Celsius

Relative Humidity: 35-70%

Test Result : Refer to the test result(s) on page 2.

Remark: 1. Information of the sample description provided by the Applicant.

2. The result(s) relate only to the items tested or calibrated.

For and on behalf of HIGH PRECISION CHEMICAL TESTING LIMITED

Lee Wai Kit Laboratory Manager

Rm 1904, Technology Park 18 On Lai Street, Shatin

NT, Hong Kong

Tel: +852 3841 4388 Website: https://www.hpct.com.hk



Report No. : 01075 Issue Date : 19 Mar 2025

Application No. : HP00913

Certificate of Calibration

Measuring equipment

Description	Sound Calibrator	
Manufacturer	Brüel & Kjær	
Model No.	TYPE 4231	
Serial No.	2326353	
Equipment No.	N-02-01	

Test Result

Reference value, dB	Indication value, dB	Deviation, dB	Allowed deviation, dB
94.0	94.2	+ 0.2	± 1.5
114.0	114.1	+ 0.1	± 1.5

Note

- : 1. "Instrument Readings" presents the figures shown on item under calibration / checking regardless of equipment precision or significant figures.
 - 2. The indication value was obtained from the average of ten replicated measurement.

- End of report -

APPENDIX C WEATHER INFORMATION

Appendix C - Weather Conditions During Impact Monitoring Period

Date	Mean Air Temperature (°C) ¹	Mean Relative Humidity	Precipitation (mm) ³
1 4 25	20.1	(%) ²	2.0
1-Aug-25	30.1	79	3.0
2-Aug-25	28.1	90	109.0
3-Aug-25	29.2	86	47.5
4-Aug-25	28.8	88	72.2
5-Aug-25	27.1	92	368.9
6-Aug-25	27.5	87	6.8
7-Aug-25	29.3	80	0.0
8-Aug-25	29.8	79	0.0
9-Aug-25	30.1	78	0.0
10-Aug-25	30.5	77	0.0
11-Aug-25	29.7	77	0.3
12-Aug-25	29.8	77	8.5
13-Aug-25	30.1	77	0.0
14-Aug-25	26.3	91	117.4
15-Aug-25	27.5	86	4.3
16-Aug-25	29.3	76	0.0
17-Aug-25	27.3	84	41.5
18-Aug-25	26.6	92	80.1
19-Aug-25	27.1	94	68.9
20-Aug-25	29.0	82	0.2
21-Aug-25	29.6	79	0.0
22-Aug-25	29.7	71	0.0
23-Aug-25	30.0	73	0.2
24-Aug-25	29.6	79	0.0
25-Aug-25	29.4	76	0.1
26-Aug-25	30.3	72	0.0
27-Aug-25	29.8	74	0.0
28-Aug-25	28.9	77	2.7
29-Aug-25	30.2	72	0.5
30-Aug-25	29.4	77	7.1
31-Aug-25	29.8	75	0.0

(Reporting Month: August 2025)

Remarks:

Source - Hong Kong Observatory

¹⁻³Retrieved from Manned Weather Station (Hong Kong Observatory) (22°18'07" N, 114°10'27" E)

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
1 Aug 2025	12:00 AM	SSE	0.7	
1 Aug 2025	1:00 AM	S	0.6	
1 Aug 2025	2:00 AM	S	0.5	
1 Aug 2025	3:00 AM	S	0.6	
1 Aug 2025	4:00 AM	S	0.6	
1 Aug 2025	5:00 AM	SSW	0.4	
1 Aug 2025	6:00 AM	SSW	0.4	
1 Aug 2025	7:00 AM	SSW	0.3	
1 Aug 2025	8:00 AM	SSW	0.4	
1 Aug 2025	9:00 AM	SSW	0.3	
1 Aug 2025	10:00 AM	SSW	0.2	
1 Aug 2025	11:00 AM	SSW	0.3	
1 Aug 2025	12:00 PM	SSW	0.3	
1 Aug 2025	1:00 PM	S	0.2	
1 Aug 2025	2:00 PM	SSW	0.2	
1 Aug 2025	3:00 PM	S	0.2	
1 Aug 2025	4:00 PM	SSW	0.4	
1 Aug 2025	5:00 PM	SSW	0.4	
1 Aug 2025	6:00 PM	S	0.1	
1 Aug 2025	7:00 PM	SSE	0.0	
1 Aug 2025	8:00 PM	SW	0.2	
1 Aug 2025	9:00 PM	SSW	0.3	
1 Aug 2025	10:00 PM	SSW	0.2	
1 Aug 2025	11:00 PM	W	0.0	
2 Aug 2025	12:00 AM	ESE	0.0	
2 Aug 2025	1:00 AM	WNW	0.0	
2 Aug 2025	2:00 AM	SW	0.1	
2 Aug 2025	3:00 AM	NNW	0.0	
2 Aug 2025	4:00 AM	NW	0.1	
2 Aug 2025	5:00 AM	SW	0.1	
2 Aug 2025	6:00 AM	S	0.3	
2 Aug 2025	7:00 AM	SW	0.3	
2 Aug 2025	8:00 AM	WNW	0.1	
2 Aug 2025	9:00 AM	WNW	0.1	
2 Aug 2025	10:00 AM	NE	0.1	
2 Aug 2025	11:00 AM	N	0.0	
2 Aug 2025	12:00 PM	NW	0.1	
2 Aug 2025	1:00 PM	NW	0.1	
2 Aug 2025	2:00 PM	W	0.3	
2 Aug 2025	3:00 PM	WSW	0.3	
2 Aug 2025	4:00 PM	WSW	0.4	
2 Aug 2025	5:00 PM	SW	0.4	
2 Aug 2025	6:00 PM	SW	0.3	
2 Aug 2025	7:00 PM	NW	0.4	
2 Aug 2025	8:00 PM	W	0.2	
2 Aug 2025	9:00 PM	S	0.1	
2 Aug 2025	10:00 PM	NNE	0.1	
2 Aug 2025	11:00 PM	ENE	0.1	
3 Aug 2025	12:00 AM	S	0.4	
3 Aug 2025	1:00 AM	SE	0.4	
3 Aug 2025	2:00 AM	NNE	0.2	
3 Aug 2025	3:00 AM	WNW	0.1	
3 Aug 2025	4:00 AM	WNW	0.0	
3 Aug 2025	5:00 AM	SSW	0.1	
3 Aug 2025	6:00 AM	NNW	0.0	
3 Aug 2025	7:00 AM	SW	0.3	
3 Aug 2025	8:00 AM	S	0.3	

August 2025				
Wind Speed and Directions				
Date	Time	Direction	Wind Speed m-s	
3 Aug 2025	9:00 AM	SE	0.4	
3 Aug 2025	10:00 AM	S	0.4	
3 Aug 2025	11:00 AM	WNW	0.2	
3 Aug 2025	12:00 PM	NW	0.4	
3 Aug 2025	1:00 PM	WNW	0.2	
3 Aug 2025	2:00 PM	WSW	0.3	
3 Aug 2025	3:00 PM	WSW	0.2	
3 Aug 2025	4:00 PM	ESE	0.3	
3 Aug 2025	5:00 PM	S	0.1	
3 Aug 2025	6:00 PM	ESE	0.1	
3 Aug 2025	7:00 PM	ESE	0.0	
3 Aug 2025	8:00 PM	ESE	0.0	
3 Aug 2025	9:00 PM	ESE	0.0	
3 Aug 2025	10:00 PM	W	0.0	
3 Aug 2025	11:00 PM	WNW	0.0	
4 Aug 2025	12:00 AM	SSW	0.0	
4 Aug 2025	1:00 AM	SE	0.0	
4 Aug 2025	2:00 AM	Е	0.0	
4 Aug 2025	3:00 AM	ESE	0.0	
4 Aug 2025	4:00 AM	ESE	0.0	
4 Aug 2025	5:00 AM	SE	0.2	
4 Aug 2025	6:00 AM	S	0.5	
4 Aug 2025	7:00 AM	S	0.4	
4 Aug 2025	8:00 AM	S	0.3	
4 Aug 2025	9:00 AM	S	0.6	
4 Aug 2025	10:00 AM	S	0.7	
4 Aug 2025	11:00 AM	S	0.5	
4 Aug 2025	12:00 PM	SSE	0.6	
4 Aug 2025	1:00 PM	ESE	0.5	
4 Aug 2025	2:00 PM	ESE	0.3	
4 Aug 2025	3:00 PM	S	0.2	
4 Aug 2025	4:00 PM	SSW	0.1	
4 Aug 2025	5:00 PM	S	0.1	
4 Aug 2025	6:00 PM	SSW	0.3	
4 Aug 2025	7:00 PM	W	0.1	
4 Aug 2025	8:00 PM	SSW	0.0	
4 Aug 2025	9:00 PM	ESE	0.0	
4 Aug 2025	10:00 PM	W	0.1	
4 Aug 2025	11:00 PM	WNW	0.1	
5 Aug 2025	12:00 AM	SW	0.1	
5 Aug 2025	1:00 AM	S	0.0	
5 Aug 2025	2:00 AM	SSW	0.0	
5 Aug 2025	3:00 AM	W	0.0	
5 Aug 2025	4:00 AM	SW	0.0	
5 Aug 2025	5:00 AM	S	0.2	
5 Aug 2025	6:00 AM	SSW	0.4	
5 Aug 2025	7:00 AM	SW	0.5	
5 Aug 2025	8:00 AM	SW	0.5	
5 Aug 2025	9:00 AM	SSW	0.8	
5 Aug 2025	10:00 AM	S	0.8	
5 Aug 2025	11:00 AM	SSW	0.6	
5 Aug 2025	12:00 PM	SW	0.8	
5 Aug 2025	1:00 PM	S	0.7	
5 Aug 2025	2:00 PM	SSW	1.0	
5 Aug 2025	3:00 PM	SSW	0.8	
5 Aug 2025	4:00 PM	S	0.6	
5 Aug 2025	5:00 PM	SSW	0.7	

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
5 Aug 2025	6:00 PM	SW	0.6	
5 Aug 2025	7:00 PM	SW	0.7	
5 Aug 2025	8:00 PM	SSW	0.4	
5 Aug 2025	9:00 PM	SSW	0.3	
5 Aug 2025	10:00 PM	SSW	0.4	
5 Aug 2025	11:00 PM	SW	0.5	
6 Aug 2025	12:00 AM	SSW	0.3	
6 Aug 2025	1:00 AM	SW	0.4	
6 Aug 2025	2:00 AM	SSW	0.4	
6 Aug 2025	3:00 AM	SSW	0.4	
6 Aug 2025	4:00 AM	S	0.4	
6 Aug 2025	5:00 AM	SW	0.7	
6 Aug 2025	6:00 AM	SSW	0.8	
6 Aug 2025	7:00 AM	SSW	0.6	
6 Aug 2025	8:00 AM	SSW	0.9	
6 Aug 2025	9:00 AM	SSW	0.8	
6 Aug 2025	10:00 AM	SW	0.9	
6 Aug 2025	11:00 AM	SSW	0.8	
6 Aug 2025	12:00 PM	SSW	0.6	
6 Aug 2025	1:00 PM	SW	0.7	
6 Aug 2025	2:00 PM	SSW	0.6	
6 Aug 2025	3:00 PM	SW	0.6	
6 Aug 2025	4:00 PM	S	0.5	
6 Aug 2025	5:00 PM	S	0.5	
6 Aug 2025	6:00 PM	SW	0.6	
6 Aug 2025	7:00 PM	SW	0.4	
6 Aug 2025	8:00 PM	SSW	0.5	
6 Aug 2025	9:00 PM	SSW	0.3	
6 Aug 2025	10:00 PM	S	0.3	
6 Aug 2025	11:00 PM	SW	0.4	
7 Aug 2025	12:00 AM	SSW	0.3	
7 Aug 2025	1:00 AM	WSW	0.3	
7 Aug 2025	2:00 AM	SW	0.4	
7 Aug 2025	3:00 AM	SSW	0.4	
7 Aug 2025	4:00 AM	SSW	0.4	
7 Aug 2025	5:00 AM	SW	0.4	
7 Aug 2025	6:00 AM	SSW	0.2	
7 Aug 2025	7:00 AM	S	0.6	
7 Aug 2025	8:00 AM	SSW	0.7	
7 Aug 2025	9:00 AM	S	0.7	
7 Aug 2025	10:00 AM	SW	0.9	
7 Aug 2025	11:00 AM	SW	0.7	
7 Aug 2025	12:00 PM	SW	0.7	
7 Aug 2025	1:00 PM	SW	0.7	
7 Aug 2025	2:00 PM	SSW	0.8	
7 Aug 2025	3:00 PM	SSW	0.6	
7 Aug 2025	4:00 PM	SW	0.4	
7 Aug 2025	5:00 PM	SW	0.5	
7 Aug 2025	6:00 PM	SW	0.3	
7 Aug 2025	7:00 PM	SSW	0.5	
7 Aug 2025	8:00 PM	SSW	0.3	
7 Aug 2025	9:00 PM	SSW	0.2	
7 Aug 2025	10:00 PM	SW	0.2	
7 Aug 2025	11:00 PM	SW	0.1	
8 Aug 2025	12:00 AM	WSW	0.1	
8 Aug 2025	1:00 AM	ESE	0.1	
8 Aug 2025	2:00 AM	SE	0.0	

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
8 Aug 2025	3:00 AM	Е	0.0	
8 Aug 2025	4:00 AM	SE	0.1	
8 Aug 2025	5:00 AM	SSW	0.4	
8 Aug 2025	6:00 AM	SSW	0.3	
8 Aug 2025	7:00 AM	SW	0.4	
8 Aug 2025	8:00 AM	SW	0.6	
8 Aug 2025	9:00 AM	SSW	0.6	
8 Aug 2025	10:00 AM	SW	0.6	
8 Aug 2025	11:00 AM	W	0.9	
8 Aug 2025	12:00 PM	SW	0.6	
8 Aug 2025	1:00 PM	WSW	0.7	
8 Aug 2025	2:00 PM	SW	0.6	
8 Aug 2025	3:00 PM	WSW	0.3	
8 Aug 2025	4:00 PM	W	0.4	
8 Aug 2025	5:00 PM	WSW	0.4	
8 Aug 2025	6:00 PM	SW	0.1	
8 Aug 2025	7:00 PM	NW	0.2	
8 Aug 2025	8:00 PM	SW	0.2	
8 Aug 2025	9:00 PM	W	0.1	
8 Aug 2025	10:00 PM	SW	0.4	
8 Aug 2025	11:00 PM	SW	0.1	
9 Aug 2025	12:00 AM	SW	0.0	
9 Aug 2025	1:00 AM	WSW	0.1	
9 Aug 2025	2:00 AM	SSW	0.0	
9 Aug 2025	3:00 AM	WSW	0.0	
9 Aug 2025	4:00 AM	WSW	0.0	
9 Aug 2025	5:00 AM	S	0.2	
9 Aug 2025	6:00 AM	S	0.3	
9 Aug 2025	7:00 AM	SW	0.5	
9 Aug 2025	8:00 AM	SW	0.8	
9 Aug 2025	9:00 AM	SW	0.6	
9 Aug 2025	10:00 AM	SW	0.7	
9 Aug 2025	11:00 AM	WSW	0.7	
9 Aug 2025	12:00 PM	WSW	0.9	
9 Aug 2025	1:00 PM	SSW	0.9	
9 Aug 2025	2:00 PM	SW	0.5	
9 Aug 2025	3:00 PM	WNW	0.3	
9 Aug 2025	4:00 PM	S	0.2	
9 Aug 2025	5:00 PM	W	0.2	
9 Aug 2025	6:00 PM	SSW	0.2	
9 Aug 2025	7:00 PM	SW	0.1	
9 Aug 2025	8:00 PM	WSW	0.2	
9 Aug 2025	9:00 PM	SSW	0.2	
9 Aug 2025	10:00 PM	SW	0.1	
9 Aug 2025	11:00 PM	SSW	0.2	
10 Aug 2025	12:00 AM	W	0.0	
10 Aug 2025	1:00 AM	WSW	0.0	
10 Aug 2025	2:00 AM	S	0.0	
10 Aug 2025	3:00 AM	SW	0.1	
10 Aug 2025	4:00 AM	SW	0.2	
10 Aug 2025	5:00 AM	SSW	0.3	
10 Aug 2025	6:00 AM	SSW	0.4	
10 Aug 2025	7:00 AM	SW	0.4	
10 Aug 2025	8:00 AM	S	0.4	
10 Aug 2025	9:00 AM	SSW	0.3	
10 Aug 2025	10:00 AM	SW	0.5	
10 Aug 2025	11:00 AM	WSW	0.4	

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
10 Aug 2025	12:00 PM	W	0.2	
10 Aug 2025	1:00 PM	W	0.3	
10 Aug 2025	2:00 PM	WSW	0.3	
10 Aug 2025	3:00 PM	W	0.3	
10 Aug 2025	4:00 PM	SW	0.5	
10 Aug 2025	5:00 PM	SSW	0.4	
10 Aug 2025	6:00 PM	WSW	0.6	
10 Aug 2025	7:00 PM	SSW	0.4	
10 Aug 2025	8:00 PM	S	0.5	
10 Aug 2025	9:00 PM	SSW	0.4	
10 Aug 2025	10:00 PM	SSW	0.4	
10 Aug 2025	11:00 PM	SW	0.4	
11 Aug 2025	12:00 AM	S	0.4	
11 Aug 2025	1:00 AM	SSW	0.5	
11 Aug 2025	2:00 AM	SW	0.6	
11 Aug 2025	3:00 AM	SSW	0.6	
11 Aug 2025	4:00 AM	SSW	0.5	
11 Aug 2025	5:00 AM	SSW	0.6	
11 Aug 2025	6:00 AM	SSE	0.7	
11 Aug 2025	7:00 AM	S	0.6	
11 Aug 2025	8:00 AM	SSW	0.9	
11 Aug 2025	9:00 AM	SW	1.2	
11 Aug 2025	10:00 AM	SSW	1.0	
11 Aug 2025	11:00 AM	S	0.9	
11 Aug 2025	12:00 PM	SSW	1.0	
11 Aug 2025	1:00 PM	S	0.9	
11 Aug 2025	2:00 PM	SW	0.7	
11 Aug 2025	3:00 PM	SSW	0.9	
11 Aug 2025	4:00 PM	SSW	0.9	
11 Aug 2025	5:00 PM	SW	0.5	
11 Aug 2025	6:00 PM	SSW	0.4	
11 Aug 2025	7:00 PM	SSW	0.1	
11 Aug 2025	8:00 PM	S	0.4	
11 Aug 2025	9:00 PM	SSW	0.5	
11 Aug 2025	10:00 PM	SW	0.5	
11 Aug 2025	11:00 PM	SSW	0.4	
12 Aug 2025	12:00 AM	SW	0.6	
12 Aug 2025	1:00 AM	SSW	0.5	
12 Aug 2025	2:00 AM	SSW	0.4	
12 Aug 2025	3:00 AM	SSW	0.3	
12 Aug 2025	4:00 AM	SSW	0.4	
12 Aug 2025	5:00 AM	SSW	0.6	
12 Aug 2025	6:00 AM	SSW	0.6	
12 Aug 2025	7:00 AM	SSW	0.6	
12 Aug 2025	8:00 AM	SSW	0.7	
12 Aug 2025	9:00 AM	SSW	0.8	
12 Aug 2025	10:00 AM	SW	0.6	
12 Aug 2025	11:00 AM	SSW	0.4	
12 Aug 2025	12:00 PM	SW	0.5	
12 Aug 2025	1:00 PM	SW	0.6	
12 Aug 2025	2:00 PM	SW	0.5	
12 Aug 2025	3:00 PM	WSW	0.5	
12 Aug 2025	4:00 PM	WNW	0.2	
12 Aug 2025	5:00 PM	NW	0.2	
12 Aug 2025	6:00 PM	WNW	0.3	
12 Aug 2025	7:00 PM	WSW	0.4	
12 Aug 2025	8:00 PM	SW	0.3	

August 2025			
Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s
12 Aug 2025	9:00 PM	SSE	0.2
12 Aug 2025	10:00 PM	SSW	0.5
12 Aug 2025	11:00 PM	SSE	0.8
13 Aug 2025	12:00 AM	S	0.8
13 Aug 2025	1:00 AM	ENE	0.8
13 Aug 2025	2:00 AM	SSE	0.8
13 Aug 2025	3:00 AM	SSW	0.4
13 Aug 2025	4:00 AM	WSW	0.7
13 Aug 2025	5:00 AM	SSE	0.4
13 Aug 2025	6:00 AM	SSW	1.0
13 Aug 2025	7:00 AM	S	0.2
13 Aug 2025	8:00 AM	Е	0.8
13 Aug 2025	9:00 AM	SSE	0.4
13 Aug 2025	10:00 AM	SSW	0.6
13 Aug 2025	11:00 AM	SSW	0.3
13 Aug 2025	12:00 PM	SSE	1.0
13 Aug 2025	1:00 PM	ESE	0.9
13 Aug 2025	2:00 PM	SW	0.5
13 Aug 2025	3:00 PM	S	0.6
13 Aug 2025	4:00 PM	W	0.2
13 Aug 2025	5:00 PM	SSW	0.5
13 Aug 2025	6:00 PM	SE	0.4
13 Aug 2025	7:00 PM	SSW	0.9
13 Aug 2025	8:00 PM	SSE	0.6
13 Aug 2025	9:00 PM	SSW	0.4
13 Aug 2025	10:00 PM	S	0.4
13 Aug 2025	11:00 PM	S	0.7
14 Aug 2025	12:00 AM	SSW	0.3
14 Aug 2025	1:00 AM	SSW	0.7
14 Aug 2025	2:00 AM	S	0.8
14 Aug 2025	3:00 AM	S	0.4
14 Aug 2025	4:00 AM	ESE	0.8
14 Aug 2025	5:00 AM	SSW	0.5
14 Aug 2025	6:00 AM	S	0.1
14 Aug 2025	7:00 AM	S	0.8
14 Aug 2025	8:00 AM	SSW	0.1
14 Aug 2025	9:00 AM	S	1.0
14 Aug 2025	10:00 AM	SW	0.5
14 Aug 2025	11:00 AM	SSE	0.4
14 Aug 2025	12:00 PM	SSW	0.6
14 Aug 2025	1:00 PM	S SW	0.8
14 Aug 2025 14 Aug 2025	2:00 PM 3:00 PM	SW	0.6
14 Aug 2025 14 Aug 2025	4:00 PM	S	0.2
14 Aug 2025	5:00 PM	SSW	1.0
14 Aug 2025	6:00 PM	NW	0.3
14 Aug 2025	7:00 PM	ESE	0.9
14 Aug 2025	8:00 PM	S	0.9
14 Aug 2025	9:00 PM	S	0.5
14 Aug 2025	10:00 PM	ESE	0.7
14 Aug 2025	11:00 PM	SW	0.7
15 Aug 2025	12:00 AM	SSW	0.8
15 Aug 2025	1:00 AM	SSW	0.8
15 Aug 2025	2:00 AM	ESE	0.7
15 Aug 2025	3:00 AM	SSE	0.5
15 Aug 2025	4:00 AM	SSW	0.0
15 Aug 2025	5:00 AM	SW	0.8
15 1145 2025	J.00 / 11VI	1 5 11	0.0

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
15 Aug 2025	6:00 AM	SSE	0.6	
15 Aug 2025	7:00 AM	SSW	0.6	
15 Aug 2025	8:00 AM	SW	0.2	
15 Aug 2025	9:00 AM	SSW	0.2	
15 Aug 2025	10:00 AM	SW	0.3	
15 Aug 2025	11:00 AM	S	0.0	
15 Aug 2025	12:00 PM	SSW	0.4	
15 Aug 2025	1:00 PM	SW	0.5	
15 Aug 2025	2:00 PM	SW	0.4	
15 Aug 2025	3:00 PM	S	0.3	
15 Aug 2025	4:00 PM	SSW	0.4	
15 Aug 2025	5:00 PM	WSW	0.3	
15 Aug 2025	6:00 PM	W	0.3	
15 Aug 2025	7:00 PM	S	0.1	
15 Aug 2025	8:00 PM	SSW	0.7	
15 Aug 2025	9:00 PM	ESE	0.3	
15 Aug 2025	10:00 PM	S	0.3	
15 Aug 2025	11:00 PM	WSW	0.3	
16 Aug 2025	12:00 AM	S	0.2	
16 Aug 2025	1:00 AM	S	0.7	
16 Aug 2025	2:00 AM	W	0.3	
16 Aug 2025	3:00 AM	SE	0.1	
16 Aug 2025	4:00 AM	W	0.2	
16 Aug 2025	5:00 AM	SE	0.0	
16 Aug 2025	6:00 AM	W	0.4	
16 Aug 2025	7:00 AM	S	0.9	
16 Aug 2025	8:00 AM	S	0.3	
16 Aug 2025	9:00 AM	SSW	0.3	
16 Aug 2025	10:00 AM	W	0.0	
16 Aug 2025	11:00 AM	SSW	0.4	
16 Aug 2025	12:00 PM	SSE	0.0	
16 Aug 2025	1:00 PM	WNW	0.3	
16 Aug 2025	2:00 PM	SSW	1.0	
16 Aug 2025	3:00 PM	WSW	0.4	
16 Aug 2025	4:00 PM	WNW	0.0	
16 Aug 2025	5:00 PM	S	0.7	
16 Aug 2025	6:00 PM	SW	0.6	
16 Aug 2025	7:00 PM	SSE	0.7	
16 Aug 2025	8:00 PM	WNW	0.3	
16 Aug 2025	9:00 PM	SSE	0.4	
16 Aug 2025	10:00 PM	SSW	0.4	
16 Aug 2025	11:00 PM	ESE	0.7	
17 Aug 2025	12:00 AM	SSW	0.3	
17 Aug 2025	1:00 AM	S	0.3	
17 Aug 2025	2:00 AM	NW	0.1	
17 Aug 2025	3:00 AM	SSE	0.1	
17 Aug 2025	4:00 AM	SW	0.4	
17 Aug 2025	5:00 AM	SW	0.4	
17 Aug 2025	6:00 AM	SE	0.4	
17 Aug 2025	7:00 AM	SSW	0.4	
17 Aug 2025	8:00 AM	SSW	0.4	
17 Aug 2025	9:00 AM	S	0.2	
17 Aug 2025	10:00 AM	SW	0.1	
17 Aug 2025	11:00 AM	SSW	0.2	
17 Aug 2025	12:00 PM	WSW	0.3	
17 Aug 2025	1:00 PM	WSW	0.7	
17 Aug 2025	2:00 PM	SE	0.5	

August 2025			
		and Directions	
Date	Time	Direction	Wind Speed m-s
17 Aug 2025	3:00 PM	WNW	0.2
17 Aug 2025	4:00 PM	S	0.6
17 Aug 2025	5:00 PM	S	0.2
17 Aug 2025	6:00 PM	SW	0.2
17 Aug 2025	7:00 PM	WSW	0.1
17 Aug 2025	8:00 PM	SE	0.1
17 Aug 2025	9:00 PM	S	0.2
17 Aug 2025	10:00 PM	S	0.1
17 Aug 2025	11:00 PM	SSW	0.0
18 Aug 2025	12:00 AM	WNW	0.2
18 Aug 2025	1:00 AM	SSW	0.4
18 Aug 2025	2:00 AM	SSE	0.2
18 Aug 2025	3:00 AM	SSW	0.2
18 Aug 2025	4:00 AM	SSW	0.0
18 Aug 2025	5:00 AM	W	0.0
18 Aug 2025	6:00 AM	S	0.9
18 Aug 2025	7:00 AM	Е	0.5
18 Aug 2025	8:00 AM	WSW	0.2
18 Aug 2025	9:00 AM	W	0.4
18 Aug 2025	10:00 AM	W	0.5
18 Aug 2025	11:00 AM	S	0.1
18 Aug 2025	12:00 PM	WSW	0.4
18 Aug 2025	1:00 PM	SE	0.3
18 Aug 2025	2:00 PM	SSW	0.2
18 Aug 2025	3:00 PM	SSE	0.4
18 Aug 2025	4:00 PM	SSW	0.2
18 Aug 2025	5:00 PM	SW	0.5
18 Aug 2025	6:00 PM	W	0.0
18 Aug 2025	7:00 PM	W	0.2
18 Aug 2025	8:00 PM	SSE	0.2
18 Aug 2025	9:00 PM	WSW	0.1
18 Aug 2025	10:00 PM	SSW	0.1
18 Aug 2025	11:00 PM	SSE	0.4
19 Aug 2025	12:00 AM	SSW	0.3
19 Aug 2025	1:00 AM	SW	0.3
19 Aug 2025	2:00 AM	SW	0.5
19 Aug 2025	3:00 AM	ENE	1.1
19 Aug 2025	4:00 AM	SE	0.2
19 Aug 2025	5:00 AM	SSE	0.1
19 Aug 2025	6:00 AM	SW	0.1
19 Aug 2025	7:00 AM	S	0.3
19 Aug 2025	8:00 AM	ESE	0.3
19 Aug 2025	9:00 AM	WSW	0.2
19 Aug 2025	10:00 AM	SW	0.0
19 Aug 2025	11:00 AM	W	0.2
19 Aug 2025	12:00 PM	W	0.1
19 Aug 2025	1:00 PM	SSE	0.1
19 Aug 2025	2:00 PM	S	0.2
19 Aug 2025	3:00 PM	S	0.1
19 Aug 2025	4:00 PM	WSW	0.3
19 Aug 2025	5:00 PM	Е	0.2
19 Aug 2025	6:00 PM	WSW	0.4
19 Aug 2025	7:00 PM	SSE	0.5
19 Aug 2025	8:00 PM	SW	0.2
19 Aug 2025	9:00 PM	S	0.0
19 Aug 2025	10:00 PM	WSW	0.0
19 Aug 2025	11:00 PM	SSW	0.4

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
20 Aug 2025	12:00 AM	S	0.2	
20 Aug 2025	1:00 AM	SSW	0.2	
20 Aug 2025	2:00 AM	SSE	0.2	
20 Aug 2025	3:00 AM	S	0.1	
20 Aug 2025	4:00 AM	ESE	0.0	
20 Aug 2025	5:00 AM	WSW	0.2	
20 Aug 2025	6:00 AM	W	0.0	
20 Aug 2025	7:00 AM	SSE	0.4	
20 Aug 2025	8:00 AM	SW	0.1	
20 Aug 2025	9:00 AM	SSE	0.1	
20 Aug 2025	10:00 AM	SW	0.1	
20 Aug 2025	11:00 AM	WSW	0.0	
20 Aug 2025	12:00 PM	S	0.9	
20 Aug 2025	1:00 PM	ESE	0.5	
20 Aug 2025	2:00 PM	SSW	0.2	
20 Aug 2025	3:00 PM	SSW	0.3	
20 Aug 2025	4:00 PM	S	0.1	
20 Aug 2025	5:00 PM	ESE	0.3	
20 Aug 2025	6:00 PM	SSW	0.5	
20 Aug 2025	7:00 PM	SW	0.4	
20 Aug 2025	8:00 PM	W	0.3	
20 Aug 2025	9:00 PM	SE	0.6	
20 Aug 2025	10:00 PM	WNW	0.6	
20 Aug 2025	11:00 PM	S	0.3	
21 Aug 2025	12:00 AM	WSW	0.1	
21 Aug 2025	1:00 AM	SE	0.6	
21 Aug 2025	2:00 AM	SSE	0.7	
21 Aug 2025	3:00 AM	SW	0.6	
21 Aug 2025	4:00 AM	SSE	1.0	
21 Aug 2025	5:00 AM	SSW	0.3	
21 Aug 2025	6:00 AM	W	0.3	
21 Aug 2025	7:00 AM	SSW	0.3	
21 Aug 2025	8:00 AM	SW	0.5	
21 Aug 2025	9:00 AM	SSW	0.2	
21 Aug 2025	10:00 AM	WNW	0.3	
21 Aug 2025	11:00 AM	E	0.1	
21 Aug 2025	12:00 PM	S	0.2	
21 Aug 2025	1:00 PM	W	0.2	
21 Aug 2025	2:00 PM	SSW		
21 Aug 2025	3:00 PM	SSE	0.0	
21 Aug 2025	4:00 PM	WNW	0.0	
21 Aug 2025 21 Aug 2025	5:00 PM 6:00 PM	SE S		
21 Aug 2025 21 Aug 2025	7:00 PM	SSW	0.0	
21 Aug 2025 21 Aug 2025	8:00 PM	WSW	0.2	
21 Aug 2025 21 Aug 2025	9:00 PM	SW	0.0	
21 Aug 2025 21 Aug 2025	10:00 PM	SW	0.0	
21 Aug 2025 21 Aug 2025	11:00 PM	NE	0.0	
22 Aug 2025	12:00 AM	NE NE	0.0	
22 Aug 2025	1:00 AM	NE NE	0.0	
22 Aug 2025	2:00 AM	NE NE	0.0	
22 Aug 2025	3:00 AM	NE NE	0.0	
22 Aug 2025	4:00 AM	NE NE	0.0	
22 Aug 2025 22 Aug 2025	5:00 AM	ESE	0.0	
22 Aug 2025	6:00 AM	W	0.0	
22 Aug 2025 22 Aug 2025	7:00 AM	SW	0.0	
22 Aug 2025	8:00 AM	SE	0.0	
22 1145 2023	0.00 / 11/1	l SE	0.1	

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
22 Aug 2025	9:00 AM	SE	0.0	
22 Aug 2025	10:00 AM	SE	0.1	
22 Aug 2025	11:00 AM	SW	0.1	
22 Aug 2025	12:00 PM	S	0.0	
22 Aug 2025	1:00 PM	WNW	0.0	
22 Aug 2025	2:00 PM	SSE	0.0	
22 Aug 2025	3:00 PM	NNW	0.0	
22 Aug 2025	4:00 PM	SSE	0.0	
22 Aug 2025	5:00 PM	SSE	0.0	
22 Aug 2025	6:00 PM	S	0.6	
22 Aug 2025	7:00 PM	S	0.6	
22 Aug 2025	8:00 PM	ESE	0.2	
22 Aug 2025	9:00 PM	SE	0.3	
22 Aug 2025	10:00 PM	WNW	0.4	
22 Aug 2025	11:00 PM	WNW	0.1	
23 Aug 2025	12:00 AM	WNW	0.1	
23 Aug 2025	1:00 AM	NNW	0.0	
23 Aug 2025	2:00 AM	SSW	0.5	
23 Aug 2025	3:00 AM	SSW	0.1	
23 Aug 2025	4:00 AM	SW	0.6	
23 Aug 2025	5:00 AM	S	0.8	
23 Aug 2025	6:00 AM	SSW	0.7	
23 Aug 2025	7:00 AM	NW	0.1	
23 Aug 2025	8:00 AM	NW	0.0	
23 Aug 2025	9:00 AM	NW	0.0	
23 Aug 2025	10:00 AM	W	0.2	
23 Aug 2025	11:00 AM	ESE	0.0	
23 Aug 2025	12:00 PM	ESE	0.0	
23 Aug 2025	1:00 PM	ESE	0.0	
23 Aug 2025	2:00 PM	ESE	0.4	
23 Aug 2025	3:00 PM	Е	0.2	
23 Aug 2025	4:00 PM	Е	0.1	
23 Aug 2025	5:00 PM	Е	0.1	
23 Aug 2025	6:00 PM	SSE	0.1	
23 Aug 2025	7:00 PM	SE	0.4	
23 Aug 2025	8:00 PM	SSW	0.2	
23 Aug 2025	9:00 PM	NW	0.4	
23 Aug 2025	10:00 PM	NW	0.0	
23 Aug 2025	11:00 PM	NW	0.0	
24 Aug 2025	12:00 AM	NW	0.1	
24 Aug 2025	1:00 AM	NW	0.0	
24 Aug 2025	2:00 AM	SW	0.1	
24 Aug 2025	3:00 AM	WNW	0.2	
24 Aug 2025	4:00 AM	WNW	0.0	
24 Aug 2025	5:00 AM	WNW	0.1	
24 Aug 2025	6:00 AM	WNW	0.0	
24 Aug 2025	7:00 AM	WNW	0.0	
24 Aug 2025	8:00 AM	WNW	0.0	
24 Aug 2025	9:00 AM	WNW	0.0	
24 Aug 2025	10:00 AM	WNW	0.0	
24 Aug 2025	11:00 AM	WNW	•	
24 Aug 2025 24 Aug 2025	12:00 PM	WNW	0.0	
	1:00 PM	WNW	0.0	
24 Aug 2025	2:00 PM	WNW	0.0	
24 Aug 2025	3:00 PM	WNW	0.0	
24 Aug 2025	4:00 PM	SW	+	
24 Aug 2025	5:00 PM	NE	0.0	

August 2025			
Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s
24 Aug 2025	6:00 PM	NE	0.0
24 Aug 2025	7:00 PM	NE	0.0
24 Aug 2025	8:00 PM	NE	0.0
24 Aug 2025	9:00 PM	NE	0.0
24 Aug 2025	10:00 PM	NE	0.0
24 Aug 2025	11:00 PM	NNE	0.0
25 Aug 2025	12:00 AM	SW	0.0
25 Aug 2025	1:00 AM	Е	0.0
25 Aug 2025	2:00 AM	ESE	0.0
25 Aug 2025	3:00 AM	SE	0.1
25 Aug 2025	4:00 AM	WSW	0.0
25 Aug 2025	5:00 AM	NNW	0.0
25 Aug 2025	6:00 AM	NNW	0.0
25 Aug 2025	7:00 AM	NNW	0.1
25 Aug 2025	8:00 AM	WNW	0.0
25 Aug 2025	9:00 AM	WNW	0.0
25 Aug 2025	10:00 AM	WNW	0.0
25 Aug 2025	11:00 AM	NNW	0.0
25 Aug 2025	12:00 PM	NNW	0.0
25 Aug 2025	1:00 PM	NNW	0.0
25 Aug 2025	2:00 PM	SW	0.0
25 Aug 2025	3:00 PM	SE	0.2
25 Aug 2025	4:00 PM	W	0.0
25 Aug 2025	5:00 PM	SE	0.1
25 Aug 2025	6:00 PM	WSW	0.1
25 Aug 2025	7:00 PM	WSW	0.0
25 Aug 2025	8:00 PM	WSW	0.1
25 Aug 2025	9:00 PM	WSW	0.0
25 Aug 2025	10:00 PM	WSW	0.0
25 Aug 2025	11:00 PM	W	0.0
26 Aug 2025	12:00 AM	W	0.1
26 Aug 2025	1:00 AM	NW	0.1
26 Aug 2025	2:00 AM	NW	0.1
26 Aug 2025	3:00 AM	NW	0.4
26 Aug 2025	4:00 AM	NW	0.0
26 Aug 2025	5:00 AM	NNW	0.0
26 Aug 2025	6:00 AM	NNW	0.0
26 Aug 2025	7:00 AM	NNW	0.0
26 Aug 2025	8:00 AM	NNW	0.0
26 Aug 2025	9:00 AM	NNW	0.0
26 Aug 2025	10:00 AM	NNW	0.0
26 Aug 2025	11:00 AM	NNW	0.0
26 Aug 2025	12:00 PM	NNW	0.0
26 Aug 2025	1:00 PM	NNW	0.0
26 Aug 2025	2:00 PM	NNW	0.0
26 Aug 2025	3:00 PM	NNW	0.0
26 Aug 2025	4:00 PM	NNW	0.0
26 Aug 2025	5:00 PM	NNW	0.0
26 Aug 2025	6:00 PM	W	0.0
26 Aug 2025	7:00 PM	WSW	0.4
26 Aug 2025	8:00 PM	W	0.0
26 Aug 2025	9:00 PM	SE	0.0
26 Aug 2025	10:00 PM	ESE	0.2
26 Aug 2025	11:00 PM	SW	0.0
27 Aug 2025	12:00 AM	WSW	0.4
27 Aug 2025	1:00 AM	NW	0.6
27 Aug 2025	2:00 AM	NW	0.1

August 2025			
		and Directions	
Date	Time	Direction	Wind Speed m-s
27 Aug 2025	3:00 AM	NW	0.1
27 Aug 2025	4:00 AM	NNW	0.0
27 Aug 2025	5:00 AM	NNW	0.0
27 Aug 2025	6:00 AM	NE	0.0
27 Aug 2025	7:00 AM	ESE	0.0
27 Aug 2025	8:00 AM	S	0.3
27 Aug 2025	9:00 AM	SSE	0.5
27 Aug 2025	10:00 AM	NE	0.3
27 Aug 2025	11:00 AM	W	0.5
27 Aug 2025	12:00 PM	NNE	0.3
27 Aug 2025	1:00 PM	ENE	0.2
27 Aug 2025	2:00 PM	NNW	0.4
27 Aug 2025	3:00 PM	NW	0.5
27 Aug 2025	4:00 PM	SSE	0.4
27 Aug 2025	5:00 PM	SSE	0.2
27 Aug 2025	6:00 PM	SSW	0.1
27 Aug 2025	7:00 PM	ENE	0.1
27 Aug 2025	8:00 PM	W	0.0
27 Aug 2025	9:00 PM	SW	0.6
27 Aug 2025	10:00 PM	SW	0.3
27 Aug 2025	11:00 PM	N	0.3
28 Aug 2025	12:00 AM	SSW	0.4
28 Aug 2025	1:00 AM	N	0.5
28 Aug 2025	2:00 AM	Е	0.3
28 Aug 2025	3:00 AM	ENE	0.3
28 Aug 2025	4:00 AM	W	0.4
28 Aug 2025	5:00 AM	NW	0.3
28 Aug 2025	6:00 AM	WNW	0.3
28 Aug 2025	7:00 AM	W	0.2
28 Aug 2025	8:00 AM	SSE	0.2
28 Aug 2025	9:00 AM	W	0.4
28 Aug 2025	10:00 AM	W	0.3
28 Aug 2025	11:00 AM	WSW	0.1
28 Aug 2025	12:00 PM	W	0.3
28 Aug 2025	1:00 PM	WNW	0.1
28 Aug 2025	2:00 PM	WNW	0.1

August 2025				
	Wind Speed and Directions			
Date	Time	Direction	Wind Speed m-s	
28 Aug 2025	3:00 PM	WNW	0.0	
28 Aug 2025	4:00 PM	WNW	0.0	
28 Aug 2025	5:00 PM	WNW	0.0	
28 Aug 2025	6:00 PM	WNW	0.0	
28 Aug 2025	7:00 PM	WNW	0.1	
28 Aug 2025	8:00 PM	WNW	0.0	
28 Aug 2025	9:00 PM	WNW	0.0	
28 Aug 2025	10:00 PM	WNW	0.1	
28 Aug 2025	11:00 PM	WNW	0.0	
29 Aug 2025	12:00 AM	WNW	0.0	
29 Aug 2025	1:00 AM	WNW	0.1	
29 Aug 2025	2:00 AM	NNW	0.0	
29 Aug 2025	3:00 AM	WNW	0.0	
29 Aug 2025	4:00 AM	W	0.2	
29 Aug 2025	5:00 AM	W	0.2	
29 Aug 2025	6:00 AM	WNW	0.4	
29 Aug 2025	7:00 AM	NW	0.1	
29 Aug 2025	8:00 AM	NW	0.2	
29 Aug 2025	9:00 AM	SSW	0.4	
29 Aug 2025	10:00 AM	NE	0.1	
29 Aug 2025	11:00 AM	NE	0.0	
29 Aug 2025	12:00 PM	NE	0.0	
29 Aug 2025	1:00 PM	NE	0.1	
29 Aug 2025	2:00 PM	NE	0.0	
29 Aug 2025	3:00 PM	NNE	0.1	
29 Aug 2025	4:00 PM	NNE	0.3	
29 Aug 2025	5:00 PM	NNE	0.0	
29 Aug 2025	6:00 PM	NNE	0.0	
29 Aug 2025	7:00 PM	N	0.1	
29 Aug 2025	8:00 PM	N	0.0	
29 Aug 2025	9:00 PM	NNE	0.0	
29 Aug 2025	10:00 PM	NNE	0.0	
29 Aug 2025	11:00 PM	NNE	0.0	
30 Aug 2025	12:00 AM	NNE	0.0	
30 Aug 2025	1:00 AM	NNE	0.0	
30 Aug 2025	2:00 AM	NNE	0.0	
30 Aug 2025	3:00 AM	NNE	0.0	
30 Aug 2025	4:00 AM	NNE	0.0	
30 Aug 2025	5:00 AM	NNE	0.0	
30 Aug 2025	6:00 AM	NNE	0.0	
30 Aug 2025	7:00 AM	N	0.1	
30 Aug 2025	8:00 AM	N	0.0	
30 Aug 2025	9:00 AM	W	0.3	
30 Aug 2025	10:00 AM	N	0.1	
30 Aug 2025	11:00 AM	NNW	0.0	
30 Aug 2025	12:00 PM	NW	0.1	
30 Aug 2025	1:00 PM	NW	0.2	
30 Aug 2025	2:00 PM	NW	0.0	
30 Aug 2025	3:00 PM	NW	0.0	
30 Aug 2025	4:00 PM	NW	0.0	
30 Aug 2025	5:00 PM	NW	0.0	
30 Aug 2025	6:00 PM	NW	0.1	
30 Aug 2025	7:00 PM	NW	0.1	
30 Aug 2025	8:00 PM	NW	0.0	
30 Aug 2025	9:00 PM	NNW	0.0	
30 Aug 2025	10:00 PM	NW	0.1	
30 Aug 2025	11:00 PM	NW	0.1	

	A		
		and Directions	
Data	Time		W. d.C d
Date		Direction	Wind Speed m-s
31 Aug 2025	12:00 AM	NW	0.0
31 Aug 2025	1:00 AM	NW	0.2
31 Aug 2025	2:00 AM	NW	0.2
31 Aug 2025	3:00 AM	NNW	0.0
31 Aug 2025	4:00 AM	NNW	0.3
31 Aug 2025	5:00 AM	NW	0.0
31 Aug 2025	6:00 AM	NW	0.3
31 Aug 2025	7:00 AM	NW	0.0
31 Aug 2025	8:00 AM	NW	0.0
31 Aug 2025	9:00 AM	WNW	0.0
31 Aug 2025	10:00 AM	WNW	0.2
31 Aug 2025	11:00 AM	NW	0.0
31 Aug 2025	12:00 PM	WNW	0.2
31 Aug 2025	1:00 PM	NW	0.3
31 Aug 2025	2:00 PM	NW	0.2
31 Aug 2025	3:00 PM	NW	0.2
31 Aug 2025	4:00 PM	NW	0.4
31 Aug 2025	5:00 PM	SE	0.3
31 Aug 2025	6:00 PM	NE	0.4
31 Aug 2025	7:00 PM	W	0.4
31 Aug 2025	8:00 PM	W	0.4
31 Aug 2025	9:00 PM	WNW	0.4
31 Aug 2025	10:00 PM	NW	0.3
31 Aug 2025	11:00 PM	NW	0.6

APPENDIX D ENVIRONMENTAL MONITORING SCHEDULES

Contract No. ED/2018/04 Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron Impact Air and Noise Monitoring Schedule (August 2025)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	,	j	Ž	,	1-Aug	2-Aug
3-Aug	4-Aug	5-Aug	6-Aug	7-Aug	8-Aug	9-Aug
		24-hrs TSP	1-hr TSP X3 Noise			
10-Aug	11-Aug	12-Aug	13-Aug	14-Aug	15-Aug	16-Aug
	24-hrs TSP	1-hr TSP X3 Noise				24-hrs TSP
17-Aug	18-Aug	19-Aug	20-Aug	21-Aug	22-Aug	23-Aug
	1-hr TSP X3 Noise			24-hrs TSP	1-hr TSP X3	
24-Aug	25-Aug	` 26-Aug	27-Aug	28-Aug	29-Aug	30-Aug
			24-hrs TSP	1-hr TSP X3 Noise		
31-Aug					_	

Air Quality Monitoring Station

1-hr TSP / 24-hrs TSP AM1 - Tin Hau Temple

AM2 - Sai Tso Wan Recreation Ground

AM3 - Yau Lai Estate Bik Lai House

AM4⁽¹⁾ - Sitting-out Area at Cha Kwo Ling Village

AM4(B)(2) - Flat 103 Cha Kwo Ling Village

Noise Monitoring Station

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong

CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong

CM4 - Tin Hau Temple, Cha Kwo Ling

Contract No. ED/2018/04

Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron Tentative Impact Air and Noise Monitoring Schedule (September 2025)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
	1-Sep	2-Sep	3-Sep	4-Sep	5-Sep	6-Sep
		24-hrs TSP	1-hr TSP X3 Noise			
7-Sep	8-Sep	9-Sep	10-Sep	11-Sep	12-Sep	13-Sep
	24-hrs TSP	1-hr TSP X3 Noise				24-hrs TSP
14-Sep	15-Sep	16-Sep	17-Sep	18-Sep	19-Sep	20-Sep
	1-hr TSP X3 Noise			24-hrs TSP	1-hr TSP X3	
21-Sep	22-Sep	23-Sep	24-Sep	25-Sep	26-Sep	27-Sep
			24-hrs TSP	1-hr TSP X3 Noise		
28-Sep	29-Sep	` 30-Sep				
	24-hrs TSP	1-hr TSP X3 Noise				

The schedule may be changed due to unforeseen circumstances (adverse weather, safety concerns, etc.)

Air Quality Monitoring Station

1-hr TSP / 24-hrs TSP

AM1 - Tin Hau Temple

AM2 - Sai Tso Wan Recreation Ground

AM3 - Yau Lai Estate Bik Lai House

AM4⁽¹⁾ - Sitting-out Area at Cha Kwo Ling Village

AM4(B)(2) - Flat 103 Cha Kwo Ling Village

Noise Monitoring Station

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong

CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong

CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong

CM4 - Tin Hau Temple, Cha Kwo Ling

Contract No. ED/2018/04

Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron Tentative Impact Air and Noise Monitoring Schedule (October 2025)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
			1-Oct	2-Oct	3-Oct	4-Oct
						24-hrs TSP
5-Oct	6-Oct	7-Oct	8-Oct	9-Oct	10-Oct	11-Oct
	1-hr TSP X3 Noise			24-hrs TSP	1-hr TSP X3	
12-Oct	13-Oct	14-Oct	15-Oct	16-Oct	17-Oct	18-Oct
			24-hrs TSP	1-hr TSP X3 Noise		
19-Oct	20-Oct	21-Oct	22-Oct	23-Oct	24-Oct	25-Oct
		24-hrs TSP	1-hr TSP X3 Noise			
26-Oct	27-Oct	` 28-Oct	29-Oct	30-Oct	31-Oct	
	24-hrs TSP	1-hr TSP X3 Noise				

The schedule may be changed due to unforeseen circumstances (adverse weather, safety concerns, etc.)

Air Quality Monitoring Station

1-hr TSP / 24-hrs TSP

AM1 - Tin Hau Temple

AM2 - Sai Tso Wan Recreation Ground

AM3 - Yau Lai Estate Bik Lai House

AM4⁽¹⁾ - Sitting-out Area at Cha Kwo Ling Village

AM4(B)(2) - Flat 103 Cha Kwo Ling Village

Noise Monitoring Station

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong

CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong

CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong

CM4 - Tin Hau Temple, Cha Kwo Ling

Contract No. ED/2018/04 Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron Tentative Impact Air and Noise Monitoring Schedule (November 2025)

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
-			•		-	1-Nov
						24-hrs TSP
2-Nov	3-Nov	4-Nov	5-Nov	6-Nov	7-Nov	8-Nov
	1-hr TSP X3 Noise			24-hrs TSP	1-hr TSP X3	
9-Nov	10-Nov	11-Nov	12-Nov	13-Nov	14-Nov	15-Nov
			24-hrs TSP	1-hr TSP X3 Noise		
16-Nov	17-Nov	18-Nov	19-Nov	20-Nov	21-Nov	22-Nov
		24-hrs TSP	1-hr TSP X3 Noise			
23-Nov	24-Nov	` 25-Nov	26-Nov	27-Nov	28-Nov	29-Nov
	24-hrs TSP	1-hr TSP X3 Noise				24-hrs TSP
30-Nov						

The schedule may be changed due to unforeseen circumstances (adverse weather, safety concerns, etc.)

Air Quality Monitoring Station

1-hr TSP / 24-hrs TSP AM1 - Tin Hau Temple

AM2 - Sai Tso Wan Recreation Ground

AM3 - Yau Lai Estate Bik Lai House

AM4⁽¹⁾ - Sitting-out Area at Cha Kwo Ling Village

AM4(B)(2) - Flat 103 Cha Kwo Ling Village

Noise Monitoring Station

CM1 - Nga Lai House, Yau Lai Estate Phase 1, Yau Tong

CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong

CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong

CM4 - Tin Hau Temple, Cha Kwo Ling

APPENDIX E 1-HOUR TSP MONITORING RESULTS AND GRAPHICAL PRESENTATIONS

Appendix E - 1-hour TSP Monitoring Results


Location AM1 -	Tin Hau Ten	nple	
Date	Time	Weather	Particulate Concentration (μg/m³)
6-Aug-25	10:05	Cloudy	50.4
6-Aug-25	11:05	Cloudy	60.9
6-Aug-25	12:05	Cloudy	63.0
12-Aug-25	13:00	Sunny	32.4
12-Aug-25	14:00	Sunny	28.8
12-Aug-25	15:00	Sunny	34.2
18-Aug-25	13:00	Cloudy	27.0
18-Aug-25	14:00	Cloudy	28.8
18-Aug-25	15:00	Cloudy	25.2
22-Aug-25	13:00	Sunny	34.2
22-Aug-25	14:00	Sunny	32.4
22-Aug-25	15:00	Sunny	30.6
28-Aug-25	15:20	Sunny	28.9
28-Aug-25	16:20	Sunny	42.5
28-Aug-25	17:20	Sunny	37.4
		Average	37.1
		Maximum	63.0
		Minimum	25.2

Location AM2 -	Sai Tso War	n Recreation Grou	und
Date	Time	Weather	Particulate Concentration (μg/m ³)
6-Aug-25	9:40	Cloudy	49.4
6-Aug-25	10:40	Cloudy	58.9
6-Aug-25	11:40	Cloudy	55.1
12-Aug-25	16:00	Sunny	18.0
12-Aug-25	17:00	Sunny	19.8
12-Aug-25	18:00	Sunny	14.4
18-Aug-25	9:00	Cloudy	14.4
18-Aug-25	10:00	Cloudy	18.0
18-Aug-25	11:00	Cloudy	19.8
22-Aug-25	9:30	Sunny	28.5
22-Aug-25	10:30	Sunny	32.3
22-Aug-25	11:30	Sunny	34.2
28-Aug-25	15:38	Sunny	81.7
28-Aug-25	16:38	Sunny	51.3
28-Aug-25	17:38	Sunny	57.0
		Average	36.9
		Maximum	81.7
		Minimum	14.4


Appendix E - 1-hour TSP Monitoring Results

Location AM3 -	Yau Lai Esta	ate Bik Lai House	
Date	Time	Weather	Particulate Concentration (μg/m ³)
6-Aug-25	14:10	Cloudy	51.3
6-Aug-25	15:10	Cloudy	51.3
6-Aug-25	16:10	Cloudy	62.7
12-Aug-25	9:00	Sunny	23.4
12-Aug-25	10:00	Sunny	27.0
12-Aug-25	11:00	Sunny	19.8
18-Aug-25	16:00	Cloudy	21.6
18-Aug-25	17:00	Cloudy	23.4
18-Aug-25	18:00	Cloudy	19.8
22-Aug-25	9:00	Sunny	14.4
22-Aug-25	10:00	Sunny	16.2
22-Aug-25	11:00	Sunny	12.6
28-Aug-25	12:38	Sunny	26.6
28-Aug-25	13:38	Sunny	24.7
28-Aug-25	14:38	Sunny	19.0
		Average	27.6
		Maximum	62.7
		Minimum	12.6

Location AM4 -	Sitting-out A	Area at Cha Kwo	Ling Village
Date	Time	Weather	Particulate Concentration (μg/m ³)
6-Aug-25	13:45	Cloudy	71.4
6-Aug-25	14:45	Cloudy	58.8
6-Aug-25	15:45	Cloudy	73.5
12-Aug-25	14:00	Sunny	34.2
12-Aug-25	15:00	Sunny	32.3
12-Aug-25	16:00	Sunny	30.4
18-Aug-25	14:00	Sunny	25.5
18-Aug-25	15:00	Sunny	22.1
18-Aug-25	16:00	Sunny	23.8
22-Aug-25	14:00	Sunny	30.4
22-Aug-25	15:00	Sunny	30.4
22-Aug-25	16:00	Sunny	26.6
28-Aug-25	9:26	Sunny	22.8
28-Aug-25	10:26	Sunny	24.7
28-Aug-25	11:26	Sunny	28.5
_		Average	35.7
		Maximum	73.5
		Minimum	22.1



1-hr TSP Concentration Levels



Notes:

- 1. The major activitie(s) being carried out on site during the reporting period is/are presented in Section 1.10
- 2. The weather conditions during the reporting month are presented in Appendix C.
- 3. Other factors which might affect the monitoring results are presented in Section 2.18.

Contract No. ED/2018/04

Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron

Graphical Presentation of 1-hour TSP Monitoring Results

Scale	N.T.S	Project No.	MA20003
Date	Jul-25	Appendi	x E



APPENDIX F 24-HOUR TSP MONITORING RESULTS AND GRAPHICAL PRESENTATIONS

Appendix F - 24-hour TSP Monitoring Results

Location AM1 - Tin Hau Temple

Start Date	Weather Filter Weight (g)		Particulate	Elaps	e Time	Sampling	Flow Rat	te (m³/min.)	Av. flow	Total vol.	Conc.	
Start Date	Condition	Initial	Final	Weight (g)	Initial	Final	Time(hrs.)	Initial	Final	(m ³ /min)	(m ³)	(µg/m³)
5-Aug-25	Rainy	2.8268	2.8580	0.0313	15306.6	15330.6	24.0	1.22	1.22	1.22	1754.6	17.8
11-Aug-25	Fine	2.8358	2.8647	0.0289	15330.6	15354.6	24.0	1.21	1.21	1.21	1748.7	16.5
16-Aug-25	Sunny	2.7466	2.7612	0.0145	15354.6	15378.6	24.0	1.22	1.22	1.22	1761.2	8.3
21-Aug-25	Sunny	2.8340	2.8579	0.0239	15378.6	15402.6	24.0	1.22	1.22	1.22	1759.2	13.6
27-Aug-25	Sunny	2.8250	2.8430	0.0179	15402.6	15426.6	24.0	1.22	1.22	1.22	1758.1	10.2
											Min	8.3
											Max	17.8
											Average	13.3

Location AM2 - Sai Tso Wan Recreation Ground


Start Date	Weather Filter Weight (g)		Particulate	Elaps	e Time	Sampling	Flow Rat	te (m³/min.)	Av. flow	Total vol.	Conc.	
Start Date	Condition	Initial	Final	Weight (g)	Initial	Final	Time(hrs.)	Initial	Final	(m ³ /min)	(m ³)	(µg/m³)
5-Aug-25	Rainy	2.7894	2.7990	0.0095	36396.6	36420.6	24.0	1.22	1.22	1.22	1755.4	5.4
11-Aug-25	Sunny	2.8377	2.8760	0.0383	36420.6	36444.6	24.0	1.22	1.22	1.22	1750.3	21.9
16-Aug-25	Sunny	3.3598	3.3740	0.0143	36444.6	36468.6	24.0	1.22	1.22	1.22	1758.5	8.1
21-Aug-25	Sunny	2.8351	2.8497	0.0146	36478.6	36502.6	24.0	1.22	1.22	1.22	1756.8	8.3
27-Aug-25	Sunny	2.6911	2.7109	0.0198	36502.5	36526.6	24.1	1.22	1.22	1.22	1761.7	11.2
											Min	5.4
											Max	21.9
											Average	11.0

Location AM3 - Yau Lai Estate, Bik Lai House


Start Date	Weather	Filter W	eight (g)	Particulate Elapse Time		Sampling	Sampling Flow Rate (m³/min.)			Total vol.	Conc.	
Start Date	Condition	Initial	Final	Weight (g)	Initial	Final	Time(hrs.)	Initial	Final	(m ³ /min)	(m ³)	(µg/m³)
5-Aug-25	Rainy	2.8459	2.8751	0.0292	10726.2	10750.2	24.0	1.22	1.22	1.22	1753.0	16.7
11-Aug-25	Fine	2.8339	2.8575	0.0237	10750.2	10774.2	24.0	1.21	1.21	1.21	1747.8	13.5
16-Aug-25	Sunny	2.7941	2.8323	0.0381	10774.2	10798.2	24.0	1.22	1.22	1.22	1757.4	21.7
21-Aug-25	Sunny	2.8291	2.8529	0.0238	10798.2	10822.2	24.0	1.22	1.22	1.22	1755.7	13.5
27-Aug-25	Sunny	2.8236	2.8558	0.0322	10822.2	10846.2	24.0	1.22	1.22	1.22	1754.8	18.3
											Min	13.5
											Max	21.7
											Average	16.8

Location AM4(B) - Flat 103 Cha Kwo Ling Village

Start Date	Weather	Filter W	eight (g)	Particulate	Particulate Elapse Time			Sampling Flow Rate (m³/min.)			Total vol.	Conc.
Start Date	Condition	Initial	Final	Weight (g)	Initial	Final	Time(hrs.)	Initial	Final	(m ³ /min)	(m ³)	(µg/m³)
5-Aug-25	Rainy	2.7776	2.8618	0.0843	22199.9	22223.9	24.0	1.22	1.22	1.22	1763.2	47.8
11-Aug-25	Fine	2.7855	2.9294	0.1440	22223.9	22247.9	24.0	1.22	1.22	1.22	1757.4	81.9
16-Aug-25	Fine	2.8079	2.9207	0.1128	22247.9	22271.9	24.0	1.22	1.23	1.22	1762.3	64.0
21-Aug-25	Sunny	2.8246	3.0394	0.2148	22271.9	22295.9	24.0	1.22	1.22	1.22	1760.5	122.0
27-Aug-25	Sunny	2.8149	2.9344	0.1195	22295.9	22319.9	24.0	1.22	1.22	1.22	1759.5	67.9
											Min	47.8
											Max	122.0
											Average	76.7



24-hr TSP Concentration Levels



Notes:

- 1) The major activitie(s) being carried out on site during the reporting period is/are presented in Section 1.10
- 2) The weather conditions during the reporting month are presented in Appendix C.
- 3) Other factors which might affect the monitoring results are presented in Section 2.18.

Contract No. ED/2018/04 Scale Project Trunk Road T2 and Infrastructure Works for Developments at the No. MA20003 N.T.S Former South Apron Date Appendix Graphical Presentation of 24-hour TSP Monitoring Results Aug-25

CINOTECH

F

APPENDIX G NOISE MONITORING RESULTS AND GRAPHICAL PRESENTATIONS

Appendix G - Noise Monitoring Results

(0700-1900 hrs on Normal Weekdays)


Location CM1 -	Nga Lai Ho	use, Yau Lai	Estate Phas	e 1, Yau Tor	ng					
		Weather	Unit: dB (A) (30-min)							
Date	Time		Meas	sured Noise	Level	Baseline Level	Construction Noise Level			
Date	11110	vvcatilei								
			L _{eq}	L ₁₀	L 90	L _{eq}	L _{eq}			
6 Aug 2025	15:15	Cloudy	65.9	68.6	59.4	65.5	55			
12 Aug 2025	9:00	Sunny	68.8	71.4	65.1	65.5	66			
18 Aug 2025	13:45	Fine	67.6	68.9	65.9	65.5	63			
28 Aug 2025	13:51	Sunny	68.0	69.5	65.8	65.5	64			

Location CM2 -	Location CM2 - Bik Lai House, Yau Lai Estate Phase 1, Yau Tong												
			Unit: dB (A) (30-min)										
Date	Time	Weather	Meas	sured Noise	Level	Baseline Level	Construction Noise Level						
Buto	11110	Woding	L _{eq}	L ₁₀	L 90	L _{eq}	L _{eq}						
6 Aug 2025	14:15	Cloudy	66.9	69.7	61.0	63.6	64						
12 Aug 2025	9:45	Sunny	69.1	72.4	65.4	63.6	68						
18 Aug 2025	13:00	Fine	66.3	67.1	60.8	63.6	63						
28 Aug 2025	13:09	Sunny	65.1	66.4	63.5	63.6	60						


Location CM3 -	Location CM3 - Block S, Yau Lai Estate Phase 5, Yau Tong												
					Uni	t: dB (A) (30-min)							
Date	Time	Weather	Meas	sured Noise	Level	Baseline Level	Construction Noise Level						
Date	Time	Wedner	L _{eq}	L ₁₀	L 90	L _{eq}	L _{eq}						
6 Aug 2025	13:40	Cloudy	66.3	69.4	60.8	65.6	58						
12 Aug 2025	10:30	Sunny	69.3	72.6	64.8	65.6	67						
18 Aug 2025	14:30	Fine	68.3	69.6	66.4	65.6	65						
28 Aug 2025	14:26	Sunny	63.8	65.5	61.7	65.6	64 Measured ≦ Baseline						

Location CM4 -	Tin Hau Te	mple, Cha Kv	o Ling									
				Unit: dB (A) (30-min)								
Date	Time	Weather	Meas	sured Noise I	Level	Baseline Level	Construction Noise Level					
Date	110	catrioi										
			L _{eq}	L ₁₀	L 90	L _{eq}	L _{eq}					
6 Aug 2025	10:55	Cloudy	59.8	62.1	56.1	62.0	60 Measured ≦ Baseline					
12 Aug 2025	13:00	Sunny	60.8	63.7	55.9	62.0	61 Measured ≦ Baseline					
18 Aug 2025	10:00	Fine	62.0	64.4	52.0	62.0	62 Measured ≦ Baseline					
28 Aug 2025	15:46	Sunny	56.5	59.6	51.4	62.0	57 Measured ≦ Baseline					

Location CM5 - CCC Kei Faat Primary School, Yau Tong											
		Weather	Unit: dB (A) (30-min)								
Date	Time		Meas	sured Noise I	_evel	Baseline Level	Construction Noise Level				
Dute	Time		L _{eq}	L ₁₀	L ₉₀	L _{eq}	L _{eq}				
6 Aug 2025	11:55	Cloudy	64.3	68.1	59.5	68.2	64 Measured ≦ Baseline				
12 Aug 2025	11:30	Sunny	67.4	70.8	63.6	68.2	67 Measured ≦ Baseline				
18 Aug 2025	10:45	Fine	66.1	70.7	52.4	68.2	66 Measured ≦ Baseline				
28 Aug 2025	15:09	Sunny	61.5 63.5 58.8 68.2 62 Measured ≦ Baseli								



Noise Levels



Notes:

- 1) The major activitie(s) being carried out on site during the reporting period is/are presented in Section 1.10
- 2) The weather conditions during the reporting month are presented in Appendix C.
- 3) Other factors which might affect the monitoring results are presented in Section 3.13.

Title Contract No. ED/2018/04
Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron

Graphical Presentation of Construction Noise Monitoring Results

Scale

N.T.S

No. MA20003

Date
Aug 25

Appendix

Aug 25

G

APPENDIX H
WASTE GENERATION IN THE
REPORTING MONTH



Name of Department: CEDD

Monthly Summary Waste Flow Table for 2025 (CKL)

Trunk Road T2 and Infrastructure Works for Developments at the Former South Apron Contract No. ED/2018/04

	Actu	al Quantities	of Inert C&D	Materials G	enerated Mo	nthly	Actual (Quantities of	C&D Wastes	s Generated	Monthly
Month	a.Total Quantity Generated (a=c+d+e)	b. Hard Rock and Large Broken Concrete	c. Reused in the Contract	d. Reused in Other Projects	e. Disposed as Public Fill	f. Imported Fill	g. Metals	h. Paper / Cardboard Packaging		j. Chemical Waste	k. Others, e.g. general refuse
	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000m ³)
January	11.536	0.843	0.866	0.259	10.410	0.000	0.000	0.000	0.000	0.000	0.048
February	11.239	1.307	0.589	0.000	10.650	0.000	0.000	0.000	0.000	0.000	0.076
March	4.432	0.820	0.359	0.000	4.074	0.000	0.000	0.000	0.000	0.000	0.075
April	15.886	1.091	0.000	0.000	15.886	0.000	0.000	0.000	0.000	0.000	0.045
May	12.110	1.262	0.000	0.000	12.110	0.000	0.000	0.000	0.000	0.000	0.038
June	5.179	0.036	0.000	0.000	5.179	0.000	0.000	0.000	0.000	0.000	0.032
Sub-total	60.383	5.360	1.815	0.259	58.309	0.000	0.000	0.000	0.000	0.000	0.313
July	1.328	0.442	0.000	0.000	1.328	0.000	0.000	0.000	0.000	0.000	0.025
August	0.637	0.161	0.000	0.000	0.637	0.000	0.000	0.000	0.000	0.000	0.030
September											
October											
November											
December											
Total	62.348	5.963	1.815	0.259	60.274	0.000	0.000	0.000	0.000	0.000	0.368

Monthly Summary Waste Flow Table

Notes:

- (1) The performance targets are given in ER Appendix 8I Clause 14 and the EM&A Manual(s).
- (2)The waste flow table shall also include C&D materials to be imported for use at the Site.
- (3)Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging material.
- (4)The Contractor shall also submit the latest forecast of the total amount of C&D materials expected to be generated from the Works, together with a breakdown of the nature where the total amount of C&D materials expected to be generated from the Works is equal to or exceeding 50,000 m3. (ER Part 8 Clause 8.8.5 (d) (ii) refers).

ED/2020/03 - Trunk Road T2 - Traffic Control and Surveillance System (TCSS) and Associated Works

Monthly Summary Waste Flow Table For 2025 (CKL)

		Actual Quanti	ties of Inert C&	O Materials Gener	ated Monthly	J	I		,	ntities of C&D	Waste Generate	d Monthly		
		Actual Qualiti	ties of filer C&	J Materials Gener	ated Monthly	1		1	Actual Qua	nuities of C&D	waste Generate	d Monthly	T I	
Month	Total Quantity Generated	Broken Concrete (see Note 4)	Estimated Quantities (Broken Concrete)	Reused in the Contract	Reused in other Projects	Disposed as Public Fill	Metals	Estimated Quantities (Metals)	Paper/ cardboard packaging	Estimated Quantities (Paper/ cardboard packaging)	Plastics (see Note 3)	Estimated Quantities (Plastics)	Chemical Waste	Others, e.g. general refuse
	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(tonne)
Jan-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Feb-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Mar-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Apr-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
May-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Jun-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Sub-total	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Jul-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Aug-25	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Sep-25														
Oct-25														
Nov-25														
Dec-25														
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Notes:

- (1) The performance targets are given in PS Sub-clause 2(5) (c).
- (2) The waste flow table shall also include C&D materials that are specified in the Contract to be imported for use at the Site.
- (3) Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging material.
- (4) Broken concrete for recycling into aggregates.

Monthly Summary Waste Flow Table for August 2025



	Actu	al Quantities	of Inert C&D	Materials G	enerated Mo	nthly	Actual (Quantities of	C&D Wastes	Generated I	Monthly
Month	a.Total Quantity Generated (see Note 8)	b. Hard Rock and Large Broken Concrete	c. Reused in the Contract	d. Reused in Other Projects	e. Disposed f. Imported as Public Fill		g. Metals (see Note 5)	h. Paper / Cardboard Packaging (see Note 5) i. Plastic (see Note		j. Chemical Waste	k. Others, e.g. general refuse
	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000m ³)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000kg)	(in '000m ³)
January	0.324	0.025	0.000	0.000	0.324	0.000	0.000	0.000	0.000	0.000	0.407
February	0.754	0.100	0.000	0.000	0.754	0.000	0.000	0.000	0.000	0.000	0.240
March	0.836	0.130	0.000	0.00	0.836	0.000	0.000	0.000	0.000	0.000	0.469
April	0.226	0.061	0.000	0.000	0.226	0.000	0.000	0.000	0.000	0.000	0.263
May	0.125	0.025	0.000	0.000	0.125	0.000	0.000	0.000	0.000	0.000	0.263
June	0.262	0.030	0.000	0.000	0.262	0.000	0.000	0.000	0.000	0.000	0.245
Sub-total	2.527	0.371	0.000	0.000	2.527	0.000	0.000	0.000	0.000	0.000	1.887
July	0.176	0.060	0.000	0.000	0.176	0.000	0.000	0.000	0.000	0.000	0.239
August	0.399	0.095	0.000	0.000	0.399	0.000	0.000	0.000	0.000	0.000	0.291
September											
October	_	_	_		_		_	_	_	_	
November											
December											
Total	3.102	0.526	0.000	0.000	3.102	0.000	0.000	0.000	0.000	0.000	2.417

Total inert C&D waste generated = c+d+e

Total inert C&D waste recycled = c+d

% of recycled inert C&D waste = Total C&D waste recycled / Total C&D waste generated



Notes: (1) The performance target are given in PS Clause 6(14)

- (2) The waste flow table shall also include C&D materials that are specified in the Contract to be imported for use at the Site
- (3) Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging material
- (4) The Contractor shall also submit the latest forecast of the amount of C&D materials expected to be generated from the Works, together with a break down of the nature where the total amount of C&D materials expected to be generated from the Works is equal to or exceeding 50,000m3. (PS Clause 1.105(4) refers)
- (5) All recyclable materials, including metals, paper / cardboard packaging, plastics, etc. will be collected by registered collector for recycling.
- (6) Conversion factors for reporting purpose:

in-situ: rock = 2.5 tonnes/m³; soil = 2.0 tonnes/m³

- (7) excavated: rock = 2.0 tonnes/m³; soil = 1.8 tonnes/m³; broken concrete and bitumen = 2.4 tonnes/m³, soil and rock = 1.9 tonnes/m³
- (8) C&D Waste = 0.9 tonnes/m³; bentonite slurry = 2.8 tonnes/m³

Diesel density: 0.8kg/l

Numbers are rounded off to the nearest three decimal places

The "Total Quantity Generated" equals to the sum of "Reuse in the Contract", "Reuse in Other Projects" and "Disposed as Public Fill"

APPENDIX I SITE AUDIT SUMMARY

Environmental Team for Trunk Road T2 and Infrastructure Works at the Former South Apron

Weekly Site Inspection Record Summary Inspection Information

Checklist Reference Number	250807
Date	07 August 2025 (Thursday)
Time	09:30 – 16:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
250807-EP458-R1	Stagnant water was observed at Portion SB.	B09
250807-EP458-R2	Stagnant water was observed at Portion TY	B09
	C. Air Quality	
	No environmental deficiency was identified during site inspection.	
	D. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	E. Waste/Chemical Management	
	No environmental deficiency was identified during site inspection.	
	F. Visual and Landscape	
	No environmental deficiency was identified during site inspection.	
	G. Permits/Licences	
	No environmental deficiency was identified during site inspection.	
	H. Marine Ecology	
	No environmental deficiency was identified during site inspection.	
	I. Others	
	• No environmental deficiency was identified in previous session (Ref No.: 250731).	

	Name	Signature	Date
Recorded by	William Yeung	K	07 Aug 2025
Checked by	Karina Chan	Zalle	11 Aug 2025

1 CINOTECH MA20003 $2508_audit_T2_CKL$

Environmental Team for Trunk Road T2 and Infrastructure Works at the Former South Apron

Checklist Reference Number	250815
Date	15 August 2025 (Friday)
Time	09:30 – 16:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Air Quality	
	No environmental deficiency was identified during site inspection.	
	D. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	 E. Waste/Chemical Management No environmental deficiency was identified during site inspection. 	
	 F. Visual and Landscape No environmental deficiency was identified during site inspection. 	
	 G. Permits/Licences No environmental deficiency was identified during site inspection. 	
	H. Marine Ecology	
	No environmental deficiency was identified during site inspection.	
	I. Others	
	• Follow up on the previous session (Ref No.:250807), all the items have been rectified	

	Name	Signature	Date
Recorded by	William Yeung	B	15 Aug 2025
Checked by	Karina Chan	Zalle	18 Aug 2025

Environmental Team for Trunk Road T2 and Infrastructure Works at the Former South Apron

Checklist Reference Number	250821
Date	21 August 2025 (Thursday)
Time	09:30 – 16:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality No environmental deficiency was identified during site inspection.	
	 C. Air Quality No environmental deficiency was identified during site inspection. 	
	 D. Construction Noise Impact No environmental deficiency was identified during site inspection. 	
	 E. Waste/Chemical Management No environmental deficiency was identified during site inspection. 	
	 F. Visual and Landscape No environmental deficiency was identified during site inspection. 	
	 G. Permits/Licences No environmental deficiency was identified during site inspection. 	
	 H. Marine Ecology No environmental deficiency was identified during site inspection. 	
	 I. Others No environmental deficiency was identified in previous session (Ref No.: 250815). 	

	Name	Signature	Date
Recorded by	William Yeung	B	21 Aug 2025
Checked by	Karina Chan	Zalle	25 Aug 2025

Environmental Team for Trunk Road T2 and Infrastructure Works at the Former South Apron

Checklist Reference Number	250828
Date	28 August 2025 (Thursday)
Time	09:30 – 16:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Remarks/Observations	Related Item No.
B. Water Quality	
No environmental deficiency was identified during site inspection.	
C. Air Quality	
No environmental deficiency was identified during site inspection.	
D. Construction Noise Impact	
E. Waste/Chemical Management	
No environmental deficiency was identified during site inspection.	
F. Visual and Landscape	
No environmental deficiency was identified during site inspection.	
• No environmental deficiency was identified during site inspection.	
H. Marine Ecology	
No environmental deficiency was identified during site inspection.	
I Othars	
	 B. Water Quality No environmental deficiency was identified during site inspection. C. Air Quality No environmental deficiency was identified during site inspection. D. Construction Noise Impact No environmental deficiency was identified during site inspection. E. Waste/Chemical Management No environmental deficiency was identified during site inspection. F. Visual and Landscape No environmental deficiency was identified during site inspection. G. Permits/Licences No environmental deficiency was identified during site inspection. H. Marine Ecology

	Name	Signature	Date
Recorded by	William Yeung		28 Aug 2025
Checked by	Karina Chan	Zolle	1 Sep 2025

Environmental Team for Trunk Road T2 – Traffic Control and Surveillance System (TCSS) and **Associated Works**

Checklist Reference Number	250807
Date	07 August 2025 (Thursday)
Time	09:30 – 12:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Air Quality	
	No environmental deficiency was identified during site inspection.	
	D. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	E. Waste/Chemical Management	
	No environmental deficiency was identified during site inspection.	
	F. Visual and Landscape	
	No environmental deficiency was identified during site inspection.	
	G. Permits/Licences	
	No environmental deficiency was identified during site inspection.	
	H. Marine Ecology	
	No environmental deficiency was identified during site inspection.	
	I. Others	
	• Follow up on the previous session (Ref No.:250731), no major environmental deficiency	
	was identified during site inspection.	

	Name	Signature	Date
Recorded by	William Yeung	K	07 Aug 2025
Checked by	Karina Chan	Zalle	11 Aug 2025

Environmental Team for Trunk Road T2 – Traffic Control and Surveillance System (TCSS) and **Associated Works**

Checklist Reference Number	250815
Date	15 August 2025 (Friday)
Time	09:30 – 12:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Air Quality	
	No environmental deficiency was identified during site inspection.	
	D. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	E. Waste/Chemical Management	
	No environmental deficiency was identified during site inspection.	
	F. Visual and Landscape	
	No environmental deficiency was identified during site inspection.	
	G. Permits/Licences	
	No environmental deficiency was identified during site inspection.	
	H. Marine Ecology	
	No environmental deficiency was identified during site inspection.	
	I. Others	
	• Follow up on the previous session (Ref No.:250807), no major environmental deficiency	
	was identified during site inspection.	

	Name	Signature	Date
Recorded by	William Yeung		15 Aug 2025
Checked by	Karina Chan	Zoll	18 Aug 2025

Environmental Team for Trunk Road T2 – Traffic Control and Surveillance System (TCSS) and **Associated Works**

Checklist Reference Number	250821
Date	21 August 2025 (Thursday)
Time	09:30 – 12:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Air Quality	
	No environmental deficiency was identified during site inspection.	
	D. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	E. Waste/Chemical Management	
	No environmental deficiency was identified during site inspection.	
	F. Visual and Landscape	
	No environmental deficiency was identified during site inspection.	
	G. Permits/Licences	
	No environmental deficiency was identified during site inspection.	
	H. Marine Ecology	
	No environmental deficiency was identified during site inspection.	
	I. Others	
	Follow up on the previous session (Ref No.:250815), no major environmental deficiency was identified during site inspection.	

	Name	Signature	Date
Recorded by	William Yeung		21 Aug 2025
Checked by	Karina Chan	Zoll	25 Aug 2025

Environmental Team for Trunk Road T2 – Traffic Control and Surveillance System (TCSS) and **Associated Works**

Checklist Reference Number	250828
Date	28 August 2025 (Thursday)
Time	09:30 – 12:30

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Air Quality	
	No environmental deficiency was identified during site inspection.	
	D. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	E. Waste/Chemical Management	
	No environmental deficiency was identified during site inspection.	
	F. Visual and Landscape	
	No environmental deficiency was identified during site inspection.	
	G. Permits/Licences	
	No environmental deficiency was identified during site inspection.	
	H. Marine Ecology	
	No environmental deficiency was identified during site inspection.	
	I. Others	
	• Follow up on the previous session (Ref No.:250821), no major environmental deficiency	
	was identified during site inspection.	

	Name	Signature	Date
Recorded by	William Yeung	B	28 Aug 2025
Checked by	Karina Chan	Zelle	1 Sep 2025

Tseung Kwan O-Lam Tin Tunnel-Main Tunnel and Associated Works

Weekly Site Inspection Record Summary

Inspection Information

Checklist Reference Number	250806
Date	06 August 2025 (Wednesday)
Time	09:00 - 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations		
	B. Water Quality	Item No.	
	No environmental deficiency was identified during site inspection.		
	C. EcologyNo environmental deficiency was identified during site inspection.		
	D. Landscape & Visual		
	No environmental deficiency was identified during site inspection.		
	E. Air Quality		
	No environmental deficiency was identified during site inspection.		
	 F. Construction Noise Impact No environmental deficiency was identified during site inspection. 		
	G. Waste / Chemical Management		
	No environmental deficiency was identified during site inspection.		
	H. Permits/ Licences		
	No environmental deficiency was identified during site inspection.		
	I. Impact on Cultural Heritage		
	No environmental deficiency was identified during site inspection.		
	J. Others		
	• Referring to the last site inspection report (Ref. no.: 250731), no major environmental deficiency was identified.		

	Name	Signature	Date
Recorded by	William Yeung		06 August 2025
Checked by	Karina Chan	Jeffer	07 August 2025

Tseung Kwan O-Lam Tin Tunnel-Main Tunnel and Associated Works

Checklist Reference Number	250813
Date	13 August 2025 (Wednesday)
Time	09:00 - 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

B. Water Quality	
2. Water Quality	
No environmental deficiency was identified during site inspection.	
C. Ecology	
No environmental deficiency was identified during site inspection.	
D. Landscape & Visual	
No environmental deficiency was identified during site inspection.	
E. Air Quality	
No environmental deficiency was identified during site inspection.	
F. Construction Noise Impact	
No environmental deficiency was identified during site inspection.	
G. Waste / Chemical Management	
No environmental deficiency was identified during site inspection.	
H. Permits/Licences	
No environmental deficiency was identified during site inspection.	
I. Impact on Cultural Heritage	
No environmental deficiency was identified during site inspection.	
J. Others	
	 C. Ecology No environmental deficiency was identified during site inspection. D. Landscape & Visual No environmental deficiency was identified during site inspection. E. Air Quality No environmental deficiency was identified during site inspection. F. Construction Noise Impact No environmental deficiency was identified during site inspection. G. Waste / Chemical Management No environmental deficiency was identified during site inspection. H. Permits/ Licences No environmental deficiency was identified during site inspection. I. Impact on Cultural Heritage No environmental deficiency was identified during site inspection.

	Name	Signature	Date
Recorded by	William Yeung		13 August 2025
Checked by	Karina Chan	Zoller	14 August 2025

Tseung Kwan O-Lam Tin Tunnel-Main Tunnel and Associated Works

Checklist Reference Number	250820
Date	20 August 2025 (Wednesday)
Time	09:00 - 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Ecology	
	No environmental deficiency was identified during site inspection.	
	D. Landscape & Visual	
	No environmental deficiency was identified during site inspection.	
	E. Air Quality	
	No environmental deficiency was identified during site inspection.	
	F. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	G. Waste / Chemical Management	
250820-R1	• The Contractor is reminded to remove the accumulated general refuse (i.e. water bottles) on the slope.	Gli
	H. Permits/ Licences	
	No environmental deficiency was identified during site inspection.	
	I. Impact on Cultural Heritage	
	No environmental deficiency was identified during site inspection.	
	J. Others	
	• Referring to the last site inspection report (Ref. no.: 250813), no major environmental deficiency was identified.	

	Name	Signature	Date
Recorded by	William Yeung	R	20 August 2025
Checked by	Karina Chan	Zelle	21 August 2025

Tseung Kwan O-Lam Tin Tunnel-Main Tunnel and Associated Works

Checklist Reference Number	250827
Date	27 August 2025 (Wednesday)
Time	09:00 - 11:00

Ref. No.	Non-Compliance	Related Item No.
-	None identified	-

Ref. No.	Remarks/Observations	Related Item No.
	B. Water Quality	
	No environmental deficiency was identified during site inspection.	
	C. Ecology	
	No environmental deficiency was identified during site inspection.	
	D. Landscape & Visual	
	No environmental deficiency was identified during site inspection.	
	E. Air Quality	
	No environmental deficiency was identified during site inspection.	
	F. Construction Noise Impact	
	No environmental deficiency was identified during site inspection.	
	G. Waste / Chemical Management	
	No environmental deficiency was identified during site inspection.	
	H. Permits/ Licences	
	No environmental deficiency was identified during site inspection.	
	I. Impact on Cultural Heritage	
	No environmental deficiency was identified during site inspection.	
	J. Others	
	• Follow up on previous audit session (Ref No.:250820), all recorded items had been rectified.	

	Name	Signature	Date
Recorded by	William Yeung	K	27 August 2025
Checked by	Karina Chan	Zelle	28 August 2025

APPENDIX J ENVIRONMENTAL MITIGATION IMPLEMENTATION SCHEDULE (EMIS)

App J - ENVIRONMENTAL MITIGATION IMPLEMENTATION SCHEDULE (EMIS)

✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?			
Air Quality									
S3.8.1	Watering eight times a day on active works areas, exposed areas and paved haul roads	To minimize the dust impact	Contractor	All Active Work Sites	Construction phase	APCO			
S3.8.1	Enclosing the unloading process at barging point by a 3-sided screen with top tipping hall / mixing area in Work Area A, provision of water spraying and flexible dust curtains	To minimize the dust impact	Contractor	Barging Points	Construction phase	APCO			
\$3.8.7	Every stock of more than 20 bags of cement or dry pulverised fuel ash (PFA) should be covered entirely by impervious sheeting or placed in an area sheltered on the top and the 3 sides. • Use of frequent watering for particularly dusty construction areas and areas close to ASRs • Side enclosure and covering of any aggregate or dusty material storage piles to reduce emissions. Where this is not practicable owing to frequent usage, watering shall be applied to aggregate fines. • Open stockpiles shall be avoided or covered. Where possible, prevent placing dusty material storage piles near ASRs. • Tarpaulin covering of all dusty vehicle loads transported to, from and between site locations. • Establishment and use of vehicle wheel and body washing facilities at the exit points of the site. • Provision of wind shield and dust extraction units or similar dust mitigation measures at the loading area of barging point, and use of water sprinklers at the loading area where dust generation is likely during the loading process of loose material, particularly in dry seasons/ periods. • Provision of not less than 2.4m high hoarding from ground level along site boundary where adjoins a road, streets or other accessible to the public except for a site entrance or exit. • Imposition of speed controls for vehicles on site haul roads. • Where possible, routing of vehicles and positioning of construction plant should be at the maximum possible distance from ASRs • Every stock of more than 20 bags of cement or dry pulverised fuel ash (PFA) should be covered entirely by impervious sheeting or placed in an area sheltered on the top and the 3 sides. • Instigation of an environmental monitoring and auditing program to monitor the construction process in order to enforce controls and modify method of work if dusty conditions arise.	To minimize the dust impact	Contractor	All Construction Work Sites	Construction phase	APCO and Air Pollution Control (Construction Dust) Regulation			
/	Emission from Vehicles and Plants All vehicles shall be shut down in intermittent use. Only well-maintained plant should be operated on-site and plant should be serviced regularly to avoid emission of black smoke. All diesel fuelled construction plant within the works areas shall be powered by ultra low sulphur diesel fuel (ULSD)	Reduce air pollution emission from construction vehicles and plants	Contractor	All construction sites	Construction stage	APCO			

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
	Valid No-road Mobile Machinery (NRMM) labels should be provided to regulated machines	Reduce air pollution emission from construction vehicles and plants				APCO
Noise Mitigation Plan	Use of Temporary Noise Barriers (i.e Acoustic box, SilentUp and etc.) or Full Enclosure for PME according to the approved Noise Mitigation Plan	To minimize construction noise impact arising from the Project at the affected NSRs	Contractor	Work Sites	Construction phase	EIAO-TM, NCO
\$4.9	Good Site Practice Only well-maintained plant should be operated on-site and plant should be serviced regularly during the construction program Silencers or mufflers on construction equipment should be utilized and should be properly maintained during the construction program. Mobile plant, if any, should be sited as far away from NSRs as possible. Machines and plant (such as trucks) that may be in intermittent use should be shut down between works periods or should be throttled down to a minimum. Plant known to emit noise strongly in one direction should, wherever possible, be orientated so that the noise is directed away from the nearby NSRs. Material stockpiles and other structures should be effectively utilized, wherever practicable, in screening noise from on-site construction activities.	To minimize construction noise impact arising from the Project at the affected NSRs	Project Proponent	Work sites	Construction Period	EIAO-TM, NCO
S4.9	Scheduling of Construction Works during School Examination Period	To minimize construction noise impact arising from the Project at the affected NSRs	Contractor	Work site near school	Construction phase	EIAO-TM, NCO
Water Quality Impac	et (Construction Phase)					
S5.6.24	The dry density of filling material for the TKO-LT Tunnel reclamation should be 1,900kg/m ³ , with fine content of 25% or less	Control potential impacts from filling activities	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO
S5.8.1	Non-dredged method by constructing steel cellular caisson structure with stone column shall be adopted for construction of seawall foundation. During the stone column installation (also including the installation of steel cellular caisson), silt curtain shall be employed around the active stone column installation points.	Control potential impacts from filling activities	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO
\$5.8.2	Formation of seawall enclosing the reclamation for Road P2 (notwithstanding an opening of about 50m for marine access) shall be completed prior to the filling activities. The seawall opening of about 50m wide for marine access shall be selected at a location as indicatively shown in Appendix 5.10. No more than 3 filling barge trips per day shall be made with a maximum daily rate of 3,000m ³ (i.e. 1,000 m ³ per trip) for the filling operation at the reclamation area for Road P2. All filling works shall be carried out behind the seawall with the use of single silt curtain at the marine access.	Control potential impacts from filling activities	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO
Silt Curtain Deployment Plan	Silt curtains should be deployed properly to surround the works area. Maintenance of silt curtain should be provided. Sufficient stock of silt curtain should be provided on site.	Control potential impacts from marine woroks	Contractor	NE/2015/01	Construction stage	EIAO

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
\$5.8.3	Other good site practices should be undertaken during filling operations include: • all marine works should adopt the environmental friendly construction methods as far as practically possible including the use of cofferdams to cover the construction area to separate the construction works from the sea; • floating single silt curtain shall be employed for all marine works; • all vessels should be sized so that adequate clearance is maintained between vessels and the seabed in all tide conditions, to ensure that undue turbidity is not generated by turbulence from vessel movement or propeller wash; • all hopper barges should be fitted with tight fitting seals to their bottom openings to prevent leakage of material; • excess material shall be cleaned from the decks and exposed fittings of barges before the vessel is moved; • adequate freeboard shall be maintained on barges to reduce the likelihood of decks being washed by wave action; • loading of barges and hoppers should be controlled to prevent splashing of filling material into the surrounding water. Barges or hoppers should not be filled to a level that will cause the overflow of materials or polluted water during loading or transportation; • any pipe leakages shall be repaired quickly. Plant should not be operated with leaking pipes; • construction activities should not cause foam, oil, grease, scum, litter or other objectionable matter to be present on the water within the site or dumping grounds; and • before commencement of the reclamation works, the holder of Environmental Permit has to submit plans showing the phased construction of the reclamation, design and operation of the silt curtain.	Control potential impacts from filling activities and marine-based construction	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, Waste Disposal Ordinance (WDO)
S5.8.4	Site specific mitigation plan for reclamation areas using public fill materials should be submitted for EPD agreement before commencement of construction phase with due consideration of good site practices.	Control potential impacts from filling activities and marine based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
ERR \$5.6.1	To minimize water quality impact arising from the dredging and filling works for Reclamation for Road P2, the following mitigation measures shall be implemented: - Before carrying out any dredging and underwater filling works, a temporary barrier shall first be constructed to a height above the high water mark to completely enclose the works site (without any opening at the barrier wall) - The temporary barrier fully enclosing the dredging and underwater filling works site shall not be removed before completion of all dredging and underwater filling works. - Water quality sampling and testing shall be carried out to demonstrate that the water quality inside the enclosed barrier is comparable to the ambient or baseline levels prior to the removal of the fully enclosed barrier. - Silt curtains shall be deployed for the installation and removal of the temporary barrier and at the double water gates marine access opening during its operation.	Control potential impacts from dredging and filling works for Reclamation for Road P2	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.5	It is important that appropriate measures are implemented to control runoff and drainage and prevent high loading of SS from entering the marine environment. Proper site management is essential to minimise surface water runoff, soil erosion and sewage effluents.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
\$5.8.6	Any practical options for the diversion and realignment of drainage should comply with both engineering and environmental requirements in order to ensure adequate hydraulic capacity of all drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Design Stage and Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO, TM- DSS

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
\$5.8.7	Construction site runoff and drainage should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). Good housekeeping and stormwater best management practices, as detailed in below, should be implemented to ensure that all construction runoff complies with WPCO standards and no unacceptable impact on the WSRs arises due to construction of the TKO-LT Tunole. All discharges from the construction site should be controlled to comply with the standards for effluents discharged into the corresponding WCZ under the TM-DSS.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO, TM- DSS
S5.8.8 S5.8.8	Exposed soil areas should be minimised to reduce the potential for increased siltation, contamination of runoff, and crosion. Construction runoff related impacts associated with the above ground construction activities can be readily controlled through the use of appropriate mitigation measures which include: use of sediment traps; and adequate maintenance of drainage systems to prevent flooding and overflow.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.9	Construction site should be provided with adequately designed perimeter channel and pretreatment facilities and proper maintenance. The boundaries of critical areas of earthworks should be marked and surrounded by dykes or embankments for flood protection. Temporary ditches should be provided to facilitate runoff discharge into the appropriate watercourses, via a silt retention pond. Permanent drainage channels should incorporate sediment basins or traps and baffles to enhance deposition rates. The design of efficient silt removal facilities should be based on the guidelines in Appendix Al of ProPECC PN 1/94.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.10	Ideally, construction works should be programmed to minimise surface excavation works during the rainy season (April to September). All exposed earth areas should be completed as soon as possible after earthworks have been completed, or alternatively, within 14 days of the cessation of earthworks where practicable. If excavation of soil cannot be avoided during the rainy season, or at any time of year when rainstorms are likely, exposed slope surfaces should be covered by tarpaulin or other means.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
\$5.8.11	Sedimentation tanks of sufficient capacity, constructed from pre-formed individual cells of approximately 6 to 8m ³ capacity, are recommended as a general mitigation measure which can be used for settling surface runoff prior to disposal. The system capacity is flexible and able to handle multiple inputs from a variety of sources and particularly suited to applications where the influent is pumped.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.12	Earthworks final surfaces should be well compacted and the subsequent permanent work or surface protection should be carried out immediately after the final surfaces are formed to prevent erosion caused by rainstorms. Appropriate drainage like intercepting channels should be provided where necessary.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.13	Measures should be taken to minimize the ingress of rainwater into trenches. If excavation of trenches in wet seasons is necessary, they should be dug and backfilled in short sections. Rainwater pumped out from trenches or foundation excavations should be discharged into storm drains via silt removal facilities.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.14	Open stockpiles of construction materials (for examples, aggregates, sand and fill material) of more than 50m ³ should be covered with tarpaulin or similar fabric during rainstorms. Measures should be taken to prevent the washing away of construction materials, soil, silt or debris into any drainage system.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
\$5.8.15	Manholes (including newly constructed ones) should always be adequately covered and temporarily sealed so as to prevent silt, construction materials or debris being washed into the drainage system and storm runoff being directed into foul sewers. Discharge of surface run-off into foul sewers must always be prevented in order not to unduly overload the foul sewerage system.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
85.8.16	Precautions to be taken at any time of year when rainstorms are likely, actions to be taken when a rainstorm is imminent or forecast, and actions to be taken during or after rainstorms are summarised in Appendix A2 of ProPECC PN 1/94. Particular attention should be paid to the control of silty surface runoff during storm events, especially for areas located near steep slopes.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S5.8.17	Oil interceptors should be provided in the drainage system and regularly cleaned to prevent the release of oils and grease into the storm water drainage system after accidental spillages. The interceptor should have a bypass to prevent flushing during periods of heavy rain.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.18	All vehicles and plant should be cleaned before leaving a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. An adequately designed and located wheel washing bay should be provided at every site exit, and washwater should have sand and silt settled out and removed at least on a weekly basis to ensure the continued efficiency of the process. The section of access road leading to, and exiting from, the wheelwash bay to the public road should be paved with sufficient backfall toward the wheel-wash bay to prevent vehicle tracking of soil and silty water to public roads and drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.19	Silt removal facilities, channels and manholes should be maintained and the deposited silt and grit should be removed regularly, at the onset of and after each rainstorm to ensure that these facilities are functioning properly at all times.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.20	It is recommended that on-site drainage system should be installed prior to the commencement of other construction activities. Sediment traps should be installed in order to minimise the sediment loading of the effluent prior to discharge into foul sewers. There shall be no direct discharge of effluent from the site into the sea.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.21	All temporary and permanent drainage pipes and culverts provided to facilitate runoff discharge should be adequately designed for the controlled release of storm flows. All sediment control measures should be regularly inspected and maintained to ensure proper and efficient operation at all times and particularly following rain storms. The temporarily diverted drainage should be reinstated to its original condition when the construction work has finished or the temporary diversion is no longer required.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.22	All fuel tanks and storage areas should be provided with locks and be located on scaled areas, within bunds of a capacity equal to 110% of the storage capacity of the largest tank, to prevent spilled fuel oils from reaching the coastal waters.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.23	Minimum distances of 100m shall be maintained between the existing or planned stormwater discharges and the existing or planned seawater intakes during construction and operational phases	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, TMDSS
S5.8.24	Under normal circumstances, groundwater pumped out of wells, etc. for the lowering of ground water level in basement or foundation construction, and groundwater scepage pumped out of tunnels or caverns under construction should be discharged into storm drains after the removal of silt in silt removal facilities.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.25 - S5.8.27 & Table 5.18	Grouting would be adopted as measure to reduce the groundwater inflow into the tunnel. During the tunnel excavation, the inflow rate of groundwater into the tunnel will be measured during the excavation. The groundwater levels above the tunnel will also be monitored by piezometers. If the inflow rate exceeds the pre-determined groundwater control criteria or the groundwater drawdown exceeds the required limit, pre-excavation grouting will be required to reduce the groundwater inflow. No significant change of groundwater levels would therefore be expected. Any chemicals/ foaming agents which would be entrained to the groundwater should be biodegradable and non-toxic throughout the tunnel construction. Potential groundwater quality impact would be minimal as the used material is non-toxic and biodegradable. No adverse groundwater quality would therefore be expected. Prescriptive measures in the form of an Action Plan with pre-emptive and re-active to preserve the groundwater levels at all times during the tunnel construction are set out in Table 5.18.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO, Buildings Ordinance
S5.8.28	Water used in ground boring and drilling for site investigation or rock / soil anchoring should as far as practicable be recirculated after sedimentation. When there is a need for final disposal, the wastewater should be discharged into storm drains via silt removal facilities.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Design Stage and Construction Phas	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.29 - S5.8.31	Wastewater generated from the washing down of mixing trucks and drum mixers and similar equipment should whenever practicable be recycled. The discharge of wastewater should be kept to a minimum. To prevent pollution from wastewater overflow, the pump sump of any water recycling system should be provided with an online standby pump of adequate capacity and with automatic alternating devices. Under normal circumstances, surplus wastewater may be discharged into foul sewers after treatment in silt removal and pH adjustment facilities (to within the pH range of 6 to 10). Disposal of wastewater into storm drains will require more elaborate treatment.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S5.8.32	All vehicles and plant should be cleaned before they leave a construction site to ensure no earth, mud, debris and the like is deposited by them on roads. A wheel washing bay should be provided at every site exit if practicable and wash-water should have sand and silt settled out or removed before discharging into storm drains. The section of construction road between the wheel washing bay and the public road should be paved with backfall to reduce vehicle tracking of soil and to prevent site run-off from entering public road drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.33	Bentonite slurries used in diaphragm wall and borepile construction should be reconditioned and reused wherever practicable. If the disposal of a certain residual quantity cannot be avoided, the used slurry may be disposed of at the marine spoil grounds subject to obtaining a marine dumping licence from EPD on a case-by-case basis.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.34	If the used bentonite slurry is intended to be disposed of through the public drainage system, it should be treated to the respective effluent standards applicable to foul sewer, storm drains or the receiving waters as set out in the WPCO Technical Memorandum on Effluent Standards.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.35	Water used in water testing to check leakage of structures and pipes should be reused for other purposes as far as practicable. Surplus unpolluted water could be discharged into storm drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.36	Sterilization is commonly accomplished by chlorination. Specific advice from EPD should be sought during the design stage of the works with regard to the disposal of the sterilizing water. The sterilizing water should be reused wherever practicable.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Design Stage and Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.37	Before commencing any demolition works, all sewer and drainage connections should be sealed to prevent building debris, soil, sand etc. from entering public sewers/drains.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.38	Wastewater generated from building construction activities including concreting, plastering, internal decoration, cleaning of works and similar activities should not be discharged into the stormwater drainage system. If the wastewater is to be discharged into foul sewers, it should undergo the removal of settleable solids in a silt removal facility, and pH adjustment as necessary	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.39	Acidic wastewater generated from acid cleaning, etching, pickling and similar activities should be neutralized to within the pH range of 6 to 10 before discharging into foul sewers. If there is no public foul sewer in the vicinity, the neutralized wastewater should be tinkered off site for disposal into foul sewers or treated to a standard acceptable to storm drains and the receiving waters	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S5.8.40	Wastewater collected from canteen kitchens, including that from basins, sinks and floor drains, should be discharged into foul sewer via grease traps capable of providing at least 20 minutes retention during peak flow.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.41	Drainage serving an open oil filling point should be connected to storm drains via a petrol interceptor with peak storm bypass.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
\$5.8.42	Vehicle and plant servicing areas, vehicle wash bays and lubrication bays should as far as possible be located within roofed areas. The drainage in these covered areas should be connected to foul sewers via a petrol interceptor. Oil leakage or spillage should be contained and cleaned up immediately. Waste oil should be collected and stored for recycling or disposal in accordance with the Waste Disposal Ordinance.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
S5.8.43	Construction work force sewage discharges on site are expected to be connected to the existing trunk sewer or sewage treatment facilities. The construction sewage may need to be handled by portable chemical toilets prior to the commission of the on-site sewer system. Appropriate numbers of portable toilets shall be provided by a licensed contractor to serve the large number of construction workers over the construction site. The Contractor shall also be responsible for waste disposal and maintenance practices.	Control potential impacts from construction site runoff and land-based construction	CEDD's Contractors	Work site	Construction Phase	ProPECC PN 1/94, EIAOTM, WPCO
\$5.8.44	Contractor must register as a chemical waste producer if chemical wastes would be produced from the construction activities. The Waste Disposal Ordinance (Cap 354) and its subsidiary regulations in particular the Waste Disposal (Chemical Waste) (General) Regulation should be observed and complied with for control of chemical wastes.	Control potential impacts from accidental spillage of chemicals	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, WDO
S5.8.45	Any service shop and maintenance facilities should be located on hard standings within a bunded area, and sumps and oil interceptors should be provided. Maintenance of vehicles and equipment involving activities with potential for leakage and spillage should only be undertaken within the areas appropriately equipped to control these discharges.	Control potential impacts from accidental spillage of chemicals	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO
\$5.8.46	Disposal of chemical wastes should be carried out in compliance with the Waste Disposal Ordinance. The "Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes" published under the Waste Disposal Ordinance details the requirements to deal with chemical wastes. General requirements are given as follows: • suitable containers should be used to hold the chemical wastes to avoid leakage or spillage during storage, handling and transport; • chemical waste containers should be suitably labelled, to notify and warn the personnel who are handling the wastes, to avoid accidents; and • storage area should be selected at a safe location on site and adequate space should be allocated to the storage area.	Control potential impacts from accidental spillage of chemicals	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO, WDO
S5.8.47	Collection and removal of floating refuse should be performed at regular intervals on a daily basis. The contractor should be responsible for keeping the water within the site boundary and the neighbouring water free from rubbish.	Control potential impacts from floating refuse and debris	CEDD's Contractors	Work site	Construction Phase	EIAO-TM, WPCO,
Ecological Impact						
\$6.8.4	Measures to Minimize Disturbance Use of Quiet Mechanical Plant during the construction phase should be adopted wherever possible. Hoarding or fencing should be erected around the works area boundaries during the construction phase. The hoarding would screen adjacent habitats from construction phase activities, reduce noise disturbance to these habitats and also to restrict access to habitats adjacent to works areas by site workers; Regular spraying of haul roads to minimize impacts of dust deposition on adjacent vegetation and habitats during the construction activities	Minimize noise, human and traffic disturbance to terrestrial habitat and wildlife; and reduce dust generation	Design Team / Contractor	Land-based works are	Construction Phase	N/A

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
\$6.8.5	Standard Good Site Practice Placement of equipment or stockpile in designated works areas and access routes selected on existing disturbed land to minimise disturbance to natural habitats. Construction activities should be restricted to works areas that should be clearly demarcated. The works areas should be reinstated after completion of the works. Waste skips should be provided to collect general refuse and construction wastes. The wastes should be properly disposed off-site in a timely manner. General drainage arrangements should include sediment and oil traps to collect and control construction site run-off. Open burning on works sites is illegal, and should be strictly prohibited. Measures should also be put into place so that litter, fuel and solvents do not enter the nearby watercourses.	Reduce disturbance to surrounding habitats	Contractor	Land-based works are	Construction Phase	N/A
\$6.8.6	Measure to Minimize Groundwater Inflow The drained tunnel construction method with groundwater inflow control measures would generally be adopted. During the tunnel excavation, pre-excavation grouting could be adopted to reduce the groundwater inflow and ensure that the tunnel would meet the long term water tightness requirements.	Minimize groundwater inflow	Contractor	Tunnel	Construction Phase	N/A
\$6.8.8	Measure to Minimize Impact on Corals Coral translocation It is recommended to translocate the affected coral colonies, except the locally common Oulastrea crispata, within the reclamation area and bridge footprint to the other suitable locations as far as practicable. The coral translocation should be conducted during the winter months (November-March) in order to avoid disturbance during their spawning period (i.e. July to October). A detailed coral translocation plan with a description on the methodology for pretranslocation coral survey, translocation methodology, identification/proposal of coral recipient site, monitoring methodology for posttranslocation should be prepared during the detailed design stage. The coral translocation plan should be subject to approval by relevant authorities (e.g. EPD and AFCD) before commencement of the coral translocation. All the translocation exercises should be conducted by experienced marine ecologist(s) who is/are approved by AFCD prior to commencement of coral translocation. Post translocation Monitoring A coral monitoring programme is recommended to assess any adverse and unacceptable impacts to the translocated coral communities Information gathered during each posttranslocation monitoring survey should include observations on the presence, survival, health condition and growth of the translocated coral colonies. These parameters should then be compared with the baseline results collected from the pre-translocation survey.	Minimize loss of coral	Design team, contractor, project operator	Within reclamation areas and pier footprint	Prior construction	N/A

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
\$6.8.9 \$6.8.10	Deployment of silt curtains around the active stone column installation points, opening of newly installed seawall and marine works area. Diverting of the site runoff to silt trap facilities before discharging into storm drain; Proper waste and dumping management; and Standard good-site practice for land-based construction.	Control water quality impact, especially on suspended solid level; minimize the contamination of wastewater discharge, accidental chemical spillage and construction site runoff to the receiving water bodies	Design Team, contractor	Marine and landbased works area	Construction phase	WQO
S6.8.11	Compensation for Vegetation Loss Felling of mature trees should be compensated by planting of standard or heavy standard trees within or in vicinity of the affected area as far as practicable. Such compensatory planting for trees should be provided with at least a 1:1 ratio. In addition, vegetation at the temporarily affected area should be reinstated with species similar to the existing condition.	Compensate for the vegetation loss	Design Team, contractor	Land-based works area	Construction phase	N/A
Fisheries Impact						
S7.7.3	Measure to Control Water Quality Impact Deployment of silt curtains around the active stone column installation points, opening of newly installed seawall and marine works area.	Control water quality impact, especially on suspended solid level	Design Team / Contractor	Marine work area	Construction phase	WQO
Waste Management (
S8.6.3	Good Site Practices and Waste Reduction Measures Nomination of an approved person, such as a site manager, to be responsible for good site practices, arrangements for collection and effective disposal to an appropriate facility, of all wastes generated at the site; Training of site personnel in site cleanliness, proper waste management and chemical handling procedures; Provision of sufficient waste disposal points and regular collection of waste; Appropriate measures to minimize windblown litter and dust during transportation of waste by either covering trucks or by transporting wastes in enclosed containers; and Regular cleaning and maintenance programme for drainage systems, sumps and oil interceptors.	To reduce waste management impacts	Contractor	All work sites	Construction Phase	Waste Disposal Ordinance (Cap. 354) Land (Miscellaneous Provisions) Ordinance (Cap. 28)
\$8.6.4	Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal; Encourage collection of aluminium cans by providing separate labelled bins to enable this waste to be segregated from other general refuse generated by the workforce; Proper storage and site practices to minimize the potential for damage or contamination of construction materials; and Plan and stock construction materials carefully to minimize amount of waste generated and avoid unnecessary generation of waste.	To achieve waste reduction	Contractor	All work sites	Construction Phase	Waste Disposal Ordinance (Cap. 354) Land (Miscellaneous Provisions) Ordinance (Cap. 28)
\$8.6.5	Good Site Practices and Waste Reduction Measures (con't) The Contractor shall prepare and implement a WMP as part of the EMP in accordance with ETWB TCW No. 19/2005 which describes the arrangements for avoidance, reuse, recovery, recycling, storage, collection, treatment and disposal of different categories of waste to be generated from the construction activities. Such a management plan should incorporate site specific factors, such as the designation of areas for segregation and temporary storage of reusable and recyclable materials. The EMP should be submitted to the Engineer for approval. The Contractor should implement the waste management practices in the EMP throughout the construction stage of the Project. The EMP should be reviewed regularly and updated by the Contractor.	To achieve waste reduction	Contractor	All work sites	Construction Phase	ETWB TCW No. 19/2005

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S8.6.6	Good Site Practices and Waste Reduction Measures (con't) C&D materials would be reused in the project and other local concurrent projects as far as possible.	To achieve waste reduction	Contractor	All work sites	Construction Phase	ETWB TCW No. 19/2005
S8.6.7	Storage, Collection and Transportation of Waste Should any temporary storage or stockpiling of waste is required, recommendations to minimize the impacts include: • Waste, such as soil, should be handled and stored well to ensure secure containment, thus minimizing the potential of pollution; • Maintain and clean storage areas routinely; • Stockpiling area should be provided with covers and water spraying system to prevent materials from wind-blown or being washed away; and • Different locations should be designated to stockpile each material to enhance reuse.	To minimize potential adverse environmental impacts arising from waste storage	Contractor	All work sites	Construction Phase	ETWB TCW No. 19/2005
S8.6.8/ Waste Management Plan	Storage, Collection and Transportation of Waste (con't) Remove waste in timely manner; Waste collectors should only collect wastes prescribed by their permits; Impacts during transportation, such as dust and odour, should be mitigated by the use of covered trucks or in enclosed containers; Obtain relevant waste disposal permits from the appropriate authorities, in accordance with the Waste Disposal Ordinance (Cap. 354), Waste Disposal (Charges for Disposal of Construction Waste) Regulation (Cap. 345) and the Land (Miscellancous Provisions) Ordinance (Cap. 28); Waste should be disposed of at licensed waste disposal facilities/ alternative disposal ground approved by RE and DEP; and Maintain records of quantities of waste generated, recycled and disposed.	To minimize potential adverse environmental impacts arising from waste collection and disposal	Contractor	All work sites	Construction Phase	ETWB TCW No. 19/2005
S8.6.9/ Waste Management Plan	Implementation of trip ticket system with reference to DEVB TC(W) No. 6/2010, Trip Ticket System for Disposal of Construction & Demolition Materials, to monitor disposal of waste and to control fly-tipping at PFRFs or landfills. A recording system for the amount of waste generated, recycled and disposed (including disposal sites) should be proposed.	To minimize potential adverse environmental impacts arising from waste collection and disposal	Contractor	All work sites	Construction Phase	DEVB TCW No. 6/2010
S8.6.11 - S8.6.13/ Waste Management Plan	Sorting of C&D Materials Sorting to be performed to recover the inert materials, reusable and recyclable materials before disposal off-site. Specific areas shall be provided by the Contractors for sorting and to provide temporary storage areas for the sorted materials. The C&D materials should at least be segregated into inert and non-inert materials, in which the inert portion could be reused and recycled in the reclamation as far as practicable before delivery to PFRFs. While opportunities for reusing the non-inert portion should be investigated before disposal of at designated landfills	To minimize potential adverse environmental	Contractor	All work sites	Construction Phase	DEVB TCW No. 6/2010 ETWB TCW No. 33/2002 ETWB TCW No. 19/2005
\$8.6.17 – \$8.6.20	Requirements of the Air Pollution Control (Construction Dust) Regulation, where relevant, shall be adhered to during boring, excavation, transportation and disposal of sediments or cement stabilization of sodiment. A treatment area should be confined for carrying out the cement stabilization mixing and temporary stockpile. The area should be designed to prevent leachate from entering the ground. Leachate, if any, should be collected and discharged according to the Water Pollution Control Ordinance (WPCO). In order to minimise the potential odour / dust emissions during boring, excavation and transportation of the sediment, the excavated sediments should be kept wet during excavation/boring and should be properly covered when placed on barges/trucks. Loading of the excavated sediment to the barge should be controlled to avoid splashing and overflowing of the sediment slurry to the surrounding water. In order to minimise the exposure to contaminated materials, workers should, when necessary, wear appropriate personal protective equipments (PPE) when handling contaminated sediments. Adequate washing and cleaning facilities should also be provided on site.	To determine the best handling and treatment of sediment	Contractor	All works areas with sediments concern	Construction Phase	ETWB TCW No. 19/2005

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S8.6.24 - S8.6.28/ Waste Management Plan	The excavated sediments is expected to be loaded onto the barge and transported to the designated disposal sites allocated by the MFC. The excavated sediment would be disposed of according to its determined disposal options and ETWB TC(W) No. 34/2002. Stockpiling of contaminated sediments should be avoided as far as possible. If temporary stockpiling of contaminated sediments is necessary, the excavated sediment should be covered by tarpaulin and the area should be placed within earth bunks or sand bags to prevent leachate from entering the ground, nearby drains and surrounding water bodies. The stockpiling areas should be completely paved or covered by linings in order to avoid contamination to underlying soil or groundwater. Separate and clearly defined areas should be provided for stockpiling of contaminated and uncontaminated materials. Leachate, if any, should be collected and discharged according to the Water Pollution Control Ordinance (WPCO). In order to minimise the potential odour / dust emissions during boring and transportation of the sediment, the excavated sediments should be kept wet during excavation/boring and should be properly covered when placed on barges. Loading of the excavated sediment to the barge should be controlled to avoid splashing and overflowing of the sediment slurry to the surrounding water. The barge transporting the sediments to the designated disposal sites should be equipped with tight fitting seals to prevent leakage and should not be filled to a level that would cause overflow of materials or laden water during loading or transportation. In addition, monitoring of the barge loading shall be conducted to ensure that loss of material does not take place during transportation. Transport barges or vessels shall be equipped with automatic self-monitoring devices as specified by the DEP. In order to minimise the exposure to contaminated materials, workers should, when necessary, wear appropriate personal protective equipments (PPE) when handling contaminated sediments. Ade	To ensure handling of sediments are in accordance to statutory requirements	Contractor	All works areas with sediments concern	Construction Phase	ETWB TC(W) No. 34/2002 & Dumping at Sea Ordinance
S8.6.26/ Waste Management Plan	• If chemical wastes are produced at the construction site, the Contractor would be required to register with the EPD as a Chemical Waste Producer and to follow the guidelines stated in the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes. Good quality containers compatible with the chemical wastes should be used, and incompatible chemicals should be stored separately. Appropriate labels should be securely attached on each chemical waste container indicating the corresponding chemical characteristics of the chemical waste, such as explosive, flammable, oxidizing, irritant, toxic, harmful, corrosive, etc. The Contractor shall use a licensed collector to transport and dispose of the chemical wastes, to either the Chemical Waste Treatment Centre at Tsing Yi, or other licensed facility, in accordance with the Waste Disposal (Chemical Waste) (General) Regulation.	To ensure proper management of chemical waste	Contractor	All works sites	Construction Phase	Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes Waste Disposal (Chemical Waste) (General) Regulation

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?				
S8.6.27/ Waste Management Plan	General Refuse • General refuse should be stored in enclosed bins or compaction units separate from C&D material. A reputable waste collector should be employed by the contractor to remove general refuse from the site, separately from C&D material. Preferably an enclosed and covered area should be provided to reduce the occurrence of 'wind blown' light material.	To ensure proper management of general refuse	Contractor	All works sites	Construction Phase	Public Health and Municipal Services Ordinance (Cap. 132)				
Impact on Cultural H	Impact on Cultural Heritage (Construction Phase)									
S9.6.4	Dust and visual impacts Temporarily fenced off buffer zone with allowance for public access (minimum 1 m) should be provided; The open yard in front of the temple should be kept as usual for annual Tin Hau festival; Monitoring of vibration impacts should be conducted when the construction works are less than 100m from the temple.	To prevent dust and visual impacts	Contractors	Work areas	Construction Phase	EIAO; GCHIA; AMO				
\$9.6.4	Indirect vibration impact Vibration level is suggest to be controlled within a peak particle velocity (ppv) limit of 5mm/s measured inside the historical buildings; Monitoring of vibration should be carried out during construction phase. Tilting and settlement monitoring should will be applied on the Cha Kwo Ling Tin Hau Temple as well. A proposal with details for the mitigation measures and monitoring of impacts on built heritage shall be submitted to AMO for comments before commencement of work.	To prevent indirect vibration impact	Contractors	Work areas	Construction Phase	Vibration Limits on Heritage Buildings by CEDD; GCHIA; AMO.				
Built Heritage Mitigation Plan	Established Alert, Alarm and Action Level for the monitoring parameters. To increase the instrumentation monitoring and reporting frequency. To propose detailed action plan or contingency plan for the Engineer's approval when AAA Level is reached or exceeded.	To prevent vibration impacts	NE/2015/01	Tin Hau Temple	Construction Phase	Vibration Limits on Heritage Buildings by CEDD; GCHIA; AMO.				
Landscape and Visua	l Impact (Construction Phase)									
Table 10.8.1/ Landscape Mitigation Plan	CM1 - Construction area and contractor's temporary works areas to be minimised to avoid impacts on adjacent landscape.	Avoid impact on adjacent landscape areas	CEDD (via Contractor)	General	Construction planning and during construction period	N/A				
Table 10.8.1/ Landscape Mitigation Plan	CM2 - Reduction of construction period to practical minimum.	Minimise duration of impact	CEDD (via Contractor)	N/A	Construction planning	N/A				
Table 10.8.1/ Landscape Mitigation Plan	CM3 - Topsoil, where the soil material meets acceptable criteria and where practical, to be stripped and stored for re-use in the construction of the soft landscape works. The Contract Specification shall include storage and reuse of topsoil as appropriate.	To allow re-use of topsoil	CEDD (via Contractor)	General	Site clearance	As per the Particular Specification				
Table 10.8.1/ Landscape Mitigation Plan	CM4 - Existing trees at boundary of site and retained trees within site boundary to be carefully protected during construction. Detailed Tree Protection Specification shall be provided in the Contract Specification, under which the Contractor shall be required to submit, for approval, a detailed working method statement for the protection of trees prior to undertaking any works adjacent to all retained trees, including trees in contractor's works areas. (Tree protection measures will be detailed at Tree Removal Application stage).	To minimize tree loss	CEDD (via Contractor)	As per approved Tree Removal Application(s)	Site clearance and throughout construction period	ETWB TC 3/2006 and as per tree protection measures in Particular Specification				

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?	
Table 10.8.1/ Landscape Mitigation Plan	CM5 - Trees unavoidably affected by the works shall be transplanted where practicable. Where possible, trees should be transplanted direct to permanent locations rather than temporary holding nurseries. A detailed tree transplanting specification shall be provided in the Contract Specification and sufficient time for preparation shall be allowed in the construction programme.	To maximize preservation of existing trees	CEDD (via Contractor)	As per approved Tree Removal Application(s)	Site clearance	ETWB TC 3/2006 and as per tree protection measures in Particular Specification	
Table 10.8.1/ Landscape Mitigation Plan	CM6 - Advance screen planting of fast growing tree and shrub species to noise barriers and hoardings. Trees shall be capable of reaching a height >10m within 10 years.	To maximize screening of the works	CEDD (via Contractor)	At Lam Tin Interchange and edge of Road P2 landscape deck, TKO	Beginning of construction period	N/A	
Table 10.8.1/ Landscape Mitigation Plan	CM7 - Hydroseeding or sheeting of soil stockpiles with visually unobtrusive material	To reduce visual intrusion	CEDD (via Contractor)	General	Throughout construction period	As per Particular Specification	
Table 10.8.1/ Landscape Mitigation Plan	M8 - Control of night-time lighting by hooding all lights and through minimisation of night To reduce visual intrusion CEDD (via Contractor related to the contractor relate		CEDD (via Contractor)	General	Throughout construction period	N/A	
Table 10.8.1/ Landscape Mitigation Plan	CM9 - Screening of works areas with hoardings with appropriate colours compatible with the surrounding area	Reduction of visual intrusion	CEDD (via Contractor)	Project site Boundary	Excretion of site hoarding	N/A	
Table 10.8.1/ Landscape Mitigation Plan	CM10 - Avoidance of excessive height and bulk of site buildings and structure	Reduction of visual intrusion and integration with environment	CEDD (via Contractor)	Built structures	Design and construction stage	N/A	
Table 10.8.1/ Landscape Mitigation Plan	CM11 - Limitation of run-off into freshwater streams, ponds and sea areas	Avoidance of contamination of water courses and water bodie	CEDD (via Contractor)	TKO reclamation, TKO tunnel portal, Cha Kwo Ling roadworks	Throughout construction period	N/A	
Table 10.8.1	CM12 - Minimise area of reclamation and design the edges sensitively to tie in with adjacent coastline characte	Minimise loss of Junk Bay and integration with existing coastlin	CEDD (via Contractor)	Temporary reclamation for barging points at TKO and Lam Tin and permanent reclamation for TKO Interchange slip roads and Road P2	Construction planning and reclamation stages	N/A	
Landfill Gas Hazard (Design and Construction Phase)							
S11.5.9	A Safety Officer, trained in the use of gas detection equipment and landfill gas-related hazards, should be present on site throughout the groundworks phase. The Safety Officer should be provided with an intrinsically safe portable instrument, which is appropriately calibrated and able to measure the following gases in the ranges indicated below:	Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill	Construction phase	EPD's Landfill Gas Hazard Assessment	
	Methane 0-100% LEL and 0100% √/v Carbon dioxide 0-100% Oxygen 0-21%			Consultation Zone		Guidance Note	

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S11.5.10 S11.5.25	Safety Measures For staff who work in, or have responsibility for "at risk" area, such as all excavation workers, supervisors and engineers working within the Consultation Zone, should receive appropriate training on working in areas susceptible to landfill gas, fire and explosion hazards. An excavation procedure or code of practice to minimize landfill gas related risk should be devised and carried out. No worker should be allowed to work alone at any time in or near to any excavation. At least one other worker should be available to assist with a rescue if needed. Smoking, naked flames and all other sources of ignition should be prohibited within 15m of any excavation or ground-level confined space. "No smoking" and "No naked flame" notices should be posted prominently on the construction site and, if necessary, special areas should be designed for smoking. Welding, flame-cutting or other hot works should be confined to open areas at least 15m from any trench or excavation. Welding, flame-cutting or other hot works may only be carried out in trenches or confined spaces when controlled by a "permit to work" procedure, properly authorized by the Safety Officer (or, in the case of small developments, other appropriately qualified person). The permit to work procedure should set down clearly the requirements for continuous monitoring for methane, carbon dioxide and oxygen throughout the period during which the hot works are in progress. The procedure should also require the presence of an appropriately qualified person, in attendance outside the 'confined area', who should be responsible for reviewing the gas measurements as they are made, and who should have executive responsibility for suspending the work in the event of unacceptable or hazardous conditions. Only those workers who are appropriately trained and fully aware of the potentially hazardous conditions which may arise should be permitted to carry out hot works in confined areas. Where there are any temporary site offices, or any other building	Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill Consultation Zone	Construction phase	EPD's Landfill Gas Hazard Assessment Guidance Note Labour Department's Code of Practice for Safety and Health at Work in Confined Space

EIA Ref. / EP Submission	Recommended Mitigation Measures	Objectives of the recommended Measures & Main Concerns to address	Who to implement the measures?	Location of the measures	When to Implement the measures?	What requirements or standards for the measures to achieve?
S11.5.10 S11.5.25	The contractor should formulate a health and safety policy, standards and instructions for site personnel to follow. All personnel who work on the site and all visitors to the site should be made aware of the possibility of ignition of gas in the vicinity of excavations. Safety notices (in Chinese and English) should be posted at prominent position around the site warning danger of the potential hazards. Service runs within the Consultation Zone should be designated as "special routes"; utilities companies should be informed of this and precautionary measures should be implemented. Precautionary measures should include ensuring that staff members are aware of the potential hazards of working in confined spaces such as manholes and service chambers, and that appropriate monitoring procedures are in place to prevent hazards due to asphyxiating atmospheres in confined spaces. Detailed guidance on entry into confined spaces is given in Code of Practice on Safety and Health at Work in Confined Spaces (Labour Department, Hong Kong).					
	 Periodically during ground-works construction within the 250m Consultation Zone, the works area should be monitored for methane, carbon dioxide and oxygen using appropriately calibrated portable gas detection equipment. The monitoring frequency and areas to be monitored should be set down prior to commencement of ground-works either by the Safety Officer or an approved and appropriately qualified person. 					
S11.5.26 - S11.5.31	● Routine monitoring should be carried out in all excavations, manholes, chambers, relocation of monitoring wells and any other confined spaces that may have been created. All measurements in excavations should be made with the extended monitoring who located not more than 10 mm from the exposed ground surface. Monitoring should be performed properly to make sure that the area is free of landfill gas before any man enters into the area. ● For excavations deeper than 1m, measurements should be carried out: • at the ground surface before excavation commences; • immediately before any worker enters the excavation; • at the beginning of each working day for the entire period the excavation remains open; and • periodically throughout the working day whilst workers are in the excavation. • For excavations between 300mm and 1m deep, measurements should be carried out: • directly after the excavation has been completed; and • periodically whilst the excavation remains open. • For excavations less than 300mm deep, monitoring may be omitted, at the discretion of the Safety Officer or other appropriately qualified person. • Depending on the results of the measurements, actions required will vary and should be set down by the Safety Officer or other appropriately qualified person. • The exact frequency of monitoring should be determined prior to the commencement of works, but should be at least once per day, and be carried out by a suitably qualified or qualified person before starting the work of the day. Measurements shall be recorded and kept as a record of safe working conditions with copies of the site diary and submitted to the Engineer for approval. The Contractor may elect to carry out monitoring via an automated monitoring system.	Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill Consultation Zone	Construction phase	EPD's Landfill Gas Hazard Assessment Guidance Note
\$11.5.32	The hazards from landfill gas during the construction stage within the Sai Tso Wan Landfill Consultation Zone should be minimized by suitable precautionary measures recommended in Chapter 8 of the Landfill Gas Hazard Assessment Guidance Note.	construction stage within the Sai Tso Wan Protect the workers from landfill gas hazards	Contractor	Project sites within the Sai Tso Wan Landfill Consultation Zone	Construction phase	EPD's Landfill Gas Hazard Assessment Guidance Note

Table II - Observation / Reminder / Non-compliance made during Site Audit

Key:

- ✓ Observation/reminder was made during site audit but improved/rectified by the contractor in the next site audit
- X Observation/reminder was made during site audit but not yet improved/rectified by the contractor in the next site audit
- # Follow up action will be reported in next reporting month
- * Non-compliance of mitigation measure
- · Non-compliance but improved by the contractor

EIA Ref	Recommended Mitigation Measures	Details of Reminder/Observation	Recorded Date/ Contract No	Status
Air Quality				
Construction 1	Noise Impact			
Water Quality	Impact			
\$5.8.7	Construction site runoff and drainage should be prevented or minimised in accordance with the guidelines stipulated in the EPD's Practice Note for Professional Persons, Construction Site Drainage (ProPECC PN 1/94). Good housekeeping and stormwater best management practices, as detailed in below, should be implemented to	Stagnant water was observed at Portion SB.	7 Aug 2025 (ED/2018/04)	√
\$5.8.7	ensure that all construction runoff complies with WPCO standards and no unacceptable impact on the WSRs arises due to construction of the TKO-LT Tunnel. All discharges from the construction site should be controlled to comply with the standards for effluents. discharged into the corresponding WCZ under the TM-DSS.	Stagnant water was observed at Portion TY.	7 Aug 2025 (ED/2018/04)	✓
Ecological Imp	pact			
Fisheries Impa	nct			•
Waste Manage	ement			•
S8.6.8/ Waste Management Plan	Remove waste in timely manner.	The Contractor is reminded to remove the accumulated general refuse (i.e. water bottles) on the slope.	20 Aug 2025 (NE/2015/01)	√
Landscape and	d Visual Impact	<u>, </u>		•
Landfill Gas H	lazards			•

APPENDIX L EVENT AND ACTION PLANS

Event and Action Plan for Air Quality (Dust)

EX ZENICE	ACTION						
EVENT	ET	IEC	ER	CONTRACTOR			
Action level being exceeded by one sampling	 Identify source, investigate the causes of complaint and propose remedial measures; Inform IEC and ER; Repeat measurement to confirm finding; Increase monitoring frequency to daily. 	 Check monitoring data submitted by ET; Check Contractor's working method. 	1. Notify Contractor.	 Rectify any unacceptable practice; Amend working methods if appropriate. 			
Action level being exceeded by two or more consecutive sampling	 Identify source; Inform IEC and ER; Advise the ER on the effectiveness of the proposed remedial measures; Repeat measurements to confirm findings; Increase monitoring frequency to daily; Discuss with IEC and Contractor on remedial actions required; If exceedance continues, arrange meeting with IEC and ER; 	 Check monitoring data submitted by ET; Check Contractor's working method; Discuss with ET and Contractor on possible remedial measures; Advise the ET on the effectiveness of the proposed remedial measures; Supervise Implementation of remedial measures. 	 Confirm receipt of notification of exceedance in writing; Notify Contractor; Ensure remedial measures properly implemented. 	 Submit proposals for remedial actions to IEC within three working days of notification; Implement the agreed proposals; Amend proposal if appropriate. 			

EN JENIJE	ACTION						
EVENT	ET	IEC	ER	CONTRACTOR			
	8. If exceedance stops, cease additional monitoring.						
Limit level being exceeded by one sampling	 Identify source, investigate the causes of exceedance and propose remedial measures; Inform Contractor ,IEC, ER, and EPD; Repeat measurement to confirm finding; Increase monitoring frequency to daily; Assess effectiveness of Contractor's remedial actions and keep IEC, EPD and ER informed of the results. 	 Check monitoring data submitted by ET; Check Contractor's working method; Discuss with ET and Contractor on possible remedial measures; Advise the ER on the effectiveness of the proposed remedial measures; Supervise implementation of remedial measures. 	 Confirm receipt of notification of exceedance in writing; Notify Contractor; Ensure remedial measures properly implemented. 	 Take immediate action to avoid further exceedance; Submit proposals for remedial actions to IEC within three working days of notification; Implement the agreed proposals; Amend proposal if appropriate. 			
Limit level being exceeded by two or more consecutive sampling	 Notify IEC, ER, Contractor and EPD; Identify source; Repeat measurement to confirm findings; Increase monitoring frequency to daily; 	Discuss amongst ER, ET, and Contractor on the potential remedial actions; Review Contractor's remedial actions whenever necessary to assure their effectiveness and advise the ER accordingly;	 Confirm receipt of notification of exceedance in writing; Notify Contractor; In consolidation with the IEC, agree with the Contractor on the remedial measures to be implemented; 	 Take immediate action to avoid further exceedance; Submit proposals for remedial actions to IEC within three working days of notification; Implement the agreed proposals; 			

IDAZIENIZE	ACTION							
EVENT		ET		IEC		ER	CC	ONTRACTOR
	5.	Carry out analysis of	3.	Supervise the implementation of	4.	Ensure remedial measures	4.	Resubmit proposals if problem
		Contractor's working procedures		remedial measures.		properly implemented;		still not under control;
		to determine possible mitigation			5.	If exceedance continues, consider	5.	Stop the relevant portion of works
		to be implemented;				what portion of the work is		as determined by the ER until the
	6.	Arrange meeting with IEC and				responsible and instruct the		exceedance is abated.
		ER to discuss the remedial actions				Contractor to stop that portion of		
		to be taken;				work until the exceedance is		
	7.	Assess effectiveness of				abated.		
		Contractor's remedial actions and						
		keep IEC, EPD and ER informed						
		of the results;						
	8.	If exceedance stops, cease						
		additional monitoring.						

Event and Action Plan for Construction Noise

EVENT	ACTION							
	ET	IEC	ER	CONTRACTOR				
Action Level	Notify IEC and Contractor;	Review the analysed results submitted by the	Confirm receipt of notification of failure in	Submit noise mitigation proposals to IEC;				
	2. Carry out investigation;	ET;	writing;	Implement noise mitigation proposals.				
	3. Report the results of investigation to the IEC,	2. Review the proposed remedial measures by the	2. Notify Contractor;					
	ER and Contractor;	Contractor and advise the ER accordingly;	3. Require Contractor to propose remedial					
	4. Discuss with the Contractor and formulate	3. Supervise the implementation of remedial	measures for the analysed noise problem;					
	remedial measures;	measures.	Ensure remedial measures are properly					
	5. Increase monitoring frequency to check		implemented.					
	mitigation effectiveness.							
Limit Level	1. Identify source;	1. Discuss amongst ER, ET, and Contractor on the	Confirm receipt of notification of failure in	Take immediate action to avoid further				
	2. Inform IEC, ER, EPD and Contractor;	potential remedial actions;	writing;	exceedance;				
	3. Repeat measurements to confirm findings;	2. Review Contractors remedial actions whenever	2. Notify Contractor;	2. Submit proposals for remedial actions				
	4. Increase monitoring frequency;	necessary to assure their effectiveness and advise	Require Contractor to propose remedial	to IEC within 3 working days of notification;				
	5. Carry out analysis of Contractor's working	the ER accordingly;	measures for the analysed noise problem;	Implement the agreed proposals;				
	procedures to determine possible mitigation to be	3. Supervise the implementation of remedial	Ensure remedial measures properly	Resubmit proposals if problem still not under				
	implemented;	measures.	implemented;	control;				
	6. Inform IEC, ER and EPD the causes and actions		5. If exceedance continues, consider what portion	5. Stop the relevant portion of works as determined				
	taken for the exceedances;		of the work is responsible and instruct the	by the ER until the exceedance is abated.				
	7. Assess effectiveness of Contractor's remedial		Contractor to stop that portion of work until the					
	actions and keep IEC, EPD and ER informed of		exceedance is abated.					
	the results;							
	8. If exceedance stops, cease additional							
	monitoring.							

Limit Levels and Action Plan for Landfill Gas

Parameter	Limit Level	Action
	<19%	• Ventilate to restore oxygen to >19%
Ovygon		• Stop works
Oxygen	<18%	• Evacuate personnel/prohibit entry
		• Increase ventilation to restore oxygen to >19%
	>10% LEL (i.e. > 0.5% by volume)	• Prohibit hot works
	>10% LEL (i.e. > 0.3% by volume)	• Ventilate to restore methane to <10% LEL
Methane		• Stop works
	>20% LEL (i.e. > 1% by volume)	• Evacuate personnel / prohibit entry
		• Increase ventilation to restore methane to <10% LEL
	>0.5%	• Ventilate to restore carbon dioxide to < 0.5%
Carbon		• Stop works
Dioxide	>1.5%	• Evacuate personnel / prohibit entry
		• Increase ventilation to restore carbon dioxide to <0.5%

APPENDIX M SUMMARIES OF ENVIRONMENTAL COMPLAINT, WARNING, SUMMON AND NOTIFICATION OF SUCCESSFUL PROSECUTION

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Reporting Month: August 2025

Table M1 Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution Received in the Reporting Period

Log Ref.	Location	Received Date	Details of Complaint/warning/sum mon and prosecution	Nature	Investigation/Mitigation Action	Status

Remarks: No environmental complaint was received in the reporting period, no warning/ summon and prosecution were received in the reporting period.

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Table M2 Cumulative Log for Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
Complaint #N02	Portion T1	10-Oct- 2020	Resident of Yau Lai Estate complained that i) an excavator operated before 7 am on 9 and 10 October 2020; and, ii) the height of noise barriers is not sufficient for noise reduction.	Noise	 Contractor was recommended to scheduled noisy works to less sensitive hours (e.g. normal weekdays between 08:00-19:00) to minimize noise nuisance. Since the complaint location stated in part II is situated out of the project boundary and within the other construction site, no investigation shall be conducted for non-project related complaint. 	Closed
Complaint #N04	Portion T1	9-Feb- 2021 6 March 2021	Resident of Cha Kwo Ling village revealed that some breaking noise was heard at his/her residence (near Cha Kwo Ling Main Street) from the ground at about 20:00 on 08 Feb, 2021 The complainant informed that they continue to hear breaking noise during 3-4 a.m. and caused	Noise	• The construction activities of Trunk Road T2 conducted inside the tunnel area and the construction activities of TKO-LT Tunnel conducted inside the tunnel section at Kwun Tong Side on the evening time and night-time of the date of complaint are considered as one of the potential noise sources of the ground	Closed
		serious noise nuisance to the residents.			 borne noise nuisance. A valid CNP was hold and the construction activities being taken 	

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Keporung I	vionin. Aug	5usi 2023				
Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					 were complied with the relevant CNP. Blast door was fully enclosed when construction activities were carried out within tunnel area to prevent, reduce or minimize the emission of airborne noise In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the requirements in the relevant CNP. According to the condition 3.d point 5 of the CNP (GW-RE0071-21), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received. 	

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
		18 July 2021	Complainant informed that breaking noise was heard at his/her residence (near Cha Kwo Ling Main Road) from the ground during 3-4 a.m. on 17 Jul and 18 Jul 2021.		The construction activities of Trunk Road T2 conducted inside the tunnel area and the construction activities of TKO-LT Tunnel conducted inside the tunnel section at Kwun Tong Side on the evening time and night-time of the date of complaint are considered as one of the potential noise sources of the ground	
Complaint #N05	Portion T1	27 July 2021	Complainant further informed that they continued to hear underground breaking noise during 3-5 a.m. on 27 July 2021.	Noise	 A valid CNP was hold and the construction activities being taken were complied with the relevant CNP. Blast door was fully enclosed when construction activities were carried out within tunnel area to prevent, reduce or minimize the emission of airborne noise In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Keporting	vionth: Aug	gust 2023				
Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					requirements in the relevant CNP. • According to the condition 3.d point 5 of the CNP (GW-RE0399-21), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received. • No major construction noise related	
Complaint #N06	Portion T1	03-Nov- 2021	Complainant informed that underground breaking noise was heard at his/her residence (near Cha Kwo Ling Main Road) at about 10 p.m. on 03 Nov 2021. Also, the complainant further informed that recently they continued to hear underground breaking noise which had caused serious noise nuisance to the residents.	Noise	 No major construction noise related environmental deficiency was identified during ad-hoc inspection carried out by ET, RE and the Contractor representative on 12 November 2021. The construction activities of Trunk Road T2 conducted inside the tunnel area and the construction activities of TKO-LT Tunnel conducted inside the tunnel section at Kwun Tong Side on the evening time and night-time of the date of complaint are considered as one of the potential noise sources of the ground borne noise nuisance. A valid CNP was hold and the 	Closed
Complaint #N06	Portion T1	25-Nov- 2021	Follow up complaint from the same complainant which informed that there was still	Noise	investigation is still undertaken in order to investigate the construction	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
			ground bound noise nuisance after 10 p.m occasionally. The complainant further requested if the relevant works that may contribute to ground bound noise nuisance could be stopped after 10 p.m.		 activities being taken were complied with the relevant CNP. Blast door was fully enclosed when construction activities were carried out within tunnel area to prevent, reduce or minimize the emission of airborne noise In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the requirements in the relevant CNP. According to the condition 3.d point 5 of the CNP (GW-RE1035-21), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received. 	

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
Complaint	Portion	17-Feb-22	Complainant informed that noise from drilling activities near Tin Hau Temple was perceived all day.		 The construction activities of Trunk Road T2 conducted inside the tunnel area and the construction activities of TKO-LT Tunnel conducted inside the tunnel section at Kwun Tong Side are considered as one of the potential noise sources of the ground borne noise nuisance. A valid CNP was hold and the construction activities being taken 	Closed
#N07	T1	24-March- 22	Follow up complaint from the same complainant was received and he/she informed that the day time ground-borne noise nuisance had deteriorated this week.	Noise	 were complied with the relevant CNP. Blast door was fully enclosed when construction activities were carried out within tunnel area to prevent, reduce or minimize the emission of airborne noise In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
		12-April- 22	3 rd complaint from the same complainant was received again, he/ she complained that his/ her family were affected by the noise from construction site of T2 at the night-time period and felt no improvement on these issues.		 regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the requirements in the relevant CNP and the approved CNMP. According to the condition 3.d point 5 of the CNP (GW-RE1201-21, GW-RE0199-22), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received. 	
Complaint #N08	Portion T1	19-Oct-22	Complainant informed that the ground borne noise was heard at his/her residence (near Cha Kwo Ling Main Road) everyday, including the public holiday. Also, the complainant further informed that recently they continued to hear ground borne noise which had caused serious noise nuisance to the residents	Noise	 A valid CNP was hold and construction activities being taken were complied with the relevant CNP Blast door was fully enclosed when construction activities were carried out within tunnel area to prevent, reduce or minimize the emission of airborne noise In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

reporting 1	vionth: Aug	zusi 2023				
Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					 Contractor is recommended to continue to strictly follow the requirements in the relevant CNP and the approved CNMP. According to the condition 3.d point 5 of the CNP (GW-RE0997-22), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received 	
Complaint #N09	Portion T1	28-Oct-22	Complainant informed that the underground breaking noise was heard at her residence (near Cha Kwo Ling Main Road) after the blasting work every day.	Noise	 A valid CNP was hold and construction activities being taken were complied with the relevant CNP Blast door was fully enclosed when construction activities were carried out within tunnel area to prevent, reduce or minimize the emission of airborne noise In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. Contractor is recommended to 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

1 cporting	vionth: Aug	5431 2023				
Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					continue to strictly follow the requirements in the relevant CNP and the approved CNMP. • According to the condition 3.d point 5 of the CNP (GW-RE0997-22), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received	
Complaint #N11	Portion T1 & Portion V	11th August 2023	Complainant informed that there was a noise nuisance from construction work between 8 am and 7 pm, causing an impact on the residents	Noise	 A valid CNP was hold and construction activities being taken were complied with the relevant CNP The contractor has taken steps to address noise concerns by implementing noise control measures such as erecting noise barriers and using a hydraulic breaker equipped with a noise muffler. In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Keporting	Month: Aug	zusi 2023				
Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the requirements in the relevant CNP and the approved CNMP. According to the condition 3.d point 5 of the CNP (GW-RE0603-23), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received	
		23rd August 2023	The complainant informed that there were vibrations caused by the works in CKL Tunnel on 21 August 2023. They stated that their units are temporary housing with certain risks involved and requested an explanation for the project as well as appropriate actions to be taken		 A valid CNP was hold and construction activities being taken were complied with the relevant CNP The contractor has taken steps to address noise concerns by implementing noise control measures such as erecting noise barriers and using a hydraulic breaker equipped with a noise muffler. In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					 less sensitive hours and provide regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the requirements in the relevant CNP and the approved CNMP. According to the condition 3.d point 5 of the CNP (GW-RE0603-23), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received 	
		6th September 2023	EPD received a complaint from a resident of Cha Kwo Ling Village regarding vibrations caused by the construction works of the T2 project on 5 September 2023. The complainant stated that these vibrations are affecting House No. 78 in the village.	Noise	 A valid CNP was hold and construction activities being taken were complied with the relevant CNP The weekly noise monitoring and additional noise assessments have verified that the noise levels remain within the set limits. Moreover, the ground borne noise measurements data suggests that the noise levels are well within the criteria outlined in the TM. 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature Investigation/Mitigation Action		Status
					 The contractor has taken steps to address noise concerns by implementing noise control measures such as erecting noise barriers and using a hydraulic breaker equipped with a noise muffler. In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. Contractor is recommended to continue to strictly follow the requirements in the relevant CNP and the approved CNMP. According to the condition 3.d point 5 of the CNP (GW-RE0973-23), the immediate remedial action shall be implemented in case adverse ground-borne noise impact on any noise sensitive receiver is received 	

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
Complaint #N14	Portion T1	11th September 2024	The complainant stated that noise nuisance was alleviated before but the noise recurred again which had affected her health.	Noise	 No violation of the NMP was recorded as the numbers and types of PMEs operated during the period of complaint comply with the latest NMP. The weekly noise monitoring and additional noise assessments have verified that the noise levels remain within the set limits. Moreover, the ground borne noise measurements data suggests that the noise levels are well within the criteria outlined in the TM. The contractor has taken steps to address noise concerns by implementing noise control measures such as covering all the noisy operating PME/equipment with silencer and noise enclosure. In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. The Contractor is recommended to strictly follow the conditions and requirements of the valid NMP and ensure the construction 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					activities being taken were complied with the relevant NMP.	
Complaint #L01	Portion Q1	03rd October 2024	EPD received complaint referred by CE office against the light nuisance and Dark Smoke from the barges berthed near Laguna City, Lam Tin. EPD's inspection on 17 Oct 2024 noticed some barges anchored outside the seafront of T2 construction site with their floodlights turned on. And this may be the source of the light nuisance complaint.	Light and Air	 The night work operation is under valid permit, lighting at Portion Q1 area including all PME was turned off before 11pm. Micro-Ringelmann Chart produced by the Marine Department was used to check the emission from the barge and no dark smoke is emitted when the barge is operating. There was no direct evidence that any dark smoke was emitted while the barge is operating. In addition, the Contractor should still maintain good site practices, such as turn 	Closed

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
					 off unnecessary lighting and adjust the angle of lighting to reduce light nuisance to public. The Contractor is recommended to conduct regular maintenance for all Powered Mechanical Equipment to prevent dark smoke emission. 	

Appendix M – Summary of Environmental Complaint, Warning, Summon and Notification of Successful Prosecution

Log Ref.	Location	Received Date	Details of Complaint/warning/summon and prosecution	Nature	Investigation/Mitigation Action	Status
Complaint #N14	Portion T1, Q	19 January 2025	Kwun Tong District Council Secretariat received a complaint from a resident of Yau Tong Estate regarding noise nuisance caused by the construction works at Yau Tong area on 19 January 2025. The complainant stated that noise nuisance was occurred during daytime on Sunday.	Noise	 No construction activities were conducted in the complaint period (public holiday). The location of the complainant (Yau Tong Estate) is located approximately 720 meters away from Portion T1/Q. The weekly noise monitoring has verified that the noise levels remain within the set limits. The contractor has taken steps to address noise concerns by implementing noise control measures such as conducting regular noise monitoring. In addition, the Contractor should still maintain good site practices, such as schedule noisy work to the less sensitive hours and provide regularly maintenance for PMEs. The Contractor is recommended to strictly follow the conditions and requirements of the valid NMP/CNP and ensure the construction activities being taken were complied with the relevant NMP/CNP. 	Closed

APPENDIX N SUMMARY OF EXCEEDANCE

Appendix N – Summary of Exceedance

Reporting Period: August 2025

(A) Exceedance Report for Air Quality

No Action and no Limit Level exceedance of 24hr TSP monitoring was recorded in this reporting month.

No Action/ Limit Level exceedance of 1hr TSP monitoring was recorded in this reporting month.

(B) Exceedance Report for Construction Noise


No Action Level exceedance was recorded due to the documented complaint in the reporting month.


No Limit Level exceedance for construction noise monitoring was recorded in the reporting month.


(C) Exceedance Report for Landfill Gas


(NIL in the reporting month).


APPENDIX O TENTATIVE CONSTRUCTION PROGRAMME





















Page 8 of 8 Print on 07-Aug-25 & 13:53 Milestones
 Planned Bar
 Actual Bar


ED/2018/04 Trunk Road T2 and Infrastructure Works for Developments at South Apron


Three Months Rolling Programme (Aug25-Oct25)





Date	Revision	Checked	Approved

















Page 7 of 7 Print on 11-Sep-25 & 17:01



ED/2018/04 Trunk Road T2 and Infrastructure Works for Developments at South Apron

Three Months Rolling Programme (Sep25-Nov25)



Date	Revision	Checked	Approved	

TRUNK ROAD T2

TRAFFIC CONTROL SURVEILLANCE SYSTEM AND ASSOCIATED WORKS

THREE MONTH ROLLING PROGRAMME

	TH RULLING PRUGRAMME										
Activity ID	Activity Name	Original Duration	Early Start	Early Finish	Late Start	Late Finish	Actual Start	Actual Finish	Predecessor Details	Aug	2025 Sep Oct Nov
										44	45 46 47
	raffic Control & Surveillance System & Associated Works	840	01-Sep-25	03-Jul-26		31-Oct-26	29-Aug-23				
Access Dates		75	01-Sep-25	15-Nov-25	02-Apr-24	07-Aug-25					
AC1010b	Portion 2 - LSCC to CP7 (NCP Side) - WB	0	01-Sep-25		02-Oct-24						<u> </u>
AC1010c	Portion 2 - LSCC to CP7 (Under OHVD) - WB	0	01-Sep-25		15-May-25						<u> </u>
AC1010d	Portion 2 - LSCC to CP7 (VSLS Signage Anchors & Niche Cabinet) - EB & WB	0	01-Sep-25		28-Jan-25						<u> </u>
AC1010f	Portion 2 - LSCC to CP7 (CP Side) - EB	0	01-Sep-25		02-Oct-24						·
AC1010g	Portion 2 - LSCC to CP7 (Under OHVD) - EB	0	01-Sep-25		15-May-25						
AC1010h	Portion 2 - LSCC to CP7 (NCP Side) - EB	0	01-Sep-25		02-Oct-24						
AC1030	Portion 4 - TKO-LTT (LT Interchange)	0	01-Sep-25		02-Apr-24						
AC1040	Underpass S21	0	01 Sep 25 01-Sep-25		16-Jan-25						
AC1040 AC1050i	Portion 2 - LS - CKL Tunnel CP7 to CP11 (Niche cabinet) - EB	0	01-Sep-25		15-Feb-25						[
		_	· ·								<u></u>
AC1050j	Portion 2 - LS - CKL Tunnel CP7 to CP11 (Niche cabinet) - WB	0	01-Sep-25		31-Jan-25						
AC1060i	Portion 2 - LS - CKL Tunnel CP11 to CP16 (Niche Cabinet) - EB & WB	0	01-Sep-25		15-May-25						
AC1070i	Portion 2 - LS - CKL Tunnel CP16 to CP21 (Niche Cabinet) - EB & WB	0	01-Sep-25		07-Aug-25						
AC1080b	Portion 2 - LS - CKL Tunnel CP24 to CP26 (Service Gallery) - EB	0	01-Sep-25		13-Feb-25						
AC1080f	Portion 2 - LS - CKL Tunnel CP24 to CP26 (Road Level) - WB	0	01-Sep-25		04-Sep-24						
AC1080i	Portion 2 - LS - CKL Tunnel CP21 to CP24 (Niche Cabinet) - WB	0	01-Sep-25		14-Feb-25						
AC1090c	Portion 2 - LS - CKL Tunnel CP26 to CP30 (Road Level) - WB	0	01-Sep-25		27-Aug-24						
AC1090d	Portion 2 - LS - CKL Tunnel CP26 to CP30 (Service Gallery) - WB	0	01-Sep-25		19-Dec-24						····
AC1000	D. U. 2. LG. CHI M.: T. and CD20 to CD22 (Date Line II). ED	0	01.025		02.624						
AC1090e	Portion 2 - LS - CKL Main Tunnel CP29 to CP32 (Road Level) - EB	0	01-Sep-25		02-Sep-24						
AC1090f	Portion 2 - LS - CKL Main Tunnel CP29 to CP32 (Service Gallery) - EB	0	01-Sep-25		21-Jan-25						
AC1090g	Portion 2 - LS - CKL Main Tunnel CP30 to CP32 (Road Level) - WB	0	01-Sep-25		17-Sep-24						<u> </u>
AC1090h	Portion 2 - LS - CKL Main Tunnel CP30 to CP32 (Service Gallery) - WB	0	01-Sep-25		21-Jan-25						
AC1080a	Portion 2 - LS - CKL Tunnel CP21 to CP26 (Road Level) - EB	0	15-Sep-25		29-Jul-24						*
AC1090a	Portion 2 - LS - CKL Tunnel CP26 to CP29 (Road Level) - EB	0	15-Sep-25		07-Sep-24					<u> </u>	•
AC1120a	Portion 2 - LS - CKL Final Connection (Service Gallery) - WB	0	15-Sep-25		01-Mar-25						*
AC1120	Portion 2 - LS - CKL Final Connection (Road Level) - WB	0	30-Sep-25		25-Sep-24						*
AC1090b	Portion 2 - LS - CKL Tunnel CP26 to CP29 (Service Gallery) - EB	0	15-Oct-25		17-Jan-25						*
AC1110	Portion 2 - LS - CKL Final Connection (Service Gallery) - EB	0	15-Nov-25		01-Mar-25					·····	•
Milestones of Co		0		01-Sep-25		27-Mar-25					·····
KD1050	Commencement of Project-wide FSD Inspection - Contract T2	0	01-Sep-25 01-Sep-25	01 3CP 23	27-Mar-25	27 Hur 23					!
			_								
Summary by Cos		553	01-Sep-25	03-Jul-26	-	21-May-25	-				
Cost Center B -	-	108	01-Sep-25		16-Aug-24		22-Jul-25				
SC1090	SAT Plan Submission & Approval for Central System	78	01-Sep-25	30-Oct-25	11-Apr-25	11-Apr-25	22-Jul-25		DS3500: SS		
SC1080	Site Installation of Central System	95	16-Sep-25	09-Jan-26	16-Aug-24	22-Jan-25			SW1100: SS, SW1120: SS, SW1960: SS, SW1090: SS, SW1670: SS,		
Coot Conton C	Traffic Control Davisco	460	01 0 25	15 000 26	22 C 24	11 4 25	22 C 24		SW1770: SS		
Cost Center C -	Traffic Control Devices	468	01-Sep-25	15-Apr-26	23-Sep-24	11-Apr-25	23-Sep-24				




Remaining Work

Critical Activity


Actual Work

Date	Revision	Checked	Approved
31-Aug-25	Rev. 0	MY	



GTECH Services (Hong Kong) Limited

Critical Activity Actual Work



Early Start

Early Finish


Late Start

Late Finish

Actual Finish

Predecessor Details

Activity Name




Early Start

Early Finish

Late Start

Activity Name


Predecessor Details



Remaining Work • Critical Activity Actual Work

Milestone


31-Aug-25 Rev. 0 MY






Critical Activity Actual Work

MY 31-Aug-25 Rev. 0








Remaining Work

Critical Activity

Actual Work

Date	Revision	Checked	Approved
31-Aug-25	Rev. 0	MY	



Date	Revision	Checked	Approved
1-Aug-25	Rev. 0	MY	

ivity ID	Activity Name	Original Duration	Early Start	Early Finish	Late Start	Late Finish	Actual Start	Actual Finish	Predecessor Details		1	2	025		
,											Aug 44	Sep	Oct		Nov
CM/2720-	Tradell Calaba Carda's area (MCD Cide)	1.4	02.04.25	10.0 1.25	25.024	12.0.1.24			CM2720 FC		44	45	46		47
	Install Cable Containment (NCP Side)	14	02-Oct-25	18-Oct-25	25-Sep-24				SW2720: FS						
SW2730	Install VSLS (CP Side)	8	02-Oct-25	11-Oct-25	05-Feb-25	13-Feb-25			SW2720: FS, SC1210: FS, EM1650: FS, DS82						
SW2750	Install Traffic Control Devices	11	02-Oct-25	15-Oct-25	25-Oct-24	06-Nov-24			SW2720: FS, SC1210: FS, EM1650: FS, DS82						
SW2760	Install CCTV Camera	11	02-Oct-25	15-0ct-25	25-Oct-24	06-Nov-24			SC1470: FF, DS4090: I FS, SW2720: FS	FS, DS6440:					
SW2810	Install Detection Camera	11	02-Oct-25	15-Oct-25	25-Oct-24	06-Nov-24			SC2120: FF, DS4490: I FS, DS7500: FS, SW27	•					
SW2830	Install SEC Camera	11	02-Oct-25	15-Oct-25	11-Mar-25	22-Mar-25			SC2390: FF, EM1130: I FS, DS7410: FS, SW27						
SW2840	Install PVMS	8	02-Oct-25	11-0ct-25	14-Feb-25	22-Feb-25			SC1210: FF, EM1030: I FS, EM1650: FS, DS82 SW2720: FS						
SW2740	Install PA in Service Gallery	12	15-Oct-25	28-Oct-25	17-Jan-25	03-Feb-25			SC1860: FF, DS4240: I FS, DS6120: FS, AC10	•					
SW2820a	Install ET (Service Gallery)	8	15-Oct-25	23-0ct-25	14-Feb-25	22-Feb-25			AC1090b: SS		1				
SW2790	Signal Cable Laying and Termination (CP26 to CP29) (CP Side)	8	16-Oct-25	24-Oct-25	07-Nov-24				SW2720: FS, SC2480: FS, SW2810: FS, SW27				_	_	
SW2730a	Install VSLS (NCP Side)	8	20-Oct-25	28-Oct-25	14-Feb-25	22-Feb-25			SW2720a: FS, SW2730): FS	1]		
SW2820	Install ET (Road Level)	8	20-Oct-25	28-Oct-25	14-Feb-25	22-Feb-25			SC1720: FF, DS4190: I FS, DS6480: FS, SW27				· · · · · · · · · · · · · · · · · · ·		
SW2770	Install PABX in Service Gallery	14	25-Oct-25	11-Nov-25	28-Jan-25	15-Feb-25			SW2740: SS 9, SC159 DS4140: FS, DS6040: FS, AC1090b: SS						•
SW2780	Install GOFS (CP26 to CP29)	8	25-Oct-25	04-Nov-25	08-Mar-25	17-Mar-25			SC2570: FF, DS8560: I FS, SW2790: FS	FS, SW2720a:					
SW2790a	Signal Cable Laying and Termination (CP26 to CP29) (NCP Side)	8	25-Oct-25	04-Nov-25	16-Nov-24	25-Nov-24			SW2720a: FS, SW2790): FS					
SW2850	Laying of Leaky Cable	8	25-Oct-25	04-Nov-25	14-Feb-25	22-Feb-25			SW2720a: FS, SW2790): FS					
SW2800	Install Radio System in Service Gallery	14	13-Nov-25	28-Nov-25	07-Feb-25	22-Feb-25			SW2770: SS 6, SC199 DS4390: FS, DS6160: FS, AC1090b: SS						
East Bound -	Tunnel Section - CP29 to CP32 (CKL Main Tunnel)	38	01-Sep-25	16-Oct-25	12-Sep-24	22-Mar-25									
SW2740a	Install PA in Service Gallery	10		11-Sep-25					SC1860: FF, DS4240: I FS, DS6120: FS, AC10						
SW2820c	Install ET (Service Gallery)	6	01-Sep-25	06-Sep-25	17-Feb-25	22-Feb-25			AC1090f: SS						
SW2720b	Install Cable Containment (CP Side)	12	06-Sep-25	19-Sep-25	12-Sep-24	26-Sep-24			SC2480: FF, SW2950: FS, DS6540: FS, AC10						
SW2770a	Install PABX in Service Gallery	11	11-Sep-25	23-Sep-25	04-Feb-25	15-Feb-25			SW2740a: SS 9, SC159 DS4140: FS, DS6040: FS, AC1090f: SS						
SW2800a	Install Radio System in Service Gallery	11	18-Sep-25	30-Sep-25	11-Feb-25	22-Feb-25			SW2770a: SS 6, SC199 DS4390: FS, DS6520: SS						
SW2720c	Install Cable Containment (NCP Side)	12	20-Sep-25	04-Oct-25	27-Sep-24	12-Oct-24			SW2720b: FS		1-1		-		
	Install VSLS (CP Side)	7		27-Sep-25	-				SW2720b: FS, SC1210 FS, EM1650: FS, DS82		:				
SW2750a	Install Traffic Control Devices	9	20-Sep-25	30-Sep-25	01-Nov-24	11-Nov-24			SW2720b: FS, SC1210 FS, EM1650: FS, DS82						
	!				1	I							 		
	Remainir	ng Work 🔷	Milestone							Date	Revision		ecked	Appro	ved
	Critical A	ctivity								31-Aug-25	Rev. 0	MY			




Critical Activity Actual Work

Date	Revision	Checked	Approved
31-Aug-25	Rev. 0	MY	

Activity	ID	Activity Name	Original Duration	Early Start	Early Finish	Late Start	Late Finish Actual Start	Actual Finish	Predecessor Details	i	20	125	
,										Aug 44	Sep 45	Oct 46	Nov 47
	SW2760a	Install CCTV Camera	9	20-Sep-25	20 Can 2E	01-Nov-24	11-Nov-24		SC1470: FF, DS4090: FS, DS6440:	44	45	46	4/
	5W270Ua	ITISCALI CCTV CATTIETA	9	20-Sep-25	30-Sep-25	01-N0V-24	11-NOV-24		FS, SW2720b: FS			1	
	SW2810a	Install Detection Camera	6	20-Sep-25	26-Son-25	05-Nov-24	11-Nov-24		SC2120: FF, DS4490: FS, DS6440:			1	
	3W2010a	Install Detection Carriera	O	20-3ep-23	20-3ep-23	03-1100-24	11-1100-24		FS, DS7500: FS, SW2720b: FS		_	1	
									13, 03/300.13, 3₩2/200.13			1	
	SW2830a	Install SEC Camera	9	20-Sep-25	30-Sep-25	13-Mar-25	22-Mar-25		SC2390: FF, EM1130: FS, DS7410:				
	3W2030a	ITISCALI SEC CAITIELA	9	20-3ep-23	30-3ep-23	13-1401-23	22-14ldi -23		FS, SW2720b: FS			1	
	SW2840a	Install PVMS	6	20-Sep-25	26-Sep-25	17-Feb-25	22-Feb-25		SC1210: FF, EM1030: FS, DS2810:			 	
	3W204Ua	TISCALI PVIVIS	O	20-3ep-23	20-3ep-23	17-160-23	22-Feb-23		FS, EM1650: FS, DS8250: FS,		_	1	
									SW2720b: FS			1	
	SW2700h	Signal Cable Laying and Termination (CP29 to CP32) (CP Side)	6	02-Oct-25	09-Oct-25	12-Nov-24	18-Nov-24		SW2720b: FS, SC2480: FF,				
	30027900	Signal Cable Laying and Termination (CF29 to CF32) (CF Side)	0	02-001-23	09-001-23	12-1100-24	10-1107-24		SW2760a: FS, SW2810a: FS,			<u> </u>	
									SW2750a: FS			1	
	SW2730c	Install VSLS (NCP Side)	7	06-Oct-25	14-0ct-25	15-Feb-25	22-Feb-25		SW2720c: FS, SW2730b: FS				
		Install ET (Road Level)	9	06-Oct-25	16-Oct-25	13-Feb-25	22-Feb-25		SC1720: FF, DS4190: FS, DS6080:			1	
	30020200	Ilistali ET (Rodu Level)	9	00-001-23	10-001-25	13-160-23	22-1 60-23		FS, DS6480: FS, SW2720c: FS			—	
									13, 530400.13, 3W2720c.13			1	
	SW2780a	Install GOFS (CP29 to CP32)	6	10-Oct-25	16-Oct-25	11-Mar-25	17-Mar-25		SC2570: FF, DS8560: FS, SW2720c:				
	3W2700a	mistali dol 3 (ci 23 to ci 32)		10 000 25	10 00 25	11 1101 25	17 1101 25		FS, SW2790b: FS			_	
	SW2790c	Signal Cable Laying and Termination (CP29 to CP32) (NCP Side)	6	10-Oct-25	16-Oct-25	19-Nov-24	25-Nov-24		SW2720c: FS, SW2790b: FS				
	3002/300	Signal Cable Laying and ICITIIIIation (Cr25 to Cr32) (NCr 31de)		10 000-23	10 0023	17 1104-24	23 INOV 27		5442720C. 13, 34427300. 13				
	SW2850a	Laying of Leaky Cable	6	10-Oct-25	16 Oct 25	17-Feb-25	22-Feb-25		SW2720c: FS, SW2790b: FS			ł	
l II		Laying of Leaky Cable	-						SW2/20C: FS, SW2/900: FS				
Ш	West Bound	Tunnel Section - CP26 to CP30	54			27-Aug-24							
			54			27-Aug-24			AC1000 - CC				
	SW3760	Install Cable Containment (CP Side)	19	01-Sep-25	•	27-Aug-24	·		AC1090c: SS				
	SW3800	Install PA in Service Gallery	16	01-Sep-25	18-Sep-25		08-Jan-25		AC1090d: SS	ļ		1	
	SW3820a	Install ET (Service Gallery)	10	01-Sep-25	11-Sep-25	12-Feb-25	22-Feb-25		AC1090d: SS	l		1	
	SW3810	Install PABX in Service Gallery	18	19-Sep-25	11-Oct-25	09-Jan-25	01-Feb-25		AC1090d: SS, SW3800: FS				
ш	SW3760a	Install Cable Containment (NCP Side)	19	23-Sep-25	16-0ct-25	19-Sep-24	12-Oct-24		SW3760: FS				
	SW3770	Install CCTV Camera	15	23-Sep-25	11-Oct-25	16-Oct-24	01-Nov-24		SW3760: FS				
	SW3780	Install Detection Camera	15	23-Sep-25	11-Oct-25	16-0ct-24	01-Nov-24		SW3760: FS				
	SW3790	Install VSLS (CP Side)	11	23-Sep-25	06-Oct-25	25-Jan-25	10-Feb-25		SW3760: FS				
		. ,		23-Sep-25 23-Sep-25		12-Feb-25				ļ		<u>=</u>	
	SW3820	Install ET (Road Level)	10		04-Oct-25		22-Feb-25		SW3760: FS			<u></u>	
	SW3830	Install Traffic Control Devices	15	·		16-0ct-24			SW3760: FS, SW3760: FF				
	SW3850	Install SEC Camera	15	·	11-Oct-25	06-Mar-25			SW3760: FS				
	SW3880	Install PVMS	10	23-Sep-25	04-Oct-25	12-Feb-25	22-Feb-25		SW3760: FS			_	
	SW3790a	Install VSLS (NCP Side)	11	08-Oct-25	20-Oct-25	11-Feb-25	22-Feb-25		SW3790: FS	ノ			
	SW3840	Install Radio System in Service Gallery	18	13-Oct-25	03-Nov-25	03-Feb-25	22-Feb-25		AC1090d: SS, SW3810: FS				_
	SW3870	Signal Cable Laying and Termination (CP26 to CP30) (CP Side)	10	13-Oct-25	23-Oct-25	02-Nov-24	13-Nov-24		SW3760: FS, SW3770: FS, SW3780:				
									FS, SW3830: FS]		1	
	SW3860	Install GOFS (CP26 to CP30)	10	24-Oct-25	05-Nov-25	06-Mar-25	17-Mar-25		SW3760a: FS, SW3870: FS			_	<u> </u>
	SW3870a	Signal Cable Laying and Termination (CP26 to CP30) (NCP Side)	10	24-Oct-25	05-Nov-25		25-Nov-24		SW3760a: FS, SW3870: FS				
	31130704	Signal cable Eaying and Termination (or 20 to 61 50) (No. 61de)	10	2.00.25	05 1101 25	21110121	25 1167 2 1		31137 6641 1 37 311367 61 1 3			1	
	SW3890	Laying of Leaky Cable	10	24-Oct-25	05-Nov-25	12-Feb-25	22-Feb-25		SW3760a: FS, SW3870: FS	····			
		Tunnel Section - CP30 to CP32 (CKL Main Tunnel)	28	01-Sep-25	03-Oct-25	17-Sep-24	22-Mar-25		31137 000. 137 311307 0. 13	/			
		Install Cable Containment (CP Side)	10			17-Sep-24			AC1090g: SS	/			
		` '		-	-	-					· · · · · · · · · · · · · · · · · · ·	1	
		Install PA in Service Gallery	8	01-Sep-25	09-Sep-25	21-Jan-25	01-Feb-25		AC1000h: SS	 	[-
	SW3820c	Install ET (Service Gallery)	5	01-Sep-25	05-Sep-25	18-Feb-25	22-Feb-25		AC1090h: SS	ļ	<mark> </mark>		
	SW3810a	Install PABX in Service Gallery	9	10-Sep-25	19-Sep-25	03-Feb-25	12-Feb-25		AC1090h: SS, SW3800a: FS		<mark></mark>	 	.
	SW3760c	Install Cable Containment (NCP Side)	10	12-Sep-25	23-Sep-25	30-Sep-24	12-Oct-24		SW3760b: FS	ļ. .		1	.
	SW3770a	Install CCTV Camera	8	12-Sep-25	20-Sep-25	05-Nov-24	13-Nov-24		SW3760b: FS	.		1	<u> </u>
	SW3780a	Install Detection Camera	8	12-Sep-25	20-Sep-25	05-Nov-24	13-Nov-24		SW3760b: FS	T T			
	SW3790b	Install VSLS (CP Side)	6	12-Sep-25	18-Sep-25	10-Feb-25	15-Feb-25		SW3760b: FS	1.1			
	SW3820b	Install ET (Road Level)	5	12-Sep-25	17-Sep-25	18-Feb-25	22-Feb-25		SW3760b: FS	<u> </u>			· †
	SW3830a	Install Traffic Control Devices	8	12-Sep-25	20-Sep-25	05-Nov-24	13-Nov-24		SW3760b: FS, SW3760b: FF	† 			
				· ·	· · · · · · · · · · · · · · · · · · ·				·	 	· · · · · · · · · · · · · · · · · · ·	1	
	SW3850a	Install SEC Camera	8	12-Sep-25	20-Sep-25	14-Mar-25	22-Mar-25		SW3760b: FS	ļ <mark>.</mark>		 	
	SW3880a	Install PVMS	5	12-Sep-25	17-Sep-25	18-Feb-25	22-Feb-25		SW3760b: FS	\sqcup		<u></u>	
		Remaining	g Work •	◆ Milestone					Date	Revis	ion Che	ecked	Approved
		Critical Act	_						31-Aug-25	Rev. 0	MY		
	A AND DESCRIPTION OF THE PERSON OF THE PERSO	Onical Act	·- <i>y</i>										I .

GTECH Services (Hong Kong) Limited

Critical Activity Actual Work





Remaining Work • Critical Activity Actual Work

Date	Revision	Checked	Approved
31-Aug-25	Rev. 0	MY	

Activ	ity ID	Activity Name	Original Duration	Early Start	Early Finish	Late Start	Late Finish	Actual Start	Actual Finish	Predecessor Details		20	025	
	, 15	The transfer of the transfer o									Aug	Sep	Oct	Nov
											44	45	46	47
	SW1800	Install Operation Facilities Equipment	14	05-Nov-25	20-Nov-25		07-Nov-24			SC2680: FF, DS6280: FS, SW1770: SS, EM1120: FS				
	SW1810	Install Radio Equipment	12	13-Nov-25	26-Nov-25	10-Feb-25	22-Feb-25			SC1990: FF, DS4390: FS, DS6160: FS, DS6520: FS, SW1790: FS				
	SW1840	Signal Cable Laying	15	28-Nov-25	15-Dec-25	08-Nov-24	25-Nov-24			SW1770: FS, SW1780: FS, SW1800: FS, SW1820: FS, SW1830: FS, SW1790: FS				
	Site Commissio	ning Test	36	12-Nov-25	23-Dec-25	08-Apr-25	21-May-25							
	TC1290	SCT of PABX System	36	12-Nov-25	23-Dec-25	08-Apr-25	21-May-25			SW2380: FS, SW2440: FS, SW2560: FS, SW2650: FS, SW2770: FS, SC1620: FF, SW3280: FS, SW3350: FS, SW3460: FS, SW3690: FS, SW3550: FS, SW3060: FS, SW3180: FS, SW3810: FS, SW4010: FS, SW4070: FS, SW4110: FS, SW4150: FS, SW4200: FS, SW4250: FS, SW4300: FS, SW2770a: FS, SW3810a: FS, DS8640: FS, SW1790: FS, SW1690: FS				
	Portion 3 - CKL E	Branch Tunnel in TKO-LTT Site	99	01-Sep-25	29-Dec-25	30-Jul-24	22-Feb-25							
Ш	SW1850	Inspect Civil Provisions & Submit Inspection Report	3	01-Sep-25	03-Sep-25	30-Jul-24	01-Aug-24			AC1020: SS	7	–		
	SW1860	Rectify Civil Provision Defects by Others	7	04-Sep-25	11-Sep-25	02-Aug-24	09-Aug-24			SW1850: FS				
	Installation Wor	ks	89	12-Sep-25	29-Dec-25	10-Aug-24	22-Feb-25							
	SW1890	Install Cable Containments	36	12-Sep-25	25-Oct-25	10-Aug-24	21-Sep-24			SC2480: FF, DS6404: FS, DS6540: FS, SW1860: FS	ل			
	SW1910	Laying of Leaky Cable	51	15-Oct-25	13-Dec-25	20-Dec-24	22-Feb-25			SW1890: SS 26				
	SW1920	Signal Cable Laying	51	15-Oct-25	13-Dec-25	10-Sep-24	11-Nov-24			SW1890: SS 26				
	SW1870	Install CCTV Camera	51	30-Oct-25	29-Dec-25	25-Sep-24	25-Nov-24			SC1470: FF, DS4090: FS, DS6440: FS, SW1860: FS, SW1890: FS, SW1920: SS 12			•	
	SW1880	Install Detection Camera	51	30-Oct-25	29-Dec-25	25-Sep-24	25-Nov-24			SC2120: FF, DS4490: FS, DS6440: FS, DS7500: FS, SW1860: FS, SW1890: FS, SW1870: SS				
	SW1900	Install Traffic Control Devices	51	30-Oct-25	29-Dec-25	25-Sep-24	25-Nov-24			SC1210: FF, DS2810: FS, EM1650: FS, DS8250: FS, SW1870: SS, SW1880: SS, SW2220: SS, SW1890: FS				

GTECH Services (Hong Kong) Limited

Remaining Work
Critical Activity
Actual Work

Date	Revision	Checked	Approved
31-Aug-25	Rev. 0	MY	

High Level 3-month Look Ahead Programme

Activities	Jul-25	Aug-25	Sep-25
Lam Tin Interchange			
Site Formation - Area 1G1, 1G2 & 5			
Site Formation - Slope Stabilisation			
Soft Landscape			
Stage 1 & 2 Commissioning Outstanding Works			

NE/2015/01 12/07/2025